

Latest Developments in X-Ray FELS* and Future Perspectives



Winni Decking, DESY, Hamburg, Germany

* X-Ray FEL: $> 100 \text{ eV}$ / $< 10 \text{ nm}$




X-Ray FELs around the world – FLS1996




Credit: Reto Stöckli, NASA Earth Observatory

X-Ray FELs around the world – FLS1999



Credit: Reto Stöckli, NASA Earth Observatory

X-Ray FELs around the world – FLS2002




Credit: Reto Stöckli, NASA Earth Observatory

X-Ray FELs around the world – FLS2006



Credit: Reto Stöckli, NASA Earth Observatory

X-Ray FELs around the world – FLS2010




Credit: Reto Stöckli, NASA Earth Observatory

X-Ray FELs around the world – FLS2012




Credit: Reto Stöckli, NASA Earth Observatory

X-Ray FELs around the world – FLS2018



Credit: Reto Stöckli, NASA Earth Observatory

X-Ray FELs around the world – FLS202?







Credit: Reto Stöckli, NASA Earth Observatory

FLASH, DESY, Hamburg

- 1.2 GeV superconducting pulsed linac
- FLASH1: fixed gap undulator, 90 – 4 nm
- FLASH2: variable gap undulator, 90 – 4 nm
- 7 end-stations



FLASH: the pioneering soft x-ray SASE FEL



FLASH Layout 2017


3rd harmonic sc module 3.9 GHz




TESLA type superconducting accelerating modules 1.3 GHz




FLASH1 fixed gap undulators



FLASH1 Albert Einstein Hall



Bart Faatz
WG-A, Wed 12:00



Normal conducting 1.3 GHz RF gun
Ce₂Te cathode / 3 injector lasers



Extraction to FLASH2

31



FLASH2 variable gap undulators



FLASH2 Kai Siegbahn Hall


Evgeny Schneidmiller
WG-A, Tue 17:00

FERMI, Elettra, Trieste

- 1.45 GeV S-band linac
- FEL1: single stage HGHG, APPLE undulators, 20 nm
- FEL2: 2-stage HGHG, APPLE undulators, 4 nm
- 5 (?) end-stations




FERMI: the pioneering seeding FEL



Giuseppe Penco
WG-A, Thu 11:30

Enrico Allaria
WG-A, Tue 16:00



LCLS, SLAC, Palo Alto

- 14 GeV S-band linac
- XU: fixed gap undulator, 0.28 – 12.8 keV
- 7 end-stations




Accelerator based Dual-Pulse / Dual-Color Modes


- Double Slotted Foil
- Split Undulator
- Injector laser pulse splitting
- Multiple laser pulses at cathode (dual lasers)
- Fresh Slice Technique

Working on 2 .. 16 pulses now
→ Laser pulse splitting techniques

XTCAV image of 4 bunches lasing



Profile Monitor OTRS:DMP1:695 05-Sep-2017 14:25:18





Under Development !!!

LCLS Machine FAQ: https://portal.slac.stanford.edu/sites/lcls_public/machinefaqpix/MultiColorModes-8-22-16.pdf

Progress (and published results!) in sub-femtosecond pulse generation


XLEAP - soft X-ray tests underway



< 0.5 fs pulses with ~50 uJ per pulse

Use space-charge boost for bandwidth-broadening (4-5x larger than previously) for non-linear science applications


HXR: Isolated 200 as pulse produced



Nonlinear compression produces High density head with low density tail

Measurements:

- 179 ± 58 as @ 9 keV (14.4 eV BW)
- 228 ± 85 as @ 5.6 keV (11.3 eV BW)
- 10 uJ x-ray pulse from 20 pC bunch



Huang et al, PRL 119, 154801 (2017)


James MacArthur
WG-A, Tue 14:00

Also:
Slotted foil results (400 as pulse): APL 111, 151101 (2017)
that also enable 2 pulse delivery

LCLS II / LCLS II HE

- 4 (8) GeV superconducting CW linac
- 2 new variable gap undulators (SXU, HXU)
- HXU can also be fed by S-band linac => 25 keV photons on 1st harmonic


Tor Raubenheimer
WG-A, Mo 14:30



LCLS-II Gun and Injector Status

- APEX gun at LBNL has demonstrated LCLS-II beam brightness at 20 pC
- Gun in fab – Delivered to SLAC in Jan. 2018
- Early injector commissioning starts Mar.

Feng Zhou
WG-D, Thu 14:00-14:30




APEX
beam




Gun in fab. at LBNL

Commissioning at 750 keV (9 mo.)



Temp. wall



improved
gun


SACLA, RIKEN/Spring-8, Hyogo

- 8 GeV C-band linac
- 2 in vacuum variable gap undulators, 4-15 keV
- Thermionic gun
- Added 800 MeV accelerator for VUV/soft x-ray (20 – 150 eV)




Recent upgrades and future plans of SACLA

- Parallel user operation of 3 beamlines has been started.
 - BL3 and BL2: Hard X-ray FEL (4-15 keV)
 - BL1: Soft X-ray FEL (20-150 eV)
- 60 Hz beam switching to BL3 and BL2, with arbitrary beam energy (6-8 GeV).
- New dog-leg optics cancels CSR effect and transport 10 kA beams to BL2.
- Ongoing and future upgrade plans
 - Beam injection to SPring-8 (and future SPring-8-II) storage ring in this year.
 - Harmonic lasing at hard-X FEL for shorter wavelength.
 - Reflection-type hard-X self-seeding for monochromatic FEL.
 - Beam energy upgrade of BL1, up to 1.7 GeV, and to obtain shorter wavelength.






Recent upgrade and future plan of SACLA







Relocation of the beam transport to BL2

- In the old dog-leg optics, CSR induced beam distortion limited the peak current.
- New optics was introduced for CSR cancellation,
 - Twin DBA optics with phase advance of π .
 - 1.5 degree, 60 Hz switching magnet with 10 ppm field stability.




Upgrade of Soft X-ray beamline BL1

- Prototype FEL machine “SCSS” was relocated to BL1 for dedicated accelerator.
- Beam energy was increased to 800 MeV.
- Photon energy can be varied 20 - 150 eV.
- **Future plan:**
 - Higher peak current with nonlinear correction of the bunch compression.
 - Beam energy upgrade up to 1.7 GeV



Example of the Operation status

Pulse Energy 736.4 micro J/pulse	Photon Energy / Wavelength 9.4 keV / 0.131 nm
Repetition Rate 30 Hz	Intensity Fluctuation in 30 shots (STD) 7.6 %




BL3 (Hard-X)
9.4 keV
700 μ J/pulse

60 Hz beam switching

BL2 (Hard-X)
7.0 keV
400 μ J/pulse


Pulse Energy 401.2 micro J/pulse	Photon Energy / Wavelength 7.0 keV / 0.177 nm
Repetition Rate 30 Hz	Intensity Fluctuation in 30 shots (STD) 8.0 %



Dedicated accelerator


BL1 (Soft-X)
103 eV
120 μ J/pulse

Pulse Energy 108.9 micro J/pulse	Photon Energy / Wavelength 102.6 eV / 12.1 nm
Repetition Rate 60 Hz	Intensity Fluctuation in 30 shots (STD) 19.3 %



SwissFEL, PSI, Villigen

Soft X-ray FEL, $\lambda=0.65\text{--}5.0\text{ nm}$
 Variable polarization, Apple-X undulators
 First users 2021




Hard X-ray FEL, $\lambda=0.1\text{--}0.7\text{ nm}$
 Linear polarization, variable gap,
 in-vacuum undulators
 First users 2018

Main parameters:

Photon wavelength	0.1–5 nm
Photon energy	0.2–12 keV
Pulse duration	1–20 fs
Electron energy	5.8 GeV
Electron bunch charge	10–200 pC
Repetition rate	100 Hz

SwissFEL Operations 2017

- Beam/systems development
- Photonics
- Shutdown



SwissFEL has reached its 2017 milestone of first pilot experiment.

Electron energy currently limited to 3 GeV, to be raised to the nominal 5.8 GeV by June 2018.

Stable running at 200 μ demonstrated for 2.2 keV photon energy.

Many important commissioning steps have been skipped and will have to be done in 2018!

Regular user operation to start in January 2019.

Shutdowns:

21 Dec – 26 Feb:
 - Installation SARUN03
 - Switchyard installations
 - Various other tasks...

3–11 Apr:
 - Waveguide connections S10CB03/04/05/06

19 Jun – 2 Jul:
 - Installation TDS
 - Upgrade timing system
 - Waveguide connections S10CB02/07/08, S30CB13

2–7 Aug:
 - Waveguide connection S10CB09 S30CB01

4 Sep – 2 Oct:
 - DRPS phase I
 - Switch test
 - PSYS
 - Waveguide connections S20CB01/02/03 S30CB02/03

22 Dec – 31 Jan 2018

Outlook Athos (soft-X-ray line)

Redesigned soft-X-ray undulator line featuring 16 Apple-X U38 undulators:

- full polarization control
- independent K and polarization control
- transverse gradient undulator (TGU)
- symmetric force distribution (gap = slit)

Small interundulator magnetic chicanes to enable


- Optical klystron mode
- High-brightness mode
- Terawatt-attosecond mode

One large magnetic chicane for two-color operation (delay between -10 fs and $+500$ fs)

Schedule:

- Athos dogleg ready for commissioning Feb. 2018
- Undulator installation Jan. 2019 – March 2020
- First pilot experiment end 2020
- User operation 2021.

Eduard Prat
Plenary, Mo 10:00



Athos U38 undulator concept



SwissFEL switchyard, Nov. 2017


PAL-XFEL

0.1 nm hard X-ray FEL using a 10 GeV S-band linac

- Apr. 2011: PAL-XFEL project started
- Jun. 2012: Ground-breaking
- Dec. 2014: Building completed
- Jan. 2016: Installation completed
- Apr. 2016: Commissioning started**
- Jun. 2017: User-service started**




Chang-Ki Min
WG-A, Mo 15:00



- ◆ 14 Jun. 2016 First SASE lasing at 0.5 nm
- ◆ 28 Oct. 2016 Lasing at 0.15 nm
- ◆ 27 Nov. 2016 Saturation of 0.15 nm
- ◆ 16 Mar. 2017 Saturation of 0.1 nm

PAL-XFEL Parameters



Main parameters



e^- Energy	10 GeV
e^- Bunch charge	20-200 pC
Slice emittance	< 0.5 mm mrad
Repetition rate	30 Hz (60 Hz)
Pulse duration	10 fs – 100 fs
Peak current	3 kA
SX line switching	DC (Phase-1) Kicker (Phase-2)

Undulator Line	HX1	SX1
Photon energy [keV]	2.5 ~ 12.8	0.3 ~ 1.2
Beam Energy [GeV]	4 ~ 10	3.15
Wavelength Tuning	energy	gap
Undulator Type	Planar, out-vac.	Planar
Undulator Period / Gap [mm]	26 / 8.3	35 / 9.0


Machine Performances

- ◆ FEL position stability: 8~9% of beam size
- ◆ FEL power stability: ~ 4.0% RMS
- ◆ E-beam energy jitter: < 0.02 %
- ◆ E-beam arrival time jitter: < 20 fs
- ◆ FEL pulse energy: ~1 mJ at 9.7 KeV
- ◆ Saturated FEL up to 15.0 KeV
- ◆ FEL beam availability: > 98%

OXC : Optical laser & XFEL Cross-correlator



Simulation:
emittance: 0.55 mm-mrad
peak current: 2.5 kA



Simulation:
emittance: 0.55 mm-mrad
peak current: 2.2 kA

Plan of Year 2018

- **Self-seeding mode operation for HX-FEL**

- Commissioning will begin in March 2018

- **60 Hz operation**

- A three days' test of 60 Hz operation was successfully done.



- Its full operation is scheduled in March 2018 after the SLED cavity tuning controller is ready to operate.

- **Pulse-by-pulse switching operation for SX-FEL**

- A kicker and a septum will be ready by February 2019

- Commissioning will begin in March 2019

- Monochromator will be installed in February 2018




European XFEL, Hamburg

- International project realised in Hamburg area, Germany
- 17.5 GeV pulsed superconducting linac
- 27000 pulses per second in 10 Hz burst mode
- Three variable gap undulators for hard and soft X-rays
- Initially 6 equipped experiments
- All accelerator and beamlines in tunnels 6 -25 m below surface



Accelerator Overview



Superconducting linac with 97 1.3 GHz superconducting modules


10 Hz pulsed mode with 600 μs flat-top, 2700 bunches/pulse

Variation of bunch charges between 20-1000 pC foreseen to vary final pulse length


Fast distribution of bunches into beam distribution lines

Accelerator complete & in operation

- Accelerator commissioned according to schedule and towards expected parameter
- **23 out of 25 RF** stations commissioned (last two will be ready in Q2/218)
- Maximum beam energy **14.9 GeV**, user operation with **14.0 GeV**
- Routine operation with **300 bunches/second** in user mode
- Test operation in linac mode with **3000 bunches/second** (\approx 18 kW beam power)



Facility performance in user run



- Seven 5 day user blocks from 9/2017 – 11/2017 (just 4 month after 1st lasing)
- 9 keV, 10-300 bunches/second
- Little tuning needed (because of limited flexibility offered), but frequent small wavelength changes and variation of bunch number (1-30)

2018 E-beam Parameters

Quantity		Project Goal	Achieved	Routine	2018 Goal
electron energy	GeV	8,12.5,14,17.5	6-14.9	14	8/12.5/14/17.5 GeV
bunch repetition frequency within pulse	MHz	Up to 4.5	1.1, 4.5	1.1	1.1
bunch charge	pC	20 – 1000	100, 500	250, 500	200, 500
electron bunch length after compression	fs (FWHM)	2 – 180	20, 90	40, 90	40, 90
beam power	kW	500 kW	18 kW	1.8 kW	50 kW
undulators in operation (lasing)		SASE1-3	SASE1,3	SASE1,3	SASE1-3
photon energy (SASE1)	keV	0.25 - 25	1,6,9-14	9-9.5	6-15
photon pulses / s / undulator		27000	3000	300	3000
saturation power (@ 14 GeV, 250 pC, 9 keV)	mJ	1	1.5	0.4	1

Plans for 2018

- SASE1: About 1200h experiment commissioning & 1600 h user operation, improve performance and flexibility
- SASE2: First e-beam in March, first lasing in May
 - Commission laser and photon systems parallel to user runs
 - First user experiments in 2019
 - In the meantime: parasitic studies (harmonic lasing, kicker schemes, photon diagnostics)
 - Installation of Self-Seeding Chicanes (December)
- SASE3:
 - First user experiments end of 2018
 - In the meantime: parasitic studies (harmonic lasing, kicker schemes, photon diagnostics)
- Accelerator:
 - Full energy by summer
 - Full # of bunches after linac by end of 2018

Evgeny Schneidmiller
WG-A, Tue 17:00

Shan Liu
WG-A, Tue 17:30

Existing High-Gain FELs in China

Laboratory Tour
Fri 14:00



SDUV-FEL:
65m, 180MeV, 250-350nm



Under commissioning





DCLS:
150m, 300MeV, 50-150nm

Operating




SXFEL Facility:
300m, 840MeV, 9-40nm
530m, 1.6GeV, 2-10nm

HXFEL, SINAP/ShanghaiTech University, Shanghai



Dong Wang
WG-A, Mo 14:00

Beam Distribution and FEL Systems for Shanghai HXFEL



Main Parameters of Shanghai HXFEL

	Nominal	Range	Unit
Beam energy	8	4-8.6	GeV
Bunch charge	100	10-300	pC
Max Repetition rate	< 1	up to 1	MHz
Electron beam power	0.8	0 - 2.4	MW
Photon energy	0.4-25	0.4-25	keV
Pulse length	20-50	5-200	fs
Peak brightness	5×10^{32}	$1 \times 10^{31} - 1 \times 10^{33}$	Photons/ $\mu\text{m}^2/\text{rad}^2/\text{s}/0.1\% \text{BW}$
Average brightness	5×10^{25}	$1 \times 10^{23} - 1 \times 10^{26}$	Photons/ $\mu\text{m}^2/\text{rad}^2/\text{s}/0.1\% \text{BW}$
Total facility length	3.1	3.1	km
Total tunnel length	5.7	5.7	km
Tunnel diameter	5.9	5.9	m
2K Cryogenic power	12	12	kW
RF Power	2.28	3.6	MW

Summary

- 7 X-ray user facilities in operation in 2018 (from 0 in 2008)
- 2 new facilities are under construction/planned based on superconducting CW linac
- Trends:
 - Parallel beam operation (FLASH, European XFEL, SACLA, PAL, PSI, LCLS) Session WG-A
Thu 11:00-12:30
 - Two pulse operation (LCLS, FERMI, FLASH) Session WG-A
Wed 14:00-18:00
 - Bandwidth control (HGHG, EEHG, self-seeding, harmonic lasing)
 - Shorter pulses
- Challenges
 - Attosecond pulses & timing Franz Kaertner
Plenary, Wed 10:00
 - Control and operability of multi-user/multi-mode machines Session WG-A
Mo 16:00-18:00, Thu 09:00-10:30
 - Source for CW accelerators Feng Zhou
WG-D, Thu 14:00-14:30
 - SC undulators for low energy / high rep-rate machines Joel Fuerst
Plenary, Mo 12:00-12:30
 - Increase the user base

All this is only possible thanks to the excellent team spirit within
the light source community

Team work and collaboration is key (& fun)

Thanks to Thomas Schietinger (PSI), Axel Brachmann (SLAC), Heunk-Sik Kang (PAL) & Hitoshi
Tanaka (SACLA) for providing me with slides

