


COMMISSIONING OF THE LHC WITH BEAM

V. Kain, LHC Operations

On behalf of the LHC Commissioning Team



Outline



LHC nominal parameters

Goals for current run

Commissioning strategy and steps achieved

Performance

Some puzzling effects

The LHC surpasses existing accelerators in two aspects

- o 7 TeV beams in the former LEP tunnel
 - LHC dipole field 8.3 T


A factor 2 in field
A factor 4 in size above
other accelerators

- o Design luminosity: pp $10^{34} \text{ cm}^{-2}\text{s}^{-1}$
 - ❑ Intensity: $3 \times 10^{14} \text{ p}^+$: stored energy 360 MJ
 - ❑ β^* : 0.55 m


A factor 30 in luminosity
above other accelerators

o To cohabitate 360 MJ in superconducting environment:

- ❑ ~ 100 collimators
- ❑ 4000 Beam Loss Monitors
- ❑ Absorbers at critical locations: injection and beam dump
- ❑ 20'000 signals connected to beam abort system







LHC collimator beam




Commissioning in steps...

- o 2008: injection tests, start-up and shutdown



LHC Start-up September 10, 2008

- o 2009: repair, re-start-up



LHC shutdown September 19, 2008

20 th Nov	Day 0	Both beams circulating after 6 hours
23 rd Nov	Day 3	First pilot collisions at 450 GeV
29 th Nov	Day 9	Beams ramped to 1.18 TeV
6 th Dec	Day 16	Stable collisions @ 450 GeV for the experiments
8 th Dec	Day 18	Both beams ramped to 1.18 TeV – first collisions

Our most optimistic plan had come true...

2009		2010			2011		
Repair of Sector 34	1.18 TeV	nQPS 6kA	3.5 TeV $I_{\text{safe}} < I < 0.2 I_{\text{nom}}$ $\beta^* \sim 3.5 \text{ m}$	Ions	3.5 TeV $\sim 0.2 I_{\text{nom}}$ $\beta^* \sim 3.5 \text{ m}$	Ions	
No Beam	B		Beam		Beam		

GOAL for 2010/11 running:

Collect **1 fb^{-1}** of data/experiment at 3.5 TeV/beam

- o → Goal of LHC operation in 2011 : **$L \sim 10^{32} \text{ cm}^{-2}\text{s}^{-1}$** ... Tevatron luminosity
 - ~ 700 bunches with 10^{11} protons/bunch: $\sim 7 \times 10^{13}$ protons/beam
 - Stored energy: **$\sim 30 \text{ MJ}$** (8 % of nominal)
- o → Strict, clean and reproducible machine setup
- o → Machine protection systems at near nominal performance

- o Phase 1: low intensity commissioning of the LHC
 - ❑ Low intensity single bunches. Very limited risk of damage
 - ❑ Machine protection commissioning

- o Phase 2: operation without crossing angle

- ❑ Bunches with large spacing ($> 1 - 2.5 \mu\text{s}$)
- ❑ Up to around $k_b = 50$ bunches per ring
- ❑ Machine protection running in



Until end of August 2010

- o Phase 3: operation with crossing angle

- ❑ Bunches with close spacing ($< 150 \text{ ns}$)
- ❑ Aim for ~ 400 bunches 2010



**Machine protection tests
have finished**

**Currently running with
104 x 104 bunches**


- o Phase 1: low intensity commissioning of the LHC
 - Low intensity single bunches. Very limited risk of damage
 - Machine protection commissioning

- o Phase 2: operation without crossing angle
 - Bunches with large spacing ($> 1 - 2.5 \mu\text{s}$)
 - Up to around kb = 50 bunches per ring
 - Machine protection running in



Until end of August 2010

- o Phase 3: operation with crossing angle
 - Bunch spacing
 - Aim for 104 x 104 bunches



Machine protection tests have finished



Currently running with 104 x 104 bunches

- o Start operation with very **LOW intensity**
 - 100'000th of the nominal intensity
- o **Machine protection “light”**
 - Machine protection is NEVER disabled, but flexibility is built into the system: MASKING with low intensity
- o Before **each** change of configuration/intensity:
 - Measure and correct parameters with low intensity; establish **references**
 - Orbit, beta beating, **aperture**
 - Set up protection devices
 - Collimators, absorbers, interlocked BPMs,...
 - **Qualify protection system**
 - Loss maps: collimation hierarchy
 - Asynchronous dumps
 - Increase intensity
 - Gain experience: 3 fills with about 20 h in physics in total
- o **Continuous monitoring:**
 - Post mortem analysis
 - Automatic post operational checks of beam dump and injection

- o **Restart** with beam **28th of Feb**
- o Commissioning to **3.5 TeV** March
 - Low intensity beams
- o **First collisions at 3.5 TeV** **30th of March**
- o **Squeeze** commissioning Mid April
 - Squeeze from $\beta^* = 10/11$ m to 2 m
- o Increase number of bunches to 13 per beam Mid April – Mid May
 - Bunch population $N = 3 \times 10^{10}$ (30 % of nominal)
- o Switch to **nominal bunch intensity** (10^{11} /bunch) **June**
 - Single bunch instabilities: octupoles on, longitudinal blow-up, transverse damper
 - Luminosity gain factor ~ 10
 - Go to 3.5 m β^* : lose factor 3.5
- o **Increase number of bunches up to 50** per beam **July – August**
 - Bunch population $\sim 9 \times 10^{10}$
 - Luminosity of $10^{31} \text{ cm}^{-2}\text{s}^{-1}$
- o Commissioning of **crossing angle** and 10 A/s ramp **September**
 - Switch to injection of bunch trains (spacing 150 ns)

- o A lot of commissioning still ongoing, but excellent performance of **ALL equipment**
 - ~ 40 % of time in physics → 10^6 collisions per month
 - Minimum turn around time ~ 4 h



- o Another 5 weeks to go with protons: goal ~ 400 bunches by November.



- o Integrated luminosity until yesterday morning:
 - 7 pb⁻¹
- o Maximum availability per week:
 - 85 %

2010/09/27 11.

2010/09/27 11.40




- o Only about **14%** of the beams above injection energy are dumped by the operations crew.
- o Quenches: a local loss of $\sim 10^7$ p/s at 3.5 TeV can lead to quench


□ So far, no quenches at 3.5 TeV

- → excellent performance of collimation system
- → fast reaction of Beam Loss Monitor System

- o Hierarchy of collimators must be preserved at all phases for cleaning and protection
- o Beam cleaning efficiencies **$\geq 99.98\%$** : ~ as expected.



- o Beta and dispersion beating within tolerances throughout all phases
- o ...and **extremely reproducible**





Reproducible optics is essential for increasing intensity, particularly for collimators.


Beta beating measured with AC dipole in tolerance of 20 %.

- o Excellent performance of LHC also due to **feedbacks**
- o Tune feedback, orbit feedback, transverse damper and radial loop

One of our first ramps:
Losses due to resonance crossing



R. Steinhagen




Running with:
tune feedback since ~ 3rd ramp trial
orbit feedback since May
transverse damper since June

Orbit stability during ramp:
 $\leq 80 \mu\text{m}$ with feedbacks

- o Good news for luminosity: injecting regularly nominal bunches with emittances below nominal (about $2 \mu\text{m}$).
 - Nominal emittance $3.5 \mu\text{m}$.

- o However, emittance blow-up due to “hump” especially in B2V




The beams are periodically excited by UNKOWN source ('hump') of varying frequency – affects mostly beam 2 V
 Leads to emittance blow up


Noise hump

After tests: excluded sources:
 Experimental magnets, transfer lines, LHC correctors, damper, AC dipole, RF cavities, injection kickers, GSM or fire brigade radio network, triplet beam screen cooling


- o Losses per bunch different for different bunches – as expected. Still studies needed to understand differences in detail.



- o Since July **transverse damper on during collisions**: stabilising coherent beam-beam instabilities
- o ~ 20- 30 h luminosity lifetime due to emittance growth





- o **8 events** of sudden local losses (some in the middle of the arc) have been recorded. No quench, but preventive dumps
- o Rise time partly < 1 ms.
- o Potential explanation: dust particles falling into beam creating scatter losses and showers propagating downstream



Next Big Step – “unsafe” injections

- o Injections above “setup beam intensity” from this week (16 bunches per injection)
- o Injection protection system commissioned
- o Have to control transverse and longitudinal parameters from injectors extremely well not to lose beam immediately due to losses on transfer line collimators (TCDI)



- o The LHC is being commissioned in steps of energy and intensity
- o Machine protection is taken seriously. Qualification tests have to be performed before each change of configuration.
- o Despite the machine complexity and immaturity, still manage 40 % of time in physics.
- o Higher intensities might bring new challenges
 - Single event upsets, more frequent “sudden local losses”,...
- o Due to an excellent performance of ALL equipment the ambitious goal of the 2010/2011 run seems to be doable
 - ❑ 30 MJ beams
 - ❑ Luminosity $10^{32} \text{ cm}^{-2}\text{s}^{-1}$

Luminosity steps

