

# SNS Operation and Upgrade Plans

## Andrei Shishlo

SNS Project,  
Oak Ridge National Lab  
Warm Linac Physicist  
On behalf of Accelerator Physics Team  
June 21, 2018

Presented at the  
**HB2018,**  
Daejeon, Korea, June 18 - 22, 2018

ORNL is managed by UT-Battelle  
for the US Department of Energy




# Outline

- **Bottlenecks for Beam Power**
  - New RFQ
  - Beam Energy
  - Target
- **Near Future Plan**
- **Upgrade Plans**
  - Proton Power Upgrade (PPU)
  - Second Target Station (STS)
- **Summary**

# Bottlenecks for Beam Power at SNS



Until recently:



- ❑ Problems with Front End and SCL final energy are solved.
- ❑ The target development is an ongoing activity.




# New RFQ Installed in Spring 2018



- New RFQ was tested at the SNS Beam Test Facility
- Installed during 5 months outage (Inner Reflector Plug replacement)
- Commissioned at the end of April
- Transmission about 94 %
- SNS Front End is ready for Second Target Station Upgrade

# Final Beam Energy is 1.01 MW




- In total 32 cavities have been plasma processed
- Two carts have doubled the rate of in situ plasma processing in last 2 outages
- Average gradient increase of 20%
- No decrease in gradient observed for plasma processed cavities


# Target with Gas Injection

Strain Magnitude vs. Beam Power (Sensor E)


○ Gas injection off ● Gas injection on



Strain measurements showed  
10%–60% reduction in strain  
during first phase of gas injection



# Beam Power History and Near Future Plans




Today we have 1.3 MW



# SNS Upgrade Plans

24 instrument positions  
19 instruments built




**FTS**

1.4 MW

Accelerator

**Now**

24 instrument positions  
19 instruments built



**FTS**

2 MW


0.8 MW

Accelerator

**After PPU Upgrade**

**FTS – First Target Station**  
**STS – Second Target Station**  
**PPU – Proton Power Upgrade**

22 instrument slots,  
8 initial instruments



**STS**

**After STS Upgrade**

- **Proton Power Upgrade project doubles accelerator power capability**
  - Increases FTS capability + capacity and provides accelerator basis for STS
- **Second Target Station provides new instrument hall with world class cold neutron brightness**



# PPU Parameters: $\Delta\text{Power} = \Delta\text{energy} * \Delta\text{Current}$


	SNS 1.4 MW	PPU FTS 60 Hz operation	PPU full upgrade capability	
Proton beam power capability (MW)	1.4	2.0	2.8	
Beam energy (GeV)	1.0	1.3	1.3	← +30%
RFQ output peak beam current (mA)	33	46	46	
Average linac chopping fraction (%)	22	41	18	
Average macropulse beam current (mA)	25	27	38	← +50%
Energy per pulse (kJ)	23	33	47	
Pulse repetition rate (Hz)	60	60	60	} No change
Macro-pulse length (ms)	1	1	1	
FTS decoupled moderator brightness/pulse (AU)	1	1.43	2.04	
FTS coupled moderator brightness/pulse (AU)	1	1.51	2.16	

- **PPU delivers 2.8 MW capable accelerator**
- **Prior to STS, accelerator will run at 2 MW to FTS**

# PPU Technical Scope

## Conventional Facilities

Klystron gallery



### *Target systems:*


- 2 MW target vessel
- Support system upgrades



# PPU Guiding Principles

- Minimize SNS operational impact
- Target: Leverage ongoing operations target improvements
- Optimize built-in facility upgrade provisions and build on operational lessons
- Accelerator
  - Use existing technology where possible
  - Utilize partnerships, sub-contract
  - No equipment rework for STS following PPU



# PPU Notional Schedule (John Galambos)





# Second Target Station: World Class Cold Neutron Performance


5 Å – long wavelength comparison



- STS will be the highest peak brightness long wavelength neutron source

# STS project activities

- Review on the initial instruments and general target/instrument hall choices in April 2017
  - Rotating water cooled tungsten target concept chosen
  - Instrument hall general layout
- Technical parameter changes:
  - 15 Hz, 2 cold moderators
- STS project activities suspended June 2017
  - Focus resources on PPU



# Summary

- PPU is launched
- Front End is ready
- All activities are at full speed

**Thanks for  
your  
attention!**



# Backup slides

# Target gas injection ramp-up: operations and PPU

