

An Operationally Integrated Approach to the SNS 2.8 MW Power Upgrade

HB 2021 workshop, Chicago II

John Galambos Director PPU October 2, 2021

ORNL is managed by UT-Battelle, LLC for the US Department of Energy





SNS overview



CAK RIDGE HIGH FLUX SPALLATION National Laboratory REACTOR SOURCE

SNS has been operating reliably at 1.4 MW since 2018



kmklj

SNS Upgrade Plans



Proton Power Upgrade project scope

Includes scope across much of the neutron source



October 5, 2021

PPU parameters

	SNS 1.4 MW	PPU full upgrade capability	PPU FTS 60 Hz operation	
Proton beam power capability (MW)	1.4	2.8	2.0	
Beam energy (GeV)	1.0	1.3	1.3	30% energy increase
RFQ output peak beam current (mA)	33	46	46	
Average linac chopping fraction (%)	22	18	41	
Average macropulse beam current (mA)	25	38	27	50% current increase
Energy per pulse (kJ)	23	47	33	
Pulse repetition rate (Hz)	60	60	60	
Macro-pulse length (ms)	1	1	1	INO change
FTS decoupled moderator brightness/pulse (AU)	1	2.04	1.43	
FTS coupled moderator brightness/pulse (AU)	1	2.16	1.51	

Partnering is a key element of the PPU strategy

Primary partner JLab has extensive cryomodule fabrication experience



CAK RIDGE HIGH FLUX SPALLATION National Laboratory REACTOR SOURCE

FNAL is designing and overseeing fabrication of new injection magnets



LBNL collaboration on LLRF development



HB 2021 October 5, 2021

Superconducting RF systems: cryomodule production ramping up

- 7 new cryomodules + 1 spare
 - Cavities received in good shape
 - Cryomodule production proceeding well at partner JLab



Cryomodule vacuum vessel





Cold mass assembly

String assembly



RF Systems: largely procurements

Klystrons being received on site (working too!)



Transmitter cooling cart at vendor



LLRF test operation on SNS

Max Chi Folina Dag Diapito Re-	In two solid for show fast toy Run State Off				
Test 25d Control records and a second and as second and a					
e aco dos alos cos ensere di 25. E	Compared and the set of the				
220 0 120 120 120 120 120 120 120 120 12					
Main Date Date (1, 1, 2, 1) No. (1, 2, 1)	10.5 000.1.007 000.000 <th< td=""></th<>				
	Escan Post turns Feed Parts (2000 MM) ter (2000 MM) ter				

HVCM fabrication at vendor



1st article circulator received



HB 2021 October 5, 2021

CAK RIDGE HIGH FLUX SPALLATION National Laboratory REACTOR SOURCE

Ring systems: injection magnet, focus on fabrication

FNAL is fabricating new injection magnets



CAK RIDGE HIGH FLUX SPALLATION National Laboratory REACTOR SOURCE

10

Injection dump imaging system: on track for install in FY22





Current pickups in tunnel for beam power limiting system

HB 2021 October 5, 2021

Target systems: target manufacture and sub-system component fabrication going well









Conventional facilities: klystron gallery buildout is complete: BIM helped

Complicated piping sections are fabricated offsite



And lifted / positioned into place: easier than fabricating in place





(BIM = Building Information Modeling)

• See: https://neutrons.ornl.gov/klystron-virtual-tour CAK RIDGE HIGH FLUX SPALLATION National Laboratory REACTOR SOURCE

HB 2021 October 5, 2021

BIM transformation from virtual to reality



CAK RIDGE HIGH FLUX SPALLATION National Laboratory REACTOR SOURCE

13

HB 2021 October 5, 2021

BIM transformation from virtual to reality





Klystron gallery activity videos



Some onsite activities can occur during beam operation

Service building round plane to equipment racks



Remote serviceability testing for target system upgrade mockup



Installation of cable tray drops and equipment racks





Other onsite activities require beam off







shield blocks mounted on rollers for quick reconfiguration



Gradual power ramp-up over 2023-2024 requires coordination with operations

- Incorporates new equipment as it arrives red shaded areas indicate downtimes
- One 10 month extended outage in 2023



Actional Laboratory

SNS operations and PPU schedules are synchronized

Red periods are

outages

5 year plan



 Directorate level negotiation with input from DOE

• PPU early finish prioritized

CAK RIDGE National Laboratory

19

Green periods are

run periods

SNS operations and PPU schedules are synchronized PPU activities will play important role in outages next2 years

Highlighted items are PPU related



National Laboratory REACTOR SOURCE

Oct. 5, 2021

- PPU is well into the fabrication construction project stage
- The plan is to implement upgrades in stages over ~ 2 years
 - Interleaved with operational runs
 - Starting soon!
- This requires a carefully choreographed "dance" with operations and the project
- 2.8 MW accelerator power capability expected in 2025

