


Acceleration of the High Current Deuteron Beam Through the IFMIF-EVEDA RFQ: Confirmation of the Design Beam Dynamics Performances



FUSION
FOR
ENERGY



Luca Bellan, INFN-LNL

on behalf of the IFMIF/EVEDA collaboration


HB 2021

64th ICFA Advanced Beam Dynamics Workshop
October 2021, Fermilab, Batavia, Illinois USA



Index

- The Radio Frequency Quadrupole
- The injector (source + low energy beam transfer line)
- The MEBT (medium energy beam transfer line)
- Proton beam commissioning results
- Deuteron beam commissioning results
- Conclusions



Full IFMIF/EVEDA prototype: 125 mA CW D⁺ @ 9 MeV



Beam dynamics commissioning phase (0.1% D.C., limited by LPBD)




IFMIF Radio Frequency Quadrupole




Input/output Energy	0.1-5	MeV
Duty cycle	cw	
Deuteron beam current	125	mA
Operating Frequency	175	MHz
Length (5.7 λ)	9.78	m
Vg (min – max)	79 – 132	kV
R0 (min - max) ρ/R0=0.75	0.4135 - 0.7102	cm
Total Stored Energy	6.63	J
Cavity RF power dissipation	550	kW
Maximum dissipated power	86	kW/m
Power density (average-max)	3.5-60	kW/cm ²
Q ₀ /Q _{sr} =0.82	13200	
Shunt impedance (<V>)/P _d	201	kΩ–m
Frequency tuning	Water temp.	
N cells (βλ/2)	489	

- 4-vane 9.8 m CW RFQ for 125 mA deuteron beam, from 0.1 to 5 MeV, Kilpatrick 1.76
 - **1.85 reached during whole assembly pulsed conditioning.** 6% D.C. at nominal voltage, 20% D.C. at half voltage.
 - **1.94 CW for 5 hours of last supermodule at LNL.**
- Generalized perveance 10⁻³ to 10⁻⁵
- Low B modification, after Critical Design Review, for decreasing input beam requirements from LEPT:
 - rms beam convergence requirement drops from 43 mrad to 24. mrad
 - Transmission for a 4D Gaussian matched (4 sigmas) beam drops from: 95% to **93.7%** (accelerated only considered)
- **Input/output rms normalized transverse emittance: 0.25/0.26 mm mm mrad.**
- Longitudinal rms emittance: 0.2 MeV deg



- The RFQ was integrated in the simulation via the software TOUTATIS
- The model integrated was the “as-built” model.

“As built” model includes:




Parameter	Relative diff. between nominal and as built simulations
$\Delta \epsilon_{rms,t,n} / \epsilon_{rms,t,n}$	+3%
$\Delta \epsilon_{rms,l} / \epsilon_{rms,l}$	+8%
$\Delta transmission / Nominal Transmission$	- 2% (i.e. 91.8%)

Input matched beam requirements (at RFQ injection point) for 90%> transmission:



$$I_{beam} \rightarrow \epsilon_{Gauss,rms,t,n} \rightarrow \forall \epsilon_{rms,t,n} < \epsilon_{Gauss,rms,t,n}$$

Defined as the maximum rms emittance at I_{beam} that can transmit > 90% of the beam, in case of 4D Gaussian distribution, 4 sigmas cut.

- Not equilibrium distribution from the source (hollow, tails etc..)
 - Design is done following the evolution of the rms quantities evolution (Sacharer equivalent principle) in order to decrease the dependence with respect the input distribution and to built a more general guideline for the input RFQ evaluation



The injector




- ECR ion source type with two coils
- Magnetic LEPT transfer line composed by two solenoids (space charge comp. applies)
- 5 electrode extraction (100 kV- variable – ground – repeller - ground)
- Multispecies beam transport with generalized un-neutralized perveance between 5×10^{-4} to 5×10^{-3}
- **Possibility to extract proton at 50 keV (scaled beam dynamics) to be used as a probe beam and for test at low power.**
Chopper implementation for the same reason
- Gas injection (Kr) in the middle of the LEPT for boosting space charge compensation.


➡ To supply the required current beam at the RFQ entrance, below $\epsilon_{rms,t,n} < 0.3 \text{ mm mrad}$ ($\epsilon_{Gauss,rms,t,n}(125 \text{ mA})$), with ideally 0% mismatch.

➡ Very difficult to measure the phase spaces at RFQ injection point (power density, technological difficulties).

➡ Measure of the phase spaces in two different points (middle of the solenoids and after RFQ injection cone during injector commissioning). ➡ Should be interpolated by some support model




Criterion for beam injection into the RFQ




Measured

Simulated

XX' phase spaces between solenoids




The emittance measurements are routinely taken between the solenoids. **Developed a criteria for evaluation of the beam quality before injection into the RFQ**




Cross talk between simulations and measurements



EMU measurements




N	Sp.	Energy [keV]	I_{ext} [mA]	$\epsilon_{exp}/\epsilon_{sim}$	$\alpha_{exp}/\alpha_{sim}$	β_{exp}/β_{sim}
1	H ⁺	50	70	0.25/0.25	14.8/10.7	14.7/13.6
2	H ⁺	50	87	0.38/0.34	7.3/5.8	18.3/17.4
3	D ⁺	100	163	0.19/0.19	2.2/1.4	20.7/18.0

Nominal point selected for injection







The MEBT



- Compact MEBT line of about 2.346 m
- 5 quadrupoles and 2 bunchers
- Generalized perveance 10^{-5} with nominal beam
- Separates the not accelerated particles, the residual contaminants and, in general, the particles with large $\Delta p/p$ difference. However, since the LEBT ACCT is sensible to contaminants, the overall calibration curve remains affected by them.




simulation



Proton beam commissioning results

Probe beam (7-10 mA) @ 50 keV


24-30 mA beam (half perveance) @ 50 keV



Half perveance beam study, outcomes:






- Emittance after the RFQ check
- Longest pulse accelerated (4.5 ms)
- RFQ can withstand a mismatch of 220%
- Effect of contaminants onto the LEBT ACCT current read-out: down estimation of transmission.

Current value	Steerer setup 1	Steerer setup 2
I_{LPBD}	9.8	9.6
$I_{LEBT, ACCT}$	11.9	9.8
T_{exp}	82%	98%



Transverse emittance after the RFQ [1]


Measurement	Value
V_{rfq} [kV]	70
I_{LPBD}	22.8
$\epsilon_{exp}/\epsilon_{sim}$	0.23/0.23
β_{exp}/β_{sim}	6.9/6.1
α/α_{sim}	-4.6/4.6




Simulation YY'

Simulation XX'

[1] J. Marroncle et al., "Transverse emittance in 2.5 MeV proton beam on LIPAc, IFMIF's Prototype", in Proc. IBIC'19, Malmö, Sweden, September 2019, pp. 288-293.





Deuteron beam commissioning results




- 125 mA 1Hz 1 ms beam reached on July 2019.
- Until 9th Aug., stable operation for several hours at 125 mA was succeeded.

Transmission I_{LPBD}/I_{LEPT} at $V/V_n=1$	Values and uncertainties [%]
Experimental	89.7 ± 1.2
Sim. D^+ and D_2^+	91.5 ± 1.0
Sim. D^+	92.5 ± 1.0

First beam pulse





Beam dist.	Year	$\epsilon_{rms,t,n}$	$\epsilon_{99\%,t,n}$	Trans.
4D Gaussian (design 4 sigma)	2011	0.25	2.2	91.8 (as-built) 93.7 (design)
Realistic estimated	2019	0.2	3.7208	92.5 ± 1.0 (estimated)



Deuteron beam commissioning: TOF measurements

- The ToF energy from different pair of BPM of the D-Plate and MEBT as function of the RFQ voltage: 5 MeV \pm 1% [2]
- Neutron production on LPBD and MEBT scrapers due to $^{27}\text{Al}(d,n)$ reaction as expected. [3]



That shape of the ToF-energy curve is linked to the beam energy at the RFQ input. The input beam was around 1 keV higher than nominal input energy (100 keV).
 The input energy offset causes synchrotron oscillations of the bunch inside the separatrix and around the nominal energy point.

Possibility to fine tune the extraction voltage , planned for the next campaign

[2] I. Podadera et al., "Beam commissioning of beam position and phase monitors for LIPAc", in Proc. IBIC'19, Malmö, Sweden, September 2019, pp. 534-538.
 [3] K. Kondo et al., "Neutron production measurement in the 125-mA 5-MeV deuteron beam commissioning of Linear IFMIF Prototype Accelerator (LIPAc) RFQ", Nucl. Fusion. September 2021,

Conclusions

- **Test low and half perveance:**
 - Transverse emittances within the expectations as design
 - Low perveance (10 mA) beam transmission close to 100% as expected
- **Test at nominal perveance:**
 - Transmission compatible with what was expected by the design
 - Energy and oscillations within the longitudinal separatrix, compatible with the expectations.

What remains to do, **from beam dynamics** point of view:

- Measurement of the transverse emittance at nominal perveance
- Estimation of the longitudinal emittance at nominal perveance

What remains to do, **from RFQ** point of view:

- **CW RF RFQ**
- CW beam, possibly to maintain it for several weeks (under discussion)
- Beam restarted in July 2021, after maintenance shut down, new line for CW test installed specifically and under commissioning

