



IBIC ✦
2021

Recommissioning of the CERN injector complex beam instrumentation

Ray VENESS

On behalf of the CERN Beam Instrumentation Group



- Introduction
 - Long-term accelerator plans
 - Objectives of the recent accelerator complex shutdown
 - Consequent changes to beam instrumentation
- Some technical highlights from the shutdown and commissioning:
 - References to papers in this conference
 - Selected new instruments
- Summary



CERN commissioning contributions to this conference

IBIC ✦
2021

WEPP24

- **PSB HO-H- monitor calibration and commissioning.** *A.Navarro and F.Roncarolo*

TUOA05

- **Commissioning of the Timepix3 based beam gas ionization profile monitors for the CERN Proton Synchrotron.** *H.Sandberg et al.*

TUPP22

- **New CERN SPS beam dump imaging system.** *S.Burger et al.*

MOPP23

- **The commissioning of ALPS, the new beam position monitoring system of CERNs Super Proton Synchrotron.** *A.Boccardi et al.*

TUPP32

- **The Beam Loss Monitoring System after LHC Injectors Upgrade at CERN.** *M.Saccani et al.*


TUPP18

- **Commissioning of the LHC Injectors BWS Upgrade.** *J.Emery et al.*



CERN long-term accelerator schedule


IBIC 2021



CERN long-term accelerator schedule, January 2020. CERN EDMS ACC-PM-MS-0004



The CERN accelerator complex Complexe des accélérateurs du CERN



▶ H^- (hydrogen anions) ▶ p (protons) ▶ ions ▶ RIBs (Radioactive Ion Beams) ▶ n (neutrons) ▶ \bar{p} (antiprotons) ▶ e^- (electrons)

LHC - Large Hadron Collider // SPS - Super Proton Synchrotron // PS - Proton Synchrotron // AD - Antiproton Decelerator // CLEAR - CERN Linear Electron Accelerator for Research // AWAKE - Advanced WAKEfield Experiment // ISOLDE - Isotope Separator OnLine // REX/HIE - Radioactive Experiment/High Intensity and Energy ISOLDE // LEIR - Low Energy Ion Ring // LINAC - LINear ACcelerator // n_TOF - Neutrons Time Of Flight //

HiRadMat - High-Radiation to Materials



The CERN accelerator complex

Complexe des accélérateurs du CERN


IBIC 2021

Focussing on:

- LHC injectors
- Protons


Not covering:

- LHC ring
- Ion injection chain
- Antiproton chain
- Fixed target lines




▶ H^- (hydrogen anions) ▶ p (protons) ▶ ions ▶ RIBs (Radioactive Ion Beams) ▶ n (neutrons) ▶ \bar{p} (antiprotons) ▶ e^- (electrons)

LHC - Large Hadron Collider // SPS - Super Proton Synchrotron // PS - Proton Synchrotron // AD - Antiproton Decelerator // CLEAR - CERN Linear Electron Accelerator for Research // AWAKE - Advanced WAKEfield Experiment // ISOLDE - Isotope Separator OnLine // REX/HIE - Radioactive EXperiment/High Intensity and Energy ISOLDE // LEIR - Low Energy Ion Ring // LINAC - LINear ACcelerator // n_TOF - Neutrons Time Of Flight // HiRadMat - High-Radiation to Materials




New H- LINAC (LINAC4)



New charge exchange injection to PSB


New H- LINAC (LINAC4)



New charge exchange injection to PSB

New H- LINAC (LINAC4)

Booster (PSB) energy upgrade




New charge exchange injection to PSB

New H- LINAC (LINAC4)

Booster (PSB) energy upgrade

Proton synchrotron (PS) energy upgrade




New internal beam dump in the SPS

New charge exchange injection to PSB

New H- LINAC (LINAC4)

Booster (PSB) energy upgrade

Proton synchrotron (PS) energy upgrade



New internal beam dump in the SPS


New extra-low energy antiproton ring

New charge exchange injection to PSB

New H- LINAC (LINAC4)

Booster (PSB) energy upgrade

Proton synchrotron (PS) energy upgrade



New extra-low energy antiproton ring

New charge exchange injection to PSB

New H- LINAC (LINAC4)

Extensions to HIE-ISOLDE

Booster (PSB) energy upgrade

Proton synchrotron (PS) energy upgrade

Achievable proton beam characteristics at injection for the post-LIU accelerators [*]

Machine	Kinematic energy (GeV)	Number of bunches	Distance between bunches (ns)	Bunch intensity (10e11 p/b)	Transverse emittance (m)	Bunch length (ns)
PSB	0.16	1/ring		29.6	1.5	650
PS	2	2+4	284	28.1	1.6	205
SPS	25	4x72	25	2.2	1.7	4.2
LHC	449	10x288	25	2	1.9	1.65

Increased from 50 MeV

Increased from 1.4 GeV

cf. 1.15 achieved in Run 2**

cf. 2.5 achieved in Run 2**

- New H- injection into the PSB
- Higher energy transfer into PS
- Higher bunch intensities in all machines
- Smaller transverse emittances in all machines

* "LHC Injectors Upgrade, Technical Design Report, Vol.1: Protons." <http://dx.doi.org/10.17181/CERN.7NHR.6HGC>

**"LHC injectors Upgrade Project: Towards new territory beam parameters." M.Meddahi et al. <http://dx.doi.org/10.18429/JACoW-IPAC2019-THXPLM1>




Long Shutdown 2 for Beam Instrumentation

IBIC ✦
2021


- LHC injectors Upgrade Project (LIU)
 - 49 new in-vacuum instruments built for installation in LS2
 - LINAC4 as a new operational machine
 - SPS beam dump. New and re-configured instruments, removed and re-installed beamlines
 - New SPS BPM readout system (ALPS)
- Accelerator Consolidation (CONS) and maintenance
 - 25 new instruments in the LHC chain from CONS project
 - New BPM interlock electronics
 - 348 new beam-loss monitor chambers and electronics
 - Replaced much of the obsolete instrumentation in ISOLDE
 - All of the ~7000 BI instrument park requires inspection or maintenance with rare access to some instruments due to long injector shutdown
- LHC (Maintenance and upgrade prototyping)
 - 1500+ BLMs and 850 cable trays removed and re-installed
 - Two new prototype instruments in LHC (BRAND,BGC)
- Non-LHC chain
 - New extra-low energy Pbar ring (ELENA) and HIE-ISOLDE extensions
- Overall
 - Total of 152 new in-vacuum instruments designed, built and installed in LS2

Machine/Complex	'New for old' replacements	Additional instruments
LINAC 4	-	36
PSB	20	12
PS	9	2
SPS	4	3
LHC	3	1
ISOLDE/HIE	20	11
ELENA	-	31
TOTAL	56	96

In-vacuum instruments newly commissioned for operation post LS2



J. Tan, "LINAC4 diagnostics experience during commissioning". ARIES workshop on Experiences During Hadron LINAC Commissioning, 2021,
 F.Roncarolo et al. "Commissioning the new CERN beam instrumentation following the upgrade of the LHC injector chain". IPAC 2021




New 'laser wire' emittance meter in LINAC4

IBIC 2021




L4@CERN




H⁰ → H⁻

Laser




Bending Magnet


Principle:




Diamond detector



Ref: CIVIDEC Instrumentation, Austria



Emittance measurement in 2021



- Minimally invasive with only a few % of intercepted particles being stripped
- Pulse freq: 35 to 500 kHz
- Line width: 1 to 5nm

See poster: WEPP24



H0-H- monitor required to:

1. Warn about stripping foil degradation (continuous monitoring function)
2. protect dedicated internal dump (interlock function)


Stripping foil observation

screen with rad-hard camera:

1. Measures beam position during set-up
2. Monitors integrity of the foils



Stripping inefficiencies of different foil types measured by the H0/H- monitor





H0/H- monitor with 4 cables Ti stripping plates




New PS beam-gas ionisation profile monitors

See talk: TUOA05

IBIC 2021



Beam position and size



600 horizontal profiles of an LHC-type beam, measured through the 1.2 second PS cycle (May 2021)

- First use of active semiconductor instruments in a CERN injector ring
- H and V devices now installed and operating with beam









New SPS beam dump imaging system

IBIC⁺ 2021

See poster: TUPP22

- 'Operation critical' observation device in a highly active area
- Fixed screen, intercepting just the extracted beam
- Light is imaged via a 17m long optical chamber, with camera in a shielded hutch



Automated image selection taking advantage of slow CROMOX decay time




New orbit system electronics for the SPS (ALPS)

See poster: MOPP23

IBIC 2021

- A Logarithmic Positioning System (ALPS) for the SPS, consisting of:
 - 240 radiation-tolerant front-end electronics systems installed around the SPS ring during LS2
 - 60 back-end boards using a CERN-design 'VME Front-end Card' (VFC)
- Extensive prototype testing during Run 2
 - First roll-out of VFC, a new CERN standard, now being used in other instruments such as the new wire scanners
- Successfully used from first beam for the SPS beam commissioning
 - Measured multi-bunch turn-by-turn resolution of $7 \mu\text{m}$ measured in vertical plane

Injection during beam commissioning





New Fast Wire Scanners for the PSB, PS and SPS

See talk: TUPP18



- 17 new 20 ms⁻¹ scanners installed and operating
 - Wire position from optical disc encoding
 - 4 PMTs coupled to same scintillator with different optical density filters
 - Fast digital integration (500MS/s) to allow bunch per bunch profile measurements
 - Standardised designs for mechanics, electronics and software
- Extensively prototyped with beam before series production







Figure 7.1 – Multi-PMT printed circuit board design.



Instruments heavily used for accelerator optimisation from first beam (PSB shown)


4-channel PMT card takes simultaneous acquisitions to allow for 'high dynamic range' signal



Beam-loss monitoring (BLM) activities

See poster: TUPP32

IBIC 2021




New monitors in the PS Booster

• New scope BLMs


- 348 new monitors, with new electronics and software in the injectors
- Automatic fast protection against excessive beam loss and measurement of losses for machine set-up
- Two measurement techniques to cover the 2×10^{10} input range

• Staged installation and commissioning

- Prototypes installed and operated from 2015
- Dry-runs with operations teams
- Successfully operating from first beams
- Some issues of synchronous and asynchronous noise being addressed



Operational applications in LINAC4 (above) and PSB (below)






Summary

IBIC⁺
2021

- Long Shutdown 2 saw probably the most complete set of changes and upgrades in the 60-year history of the CERN injector complex
 - 152 new in-vacuum instruments built and installed as well as 348 new beam-loss monitors
 - Two new machines (LINAC4 and ELENA) put into operation
- Commissioning has been remarkably successful
 - All instruments, including new design concepts, were available when needed by operations
 - There are six papers at this conference covering commissioning of specific instruments
 - Commissioning is still ongoing, with performance optimisation in progress and some non-critical issues to be resolved
 - Key common elements in this success have been testing of prototypes with beam and preparing by working closely with operations teams
- CERN BI group took the opportunity to replace obsolete instruments, electronics and software with new standards
 - Expecting efficiency gains for our limited number of expert personnel
 - ...but compensated by the increase of 96 new instruments to operate and maintain post-shutdown



Thanks to the many people, both at CERN and our collaborating institutes around the world, who have made this commissioning a success