



LCLS-II Injector Source Controls and Early Injector Commissioning (EIC)

D. Rogind[#], M. Boyes, H. Shoaee

SLAC National Accelerator Laboratory, Menlo Park, CA 94025 USA

Acknowledgements: SLAC Controls Teams; JLAB LLRF Group; LBNL APEX Controls + LLRF Group; FNAL LLRF Group; FNAL LLRF Group; FNAL LLRF Group; Team. (Individual names are too numerous to mention.)

Abstract

LCLS-II is a superconducting upgrade to the existing Linear Coherent Light Source at SLAC with a continuous wave beam rate of up to 1 MHz. Construction is underway with first light planned for 2020. The LCLS-II Injector section that comprises low energy from the gun up to the location of the first cryomodule is based on the LBNL Advanced Photo-Injector Experiment (APEX), and is being provided by LBNL. In 2015, responsibility for **controls** design and fabrication was transferred to SLAC from LBNL to promote commonality with the rest of the LCLS-II control subsystems. Collaboration between the LBNL APEX controls community and SLAC LCSL-II EPICS controls teams proved vital in advancing the controls architecture toward standardized implementations integrated with the rest of LCLS-II. An added challenge is Early Injector Commissioning (EIC), ~1.5 years ahead of the rest of LCLS-II, in Jan. 2018. EIC controls scope, approach, and advantages are discussed.





What is EIC Scope?

EIC Approach

□ Appointed SLAC GUNB / EIC Project Lead Create comprehensive Interface Control Doc (ICD) Create Partner Lab Scope Handoff Agreements Weekly EIC dedicated meetings

- GUNB: Collaborate between the LBNL APEX & SLAC mechanical / controls communities
- Design & incorporate LCLS-II standard controls for use with GUNB Injector Source
 - Only Motion and Interlocks are unique designs for GUNB
 - Use SLAC BPM stripline, YAG screen design & controls
 - LLRF controls remain Partner Lab scope
 - 1MHz-based control systems incorporated

□ EIC: Advance schedules for "warm" LCLS-II Controls Subsystems by ~ 1 year:



EIC Interim Solutions

Motion



Partner Lab Handoff Agreements

| 5 | 2016 | 2017 | 20 | 81 | 201 | .9 | 2020 |
|-------|--|-----------------------------|-------------------|-----------|--------|------|------------|
| LS Op | erations (Ops) | | | LCLS 1 Yr | . Down | LCLS | Comm./Ops |
| | | | | LCLS-II I | nstall | LCLS | 6-II Comm. |
| | GUNB Mechanical Final Design Complete | LCLS-II 1MH based Comr | Iz ATCA | | | | |
| | | Platform Co Final Design | ntrols Reviews | | | | |
| | | Complete | | | | | |
| | | | | | | | |

EIC Pay-Offs

- Debut LCLS-II 1MHz ATCA Common Platform based controls & integrate
- Debut Partner Lab Gun & Buncher LLRF Controls
 - Integrate SLAC EPICS Controls including Gun **Resonance Motion**

Debut Particle Free Vacuum (new to SLAC)



Debut EPICS 3.15.5 & git version control; Software Global Controls Integration



Lock down Procurement and Asset tracking process & tools

- Drive Laser (only), Vacuum, PPS, BPM, BCM, YAG, MPS, Timing
- Gun & Buncher LLRF
- ✤ No requirement for Beam Containment; no cryogenics
- Some temporary / basic solutions will exist: Computing Infrastructure uses LCLS infrastructure Basic: Timing, Machine Protection Systems FCUP temporary location on temporary shield wall
- □ Some first article "prototypes" will be fielded: Gun & Buncher LLRF controls Racks, shorter Phase Reference Line

*Work supported by the U.S. DOE Contract DE-AC02-76SF00515 #drogind@SLAC.Stanford.EDU





Qualtiy Control (QC) Controls Subsystems Hardware drawing packages

QC Production & Rack Loading processes

QC Controls check-out procedures; both Prebeam and with beam

QC ARR, Commissioning, support processes

QC Partner Lab Scope Hand-off agreements

All activities for LCLS-II Controls will benefit from experiences gained by EIC

THPHA002