Table : # of IOCs for each subsystem.

Safety

Monitor

Magnet

Vacuum

Operation

Timing

Temperature

of IOCs

48

57

21

Control System Status of SuperKEKB Injector Linac

M. Satoh, I. Satake, H. Sugimura, Y. Seimiya, F. Miyahara, T. Natsui, Y. Enomoto, T. Suwada, K. Furukawa, KEK/SOKENDAI, Tsukuba, Japan

Y. Mizukawa, K. Hisazumi, T. Kudou, S. Ushimoto, Y. Kuroda, S. Kusano, Mitsubishi Electric System & Service Co., Ltd, Ibaraki, Japan H. Saotome, T. Ohfusa, M. Takagi, Kanto Information Service (KIS), Accelerator Group, Tsuchiura, Japan

SuperKEKB Injector Linac Overview

- •High bunch charge (4 nC), low emittance (20 μm), small
- •Simultaneous top-up injection for 5 independent rings
- (SKB e-/e+, e+ damping ring PF, PF-AR) w/ different beam energies.



FIG. 1: Schematic drawing of SuperKEKB Linac. Colored parts will be newly installed.

Pı	Project		KEKB'''		SuperKEKB''' (Phase I)		SuperKEKB**** (Phase II)		SuperKEKB''' (Phase III)	
Beam		e-	e+	e-	e+	e-	e+	e-	e+	
Beam energy(GeV)		8	3.5	7	4	7	4	7	4	
Stored current (A)		1.1	1.6	1	1	-	-	2.6	3.6	
Beam life time (min.)		200	150	100	100		-	6	6	
Bunch charge (nC)		1	1 (10")	1	0.4(8)	1	0.5 (10°)	4	4(10	
emi	Normalized vertical emittance (mm-mrad) Normalized horizontal emittance (mm-mrad)		1400	300 130"	1200	150	40	20	15	
horizont				160 200"	1000	150	200	40	100	
Energy:	spread (%)	0.125	0.125	0.5	0.5	0.1	0.16	0.07	0.16	
Bunch le	ength (mm)	1.3	2.6	1.3	2.6	1.3	0.7	1.3	0.7	
#of	#ofbunch		2		2		2			
Maximum beam repetition (Hz)		50		25		25 / 50				
Top up injection		3 rings (HER, LER, PF)		n/a		5 rings (HER, LER, DR, PF, PF-AR)				

Design values




FIG. 2: Schematic drawing of simultaneous top-up injection operation scheme for SuperKEKB Linac.

Low Emittance Preservation for e- Beam (w/o damping ring)

- •Component misalignment (Accelerating structure, Q-Mag.) causes the serious emittance growth.
- •Simulation was carried out for the 500-m-long straight line (5 nC, initial emittance 10 mm·mrad w/ various misalignments of the accelerating structures and quadrupole magnets)
- Precise beam position measurement and control => Important issues




•The electron beam of short bunch length can mitigate the transverse wake field and eventually can avoid the significant emittance growth. However, it may cause the large energy spread if the longitudinal bunch shape is Gaussian. The rectangular like longitudinal bunch shape can keep the small energy spread beam.

nal RF ph

Injector Linac Control System

- EPICS based Control System
 - Base R3.14.9, R3.14.12
- EPICS Channel Archiver, CSS Archiver, CSS Alarm
- Server machines (x17)
 - CentOS 5.10 (x86_64)
- •HP blade BL460c G1/G8/G9, BL680c G5, 1U/2U server
- •Storage: NetApp FAS3220, FAS2040, FAS2020
- Operation terminal machines (x10)
 - PC (Windows 7/CentOS 5.11, 6.8, 7.2 (x86_64))
- •Tcl/Tk, SAD (Strategic Accelerator Design) => Python, SAD, MEDM, CSS







Event Based Timing Control System

•MRF: VME EVG 230 x3, EVR-230RF x46, PXI EVR-230 x13

•VME 64x based. VxWorks 6.8.



Beam Monitor Control System



Summary and Future Plan

- SuperKEKB injector linac control system is based on the EPICS framework. We manage about 150 EPICS IOCs and about 50,000 PVs.
- The new BPM readout system based on a double width VME card w/ the precision of about 10 μm (1σ).
- The PXI based EVR 230 system is implemented for the pulsed steering and quadrupole magnet controls, now under test. It will be applied for the real beam operation in this October 10th.
- Project management tool Redmine and Git SCM are very effective for pushing the productivity of linac control group.