




The Phase-1 Upgrade of the ATLAS Level-1 Calorimeter Trigger

Tigran Mkrtchyan (KIP, Heidelberg)

On behalf of the ATLAS Collaboration




ICALEPCS 2021

19.10.2021



ATLAS Trigger and Data Acquisition




• Latency of max. 2.5us

Overview of the ATLAS Trigger and Data Acquisition

Overview of L1Calo


- Hardware-based, pipelined system
- Processing signals from the ATLAS Liquid Argon (LAr) and Tile calorimeters
- Identifies e, γ , τ candidates
- Small and large-R jet candidates
- Missing E_{T} and Σ E_{T}
- Upgrade:
 - New Feature Extractor (FEX) processors
 - Upgraded Level-1 Topological (L1Topo) processor
 - New Tile Rear Extension (TREX)
 - New readout system: Front-End Link eXchange (FELIX)
- The L1Calo Upgrade and legacy systems will run in parallel during commissioning




Why upgrade?

Challenging high-pileup environment

- New calorimeter trigger electronics from LAr
 - Run 2 used lower granularity Trigger Tower ($\Delta\eta x \Delta \phi = 0.1 \times 0.1$) information
 - 10x granularity increase with Super Cells ($\Delta\eta x \Delta \phi = 0.025 \times 0.1$)
 - Higher resolution and shower information



Reduce Level-1 rate while maintaining low selection thresholds



Hardware overview



- Electron Feature Extractor (eFEX)
 - 24 modules in 2 ATCA shelves
 - Takes advantage of the new higher granularity of the EM calorimeter
 - e, γ , τ identification




- Jet Feature Extractor (jFEX)
 - 6 ATCA modules
 - Taus, Large- and small-R jets
 - Missing E_{T} and Σ E_{T}



- Global Feature Extractor (gFEX)
 - 1 ATCA module
 - Large-Rjets
 - Missing E_{T} and Σ E_{T}
 - Receives inputs from the entire calorimeter systems

Hardware overview





- Level-1 Topological
 Tile Rear Extension Trigger (L1Topo)
 - 3 ATCA modules
 - Receives inputs from the FEXes + L1 Muon
 - Performs topological algorithms and multiplicity trigger


- (TREX)
 - 32 VME-RTM modules
 - Physical extension of the Legacy PreProcessor
 - Provides digitized hadronic inputs from TileCal to the FEXes (optical) and the Legacy system (electrical)

- Hub+Readout Driver • (ROD)
 - 7 ATCA modules
 - 2x2 in eFEX, 2x in jFEX 1x in L1Topp shelves
 - Distributes timing and trigger information to eFEX/jFEX/L1Topo
 - Buffers and sends readout data to the DAQ

- Topo-FOX FOX
 - Fiber-Optic Exchange(FOX)
 - 6 boxes
 - Map calorimeter inputs to FEXes
 - ~7500 fibers
 - FEX-L1Topo box • (Topo-FOX)
 - ~1500 fibers

Expected Performance

- Significant improvement to the energy resolution w.r.t existing L1 $\rm E_{T}$
- Improved efficiency and sharper turnon curves
- eFEX performance
 - Using full detector resolution
 - Z → ee simulation comparing the upgrade with the existing system
 - Thresholds chosen to match the Run2 rate




7

Expected Performance

- jFEX performance:
 - Per-jet efficiencies using $HH \rightarrow bb(bb)$ simulation
 - New circular 0.9 x 0.9 sliding window
 - Comparison with offline Anti-kt and Run 2 L1
 - Thresholds of the methods tuned to have matching trigger rates

- gFEX performance:
 - Per-jet efficiencies using pair-produced top quark simulation with a pileup level of <mu> = 80
 - Seeded cone algorithm with a nominal jet radius of R = 1.0



Installation in ATLAS

- All racks and ATCA shelves installed
 - 3x racks
 - 2x eFEX, 1x jFEX, 1x gFEX, 1x L1Topo shelves
- Control and monitoring PCs installed
 - 4x PCs for the Detector Control System
 - 2x PCs Monitoring/ControlHub
 - 2x PCs for JTAG connectivity
- Optical fibers and network cabling routed between the modules
 - ~ 6000 fibers
- Modules undergo validation at home institutes and CERN at the Surface-Test-Facility (STF) before installation



Installed gFEX module

Topo-FOX installation

Installation in ATLAS

- gFEX (1/1) and TREX (32/32) fully installed!
- eFEX
 - 6 module installed (out of 24)
 - 18 to be installed in 2022
- jfex
 - 3 module installed (out of 6)
 - 2 further modules to be installed soon
- L1Topo
 - 1 module to be installed by the end of the year
- Hub + ROD
 - 4 modules installed
 - Rest of the modules at CERN and ready to be installed
- FOX + TopoFOX
 - 6 Boxes
 - FOX fully installed and connected
 - TopoFOX installed and soon to be connected



e/jFEX shelves with Hub+RODS



Fully equipped TREX crate




Commissioning

- Surface Test Facility (STF)
 - Test-rig for single modules
 - Full vertical slice of L1Calo modules
 - Full DAQ infrastructure available
- Dedicated for firmware and software integration
- Achieved combined slice with all modules!
 - Synchronous readout and event building
 - Successful transmission tests


Individual


Module Tests



Commissioning in ATLAS

- ATLAS P1
 - Integration into ATLAS run control software
 - Fiber mapping and connectivity debugging
 - Bit-Error Rate Testing of the high-speed transmission links
 - Integration with the Calorimeters
 - Timing-in the full Trigger system
- Module control integrated in the ATLAS software
- TREX running in ATLAS with 100 kHz readout
- Installed FEX modules successfully integrated in ATLAS
- Preparing for first LHC Pilot Beams!





during L1Calo Tests

12

Summary

- Huge effort from experts all around the world!
 - 15 institutes from USA and Europe
 - Experts working at CERN and remotely
- Installation and commissioning activities ramping up in ATLAS
 - Transmission tests and mapping validation ongoing
- Firmware development of all modules in good shape and close to completion
- Ready to test with LHC pilot beams

