



ARIEL Buildings Construction and Electron Linac Photo-Fission Driver for the Rare Isotope Program at TRIUMF


IPAC'12, 2012 May 21

Yu-Chiu Chao for e-linac team



- **Motivation – RIB science at ISAC**
- **ARIEL Civil Construction**
 - Stores & Badge Buildings
 - Compressor Building
 - ARIEL Targets and RIB Building
 - E-hall renovation
- **E-linac (the machine)**
 - E-Gun
 - ELBT at VECC test area
 - Cryomodules
 - Cryogenic System
 - HPRF
- **Conclusion**

ARIEL triples RIB science at ISAC



10-Year Vision: expanded RIB program with:

- three simultaneous beams
- increased number of hours delivered per year
- new beam species
- increased beam development capabilities

Implementation:

- Complementary electron linac driver for photo-fission
- New target stations and front end
- New proton beamline
- Staged installation

Site Preparation: demolition, relocation, construction



- **2011 October**
- **CONGESTED SITE**
- **Old Stores & RH Demolition**
- **Excavation and shoring**
- **Makes way for ARIEL building**



New Badge building

New Stores building

New GHe compressor building

 **TRIUMF**
New Stores Bldg



Ground Breaking:
2011 March

Completion:
2011 September



New Badge Building



Construction started:
2011 August

Occupancy:
2011 November



Helium Compressor Building



Ground breaking: 2012 March




- Foundations: 2012 May
- **Expect occupancy: 2012 December**

ARIEL building design



The culmination of an intensive study of what is needed to facilitate smooth and routine RIB delivery.

ARIEL Layout – below ground



Excavation, Shoring, Construction

Excavation started: 2011 November





Tunnel

RIB front end


ARIEL site: 2012 Jan

**Building occupancy
expected: 2013 April**

ARIEL site: 2012 May




Electron Hall Renovation: Cleanout



- Proton hall clean up complete 2012 Feb
- Construction underway 2012 March
- Expect occupancy 2012 October



Electron Hall Renovation: South shield wall



1st concrete pour 2012/March



- Shielding upgrades
- South wall B2 up to ground for ERL/RLA operation.



Final S. wall pour, 2012/April



Electron Hall Renovation: North shield wall

- Poured-in-place concrete
- N. Wall (shield e-hall from BL4N)

Rebar for N shield wall,
2012/April



1st pour cured 2012/May

E-Linac: Accelerator Overview

**300 keV thermionic gun:
650 MHz modulated**

Injector:

10 mA, 5-10 MeV gain
 ≤ 100 kW beam power

Accelerator:

Two cryomodules
Two cavities/module,
10 mA, 40 MeV gain
 ≤ 400 kW beam power

NC Buncher



**ARIEL Phase I:
25 MeV, 200kW**

**ARIEL Phase II:
50 MeV, 500kW**

Installed Cryoplant for Phase I & II


300 kV 10 mA Electron Gun

Gun assembly



SF6 Vessel


- Detail design mostly complete
- Procurements in progress
- Installation begins: 2012 Sept



Many long lead items
already delivered:
Ceramic, HVPS, ITX, RF
Cathodes, Steering coils




HVPS




HV cage

Gun Components



SF₆ vessel & Gun RF modulation


RF horns and ceramic waveguide



Eimac cathode


rf matching network

Successful dielectric waveguide R&D program with scale model & HFSS





Transmission optimized at 650 MHz


RF modulation on 100kV prototype makes bunched beam at 650MHz
 RF power on grid used to generate duty factors 0.1% to 99.9% at rep rates 100Hz to 1kHz



ELBT at VECC test stand




Test 1 Configuration




University of Victoria View
Screen Profile Monitor





300 W
Faraday
cup




VECC ELBT Test1 – 2011 Dec/2012 Feb



Allison emittance scans performed 2012 Feb 09 onward up to to 660W beam power at ~20W/mm




Accelerator Cryomodule




Jlab style Scissor-Tuner prototype



- Single-cavity EIJN prototypes most features of two-cavity EACA design.
- 2011 June: focus narrowed to completion of EIJN design, and fabrication in 2012



Injector Cryomodule



Cryomodule concept borrows significantly from ISAC-II


Top loading box concept with cavity mounted to strongback that is suspended from struts


Box gives headroom for on-board 2K/4K heat exchanger & 4K separator

- All procurements in hand
- Fabrication underway
- Cavity, 4K/2K insert (75% done)

Injector Cryomodule Detailing

- Detail design complete:
 - Cold mass support (strongback, struts), lid, cold mu-metal, scissor tuner
- Detail design in progress:
 - Tank, warm/cold transition, LN2 shield








Cavity Status

**Success: 7 out of 7
PAVAC/TRIUMF single-
cells meet requirements**

- 7 cell Cu cavity delivered from PAVAC
- Nine cell cavity design fixed and contract signed
- Tooling optimized
- Four Nb half cells formed and welded



Cryogenic System Design/Procurement



- White boxes: TRIUMF responsibility
- Pale blue boxes: cryoplant ordered from Air Liquide Advanced Technology, 2011 Oct

Supplied by ALAT



Helial Cold Box




Main Compressor



Figure 6 : CSD 82 View

Recovery Compressor



Oil removal & Gas Management System

Schedule

2013 March: ALAT cryoplant at TRIUMF


2013 October: commissioned

Successful Final Design Review concluded 2012 May15

Cryo-plant specs

The plant shall demonstrate 3 modes:

- Mixed Mode: >130W @ 4,6K and 242 L/h rising level
- Pure Liquefaction: 288 L/h at 4.6K in the Dewar rising level
- Pure Refrigeration: 600W at 4.6K in the Dewar (expected)





Other major components

- He buffer tanks: delivery expected 2013 Jan
- Dewar in hand; will widen neck
- He Purifier in design stage
- Cold Helium Distribution System: tender mid 2012
- 2K sub-atmospheric components:
 - Pumps: tendere mid 2012
 - He heaters: prototyping




- Tanks rated 15 Bara
- Capacity $\sim 113 \text{ m}^3$ each





15 Ω Resistive heater prototype

High Power RF staging: 5mA, 25 MeV in 2014




30 kW IOT Transmitter

- IOT transmitter will be used for EIJN beam test 2013 Jan;
- RF input coupler conditioning (10kW) 2012 March onward



- 2011 June: Tube operated tube in excess of 30kW
- 2011 July: Successful acceptance tests: ran cw at 30 kW for 24 hours, at 25kW for 40 hours and at 20 kW for 7 days without trip.
- Now running routinely


Coupler Conditioning Stand in VECC test area




1.3 GHz 290 kW klystron & HVPS procurement

Require 200kW cw for EACA (2-cavity) cryomodule

- 2011 Aug: 290kW Klystron ordered from CPI, USA
- Coordinated purchase with Helmholtz Zentrum Berlin
- 2012 June: Final design review
- 2012 Nov: klystron factory test




Klystron predicted CW Power Output vs. RF Input Drive



600kW High Voltage Power Supply

- 2012 Feb: Tender issued
- 2012 March: Tender closed
- Vendors under consideration




Conclusion

- **Outstanding Progress Across All Areas**
- **Buildings Construction – on schedule for 2013 April**
- **Injector Cryomodule beam test – on schedule for 2013 March**
- **Accelerator Cryomodule beam test – on schedule for 2014 June**

Cavity & HOM Damping


- 9 cell cavity
- Inner 7 cells TTF geometry
- Modified end groups for larger coupler & HOM damping



Two 50 kW Cornell/
CPI coupler per cavity



HOM frequency spectrum and
shunt resistance for 9-cell cavity



- HOM damping target set by Regenerative BBU (2-pass)
- 39/35/48 mm iris geometry gives the lowest maximal $(R_d/Q) \times Q_L$
- Damping by SS ring on coupler end, CESIC ring on tuner end
- All modes $(R_d/Q) \times Q_L < 2 \times 10^6 \text{ ohm}$

EINJ: Injector Cryomodule Detailing

