

# **The KOMAC Accelerator Facility**

**Yong-Sub Cho for the KOMAC team**

**May 15, 2013**



**한국원자력연구원**  
Korea Atomic Energy Research Institute



## KOrea Multi-Purpose Accelerator Complex

- PEFP
- Facility Introduction
- 100MeV Linac Commissioning
- Applications
- Conclusion



## ❖ Proton Engineering Frontier Project

- Period: 2002.7 ~ 2012.12 (10.5 Year)
- Total Budget: 314.3 B Won (1USD ~ 1.1 kWon)
  - ✧ Gov: 183.6 B, Gyeongju: 118.2 B, Industry: 12.5 B
- Gyeongju city provides land for KOMAC.

## ❖ Project Goals

1. Development of 100 MeV Proton Linac
2. Development of Beam Utilization Tech.
3. Development of Tech. for Industrial Application





KTX Station  
To Seoul ~2 Hour

KOMAC phase 2 Site  
650m(L) X 400m(W)

Access Road 1,100m(L) x 20m(W)

KOMAC site  
450m(L) X 400m(W)

- Land & Electricity for Future
- Easy Access from Seoul, Busan, and Pohang
- Good for sightseeing

Seoul-Busan  
Expressway



# Main Facilities


Yong-Sub Cho IPAC2013



- **Site:** 180,000 m<sup>2</sup>
- **Building:** 39,843 m<sup>2</sup>  
(Accelerator and beam line 14,426 m<sup>2</sup>)
- **Electricity :** 154kV, 20MVA



# Buildings and Utilities









## Features of KOMAC 100MeV linac

- 50 keV Injector (Ion source + LEBT)
- 3 MeV RFQ (4-vane type)
- 20 & 100 MeV DTL
- RF Frequency : 350 MHz
- Beam Extractions at 20 or 100 MeV
- 5 Beamlines for 20 MeV & 100 MeV

Output Energy (MeV)	20	100
Max. Peak Beam Current (mA)	1 ~ 20	1 ~ 20
Max. Beam Duty (%)	24	8
Avg. Beam Current (mA)	0.1 ~ 4.8	0.1 ~ 1.6
Pulse Length (ms)	0.1 ~ 2	0.1 ~ 1.33
Max. Repetition Rate (Hz)	120	60
Max. Avg. Beam Power (kW)	96	160




# Radiation Shielding & Radiation License



## Target Room Shielding

- Iron: 0.9m
- Concrete: 2.4m

Area	$\mu\text{SV/hr}$	Facilities
High level Radiation Area	$DL > 12.5$	- Accelerator Tunnel - Beam Line Room
Radiation Worker Area	$0.25 < DL \leq 12.5$	- Klystron Gallery (Klystron, AHU, CCW HX room) - Beam Utilization Facility (Beam Experimental Hall, Test Prep., ACU room)
General Public Area	$DL \leq 0.25$	- Office & General Laboratory



**License for Operation of Radiation Generating Facility**  
- issued by NSSC (Jan.2012)





- **2.45GHz Microwave ion source:**
  - Extraction energy: 50 keV
  - Peak beam current: 30 mA
  - Compact with one solenoid
  - Operation modes:  
DC or Pulsed  
with IGBT switch
- **LEBT :**
  - 2 solenoids
  - 2 steering magnets








## ● Specifications

- frequency : 350MHz
- energy : 3MeV
- peak current : 20mA
- 4 vane type
- dipole stabilizer rods
- iris coupling
- length : 3.2 m
- duty : 24%







## ● Specifications

- frequency : 350MHz
- energy : 3~20 MeV
- peak current : 20 mA
- electromagnetic Q
- FFDD
- 4 tanks
- driven by  
a 1-MW klystron
- duty : 24%



2013/05/14






## ● Specifications

- a bending magnet at 20MeV to extract beam to 20MeV target rooms
- matching section with two cavities

20MeV Linac




100MeV Linac





## ● Specifications


- frequency : 350MHz
- energy : 20 ~ 100 MeV
- peak current : 20 mA
- electromagnetic Q
- FFDD
- 7 tanks
- driven by  
a 1.6-MW klystron  
per each tank
- duty : 8%







- RCCS (Resonant Control Cooling System) for temperature control of DT.
- Operation Range 21~33 °C, Temperature Control  $< \pm 0.1^{\circ}\text{C}$
- 11 sets for 11 DTL tanks







- 9 Klystrons : 1 for RFQ, 1 for 20-MeV DTL, 7 for 100-MeV DTL
- Penetration wave guides were installed in building construction.








- 4 Modulators (Each modulator drives 2 or 3 klystrons)
- Output peak power 5.8 MW, duty 9%, pulse width 1.5 ms, repetition 60Hz







- Initial operation : 1 beam line for 20 MeV and 1 beam line for 100 MeV
- Beam lines will be prepared according to the beam needs from users.








## ● Specifications

- 5 rooms for 20 & 5 rooms for 100 MeV
  - : 1 room for 20 & 1 room for 100MeV will be available on June.
- In air irradiation
- beam widow : 0.5mmt 300mm $\Phi$  AlBeMat




Proton beam




# Digital LLRF system



- Goal : 1% in amplitude, 1 degree in phase
- hardware : Commercially available FPGA board
- software : PI implemented in FPGA and EPICS OPI



LLRF OPI based on EPICS




Phase variation during HPRF operation





- EPICS based system was developed for linac and beam lines.
- Radiation monitoring system & personal safety interlock system are prepared.



EPICS based OPI



Main Control Room




# Status of Commissioning

Yong-Sub Cho IPAC2013




Up to now

- Initial goal : 100 MeV 1kW in June



20MeV  
~1mA peak







- **Basic science studies**
  - Bio- and medical
  - Space, detectors etc
- **Radio isotope production**
- **Nuclear fission and fusion material damage test**
- **ISOL target test**





- **KOMAC has the 1<sup>st</sup> phase facility through the PEFP.**
  - **Land, buildings, utilities and 100-MeV linac**
  - **The linac is under commissioning**
  - **Beam service in 2 target rooms will start from July.**
  
- **For the plan,**
  - **Preparation of all target rooms for many applications**
  - **GeV extension for pulsed neutron source**
  - **And many accelerators for many purposes**



An aerial rendering of the KOMAC industrial and research complex. The facility is a large, rectangular area with a grid-like layout of roads and buildings. It includes several large industrial buildings, a central area with a swimming pool and a fountain, and various smaller structures. The complex is surrounded by green fields and a dense forest of mountains in the background. The sky is blue with some clouds.

**KOMAC will be**

谢谢!