

# Beam Commissioning of PAL-XFEL

**J.-H. Han for PAL-XFEL Commissioning Team**  
**Pohang Accelerator Laboratory**

# PAL-XFEL Project

- Project start in 2011
- Building construction in 2012~2014
- Accelerator components installed in 2015
- Beam commissioning from 14th April 2016 to end 2016
- XFEL user facility from early 2017




# PAL-XFEL Parameter

10 GeV electron linac + two undulator beamlines at Phase-1

Undulator line	Hard X-ray line	Soft X-ray line
Wavelength	0.1 (0.06) ~ 0.6 nm	1 ~ 4.5 nm
Electron beam energy	4 ~ 10 GeV	3.15 GeV (branched)
Undulator type	Planar	Planar (+EPU in future)
Undulator length	5 m	5 m
Undulator period	26 mm	37 mm
Undulator min. gap	8.3 mm	10 mm
Number of segments	20	7 (+EPU in future)
Repetition rate	60 Hz	


Two more HX beamlines and one more SX beamline planned

# PAL-XFEL Layout





# 10 GeV Achieved

On 25th April (12th day of beam commissioning)



beam energy measured




# Timeline of Commissioning

- **RF conditioning:** Nov 2015 ~
- **First beam from gun** (6 MeV): 14 April 2016
- **Acceleration to injector end** (130 MeV): 14 April
- **Acceleration to BC1** (350 MeV): 18 April
- **10 GeV acceleration to linac end:** 25 April
- **Injector & linac parameter optimization:** April ~ May
- **Undulator:** May ~ June
- **Free electron laser (SASE) at HX:** June ~
- **SASE at SX:** late 2016
- **User service:** early 2017~ (120 days user run in 2017)


# Injector

- 1.5 cell S-band photocathode gun
- Two 3 m long S-band accelerating columns
- Focusing solenoids
- Drive laser
- Beam with 200 pC & 137 MeV




# Injector Laser


<Laser system layout>



<UV laser profile>




transverse profile



longitudinal profile




# RF Gun





- Operates at 2856 MHz
- Developed at PAL
- Designed for 120 Hz at 120 MV/m
- 4 holes at full cell for field symmetry
- 2 RF probes

stored power  
in the gun





reflected power  
from the gun





# Photocathode

- Back plane of the gun cavity made from polycrystalline copper
- Diamond machining with surface roughness  $\sim 100$  nm
- Vacuum  $< 10^{-10}$  mbar measured with the nearest gauge
- Quantum efficiency  $\sim 2.5 \times 10^{-4}$  measured at 200 pC, 120 MV/m






# Gun RF Phase Scan

## Phase scan for bunch charge




## Phase scan for beam energy




# Laser Cleaning of Cathode


- Laser cleaning using IR laser pulse with 130  $\mu\text{m}$  FWHM size
- $3 \times 3$  mm cathode area irradiated without RF power with 100  $\mu\text{m}$  step
- Quantum efficiency maps taken for 4 x 4 mm area



Before cleaning  
vacuum  $< 1 \times 10^{-10}$  mbar



After 2nd cleaning  
with 1.16 mJ IR laser  
vacuum  $\sim 5 \times 10^{-10}$  mbar  
recovered after cleaning





After 4th cleaning  
with 1.39 mJ IR laser  
vacuum  $\sim 1 \times 10^{-9}$  mbar  
recovered after cleaning

QE  $\sim 2.5 \times 10^{-4}$




# Gun Laser BBA

- Drive laser position aligned on cathode center (gun RF field center)
- Gun field reduced from 120 to 90 MV/m for laser align (no dark current on gun screen) and gun solenoid switched off
- Beam position at gun screen while scanning RF gun phase around  $110^\circ$  from 0-crossing for RF focusing and large phase delay




# Gun Solenoid BBA



While scanning gun solenoid current from 80 to 115 A at 90 MV/m gun field, beam position movement measured at gun screen  
After 3rd trial, we aligned the gun solenoid so that the beam position movement within 50  $\mu\text{m}$  at the screen




# Beam Shape in Injector




Drive laser



After gun








After L0



After laser heater

# Emittance at Injector

laser  
 $\phi \sim 1$  mm  
 $l \sim 3$  ps



Best measured projected transverse emittance so far:


$\epsilon_x \sim 0.8x$  mm mrad

$\epsilon_y \sim 0.4x$  mm mrad


(200 pC, 137 MeV, 95% rms)




# Phase Scan for On-crest



L1-02 phase scan




X-band phase scan




# Linearization using X-band


Linearization of longitudinal phase space using X-band cavity



S-band curvature shown




S-band curvature linearized




# Bunch Compression at BC1


Bunch compression by applying  $-15^\circ$  off-crest phase at L1



Not compressed  
(S-band curvature linearized)





3x compressed  
(S-band curvature linearized)



# Ongoing Commissioning – 1

Fine Tuning of Injector Parameters  
→ Minimum Transverse Emittance


- Gun gradient
- Gun solenoid field
- Gun phase
- L0 gradient
- Drive laser shaping



# Ongoing Commissioning – 2

## BBA for Injector and Linac

through cavities and magnets using BPMs and correctors



# Tasks to be done for Linac

- Beta matching & dispersion correction
- Beam energy feedback
- Bunch compression feedback at BCs
- Beam position feedback at beam transport line

# Tasks to be done for Undulator

- BBA thought undulator line (quads, correctors)
- Undulator & phase shifter steering table
- Undulator height alignment with beam
- Undulator K measure vs gap
- Phase shifter gap optimization
- Spontaneous emission
- SASE saturation

# Summary

- PAL-XFEL construction including accelerator components installation ready
- Beam commissioning started on 14 April 2016
- 10 GeV acceleration succeeded on 25 April
- Injector and linac parameter optimization ongoing
- Undulator commissioning to start soon
- User service to start from early 2017



# Thank you for attention!

The PAL-XFEL commissioning team  
thank the PAL staffs  
for their magnificent contribution  
to the beam commissioning.