

Status and Performance of ORNL Spallation Neutron Source Accelerator Systems

Y. Kang, A. Aleksandrov, D. Anderson, M. Champion, M. Crofford, J. Galambos, B. Han, S-H. Kim, S-W. Lee, L. Longcoy, K. Magda, M. Middendorf, J. Moss, V. Peplov, C. Peters, C. Piller, M. Plum, J. Price, R. Saethre, J. Saunders, A. Shishlo, J. Schubert, M. Stockli, C. Stone, R. Welton, D. Williams, A. Zhukov

SNS, Oak Ridge National Laboratory


May 10, 2016

IPAC 2016

Busan, Korea

ORNL is managed by UT-Battelle
for the US Department of Energy

A. Aleksandrov




Outline

- SNS Overview
- SNS Accelerator Complex Operation and Performance
- Accelerator Systems and Components
 - Ion Source, RFQ, MEBT, DTL, CCL, and SCL
 - Subsystem Status, Performances, Issues, and Improvements
- SNS Upgrade Project
 - Proton Power Upgrade (PPU) with Second Target Station (STS)
- New Beam Test Facility
- Summary

Spallation Neutron Source

- SNS is a pulsed neutron source, driven by a 1.4 MW SRF proton accelerator to be the leading facility for neutron scattering research
- SNS was funded through DOE-BES at a cost of 1.4 B\$ and constructed with a collaboration of six US DOE laboratories
- Since accelerator complex was fully commissioned in 2006, operation has been ramping up to 1.4 MW beam power and 1GeV beam energy, the design goals
- Future upgrades of the beam power and the energy have been planned with the addition of the second target station



Outline

- SNS Overview
- **SNS Accelerator Complex Operation and Performance**
- Accelerator Systems and Components
 - Ion Source, RFQ, MEBT, DTL, CCL, and SCL
 - Subsystem Status, Performances, Issues, and Improvements
- SNS Upgrade
 - Proton Power Upgrade (PPU) with Second Target Station (STS)
- New Beam Test facility
- Summary

The SNS Provides the World's Most Intense Pulsed Neutron Beams


Front-End:

(ion source, LEBT, RFQ, MEBT)

Produces a 60 Hz 1-msec long, chopped, H⁻ beam pulses



LEBT chopper system makes ~ 300 nsec gaps



Accumulator Ring:
Compress 1 msec long
pulse to 700 nsec

H⁻ stripped to p

Injection


Extraction

~ 700 nsec

~ 957 MeV


HEBT

Liquid Hg Target



Power and Energy on Target

History: from 01-Nov-2006 to 26-Apr-2016



- SNS has demonstrated it is capable of sustained operation at power levels up to 1.4 MW
- Failures of the Target and the MEBT systems lowered the system reliability


SNS Performs Well relative to Design Parameters

	Design	Best Ever	Routine Operation
Kinetic Energy [GeV]	1.0	1.07	0.957
Beam Power [MW]	1.4	1.427	0.8-1.40
Linac Beam Duty Factor [%]	6	6	5
Modulator/RF Duty Factor [%]	8	8	7
Peak Linac Current [mA]	38	42	36
Average Linac Current [mA]	1.6	1.6	1.1-1.49
Linac pulse length [msec]	1.0	0.98	0.975
Repetition Rate [Hz]	60	60	60
SRF Cavities	81	80	79-80
Ring Accumulation Turns	1060	1020	1008
Peak Ring Current [A]	25	26	14.5-25.8
Ring Bunch Intensity	1.5×10^{14}	1.74×10^{14}	$0.87-1.5 \times 10^{14}$
Ring Space Charge Tune Spread	0.15	0.14	0.09-0.16

Outline

- SNS Overview
- SNS Accelerator Complex Operation and Performance
- **Accelerator Systems and Components**
 - **Ion Source, RFQ, MEBT, DTL, CCL, and SCL**
 - **Subsystem Status, Performances, Issues, and Improvements**
- SNS Upgrade
 - Proton Power Upgrade (PPU) with Second Target Station (STS)
- New Beam Test facility
- Summary

SNS Linac RF Cavities are Powered by 92 Klystrons



RFQ	DTL	CCL
1 x	6 x	4 x
402.5 MHz	402.5 MHz	805 MHz
2.5 MW	2.5 MW	5 MW

SCL
81 x 805 MHz, 550 kW
1:1 control for operational flexibility

- Ten years of operation reveals some increases of component failures. Most of the 92 klystrons have exceeded the specified life of 50,000 operational hours. Operational management of klystrons is now focused on promoting long tube life for the aging.

Ion Source (H^-) and LEBT


- The SNS H^- ion source is a cesium-enhanced, multicusp RF ion source generates 65 keV H^- ions to the RFQ with an internal antenna.
- Updates and corrective maintenance of the front-end systems on the ion source, LEBT, RFQ, and MEBT have been significant since commissioning.
- The beam current from the ion source has increased steadily (20 mA → 35 mA)
- 2 MHz pulsed tube amp running at > 60 kW capable up to 80 kW 8% duty cycle is used with 13 MHz 300 W CW to the antenna for ignition
- Antenna failure rates reduced significantly due to improved quality control; there has been only one antenna failure during past 12 months.
- The two-lens, electrostatic LEBT is 12-cm long. The second lens is split into four quadrants to steer, chop, and blank the beam. The short electrostatic LEBT has been operating reliably with a routine change-out of LEBT that is done twice a year due to insulator coating which seems to be a good plan to maintain the reliability.



Production Ion Source

RFQ


- **3.7 m long 4 vane type structure operating at 402.5 MHz and 550 kW structure power deliver 2.5 MeV**
- **The beam transmission through the RFQ decreased and has been a concern in the front-end system for the higher beam power operation through the years.**
- **The beam transmission has been measured lower than the design minimum of 80% lately. In the summer of 2013, the RFQ was retuned after observation of field tilt. Then, the transmission increased from 72% to 77% for a 45 mA input current which was still not satisfactory.**
- **A new spare RFQ has been built and fully RF tested. After validation of the performance of the new RFQ with beam, the existing RFQ will be replaced with the spare.**



MEBT

- **Performs longitudinal beam compression after 2.5 MeV beam through RFQ**
- **RF amplifiers were upgraded SSA each running at 25 kW @ 402.5 MHz, 8% duty cycle (6 modules per amplifier)**


15 Modulators in 3 Different Configurations Power 92 klystrons in the Linac



- All klystrons are powered by IGBT based High Voltage Converter Modulator (HVCM) each rated to 11MW peak at 8% duty cycle
- An HVCM feeds 2 or 3 klystrons in DTL, 1 klystron in CCL, and 10-11 klystrons in SCL



15 Modulators in 3 Different Configurations Power 92 klystrons in the Linac




Some of the many HVCM improvements:

- Improved boost capacitor performance by finding better capacitors and 12 – 18 month scheduled replacements (the failures of boost capacitors have been a key vulnerability of HVCM)
- The pulse flattening developed with 17.8 to 23.0 kHz frequency modulation is to be deployed (Currently ≤5% pulse droop operating in open-loop)
- New IGBT gate driver circuits and addition of IGBT snubbers



SNS SCL Cavities and Cryomodules


- 81 6-cell cavities in 23 cryomodules
 - 11 medium-beta CM
($\beta=0.61$ cavities)
 - 12 high-beta CM
($\beta=0.81$ cavities)
- $E_a=15.9 \text{ MV/m}$ at $\beta=0.81$ & $Q_o>5\text{E}9$
- One klystron per one 6-cell cavity operation
- SNS has built first own high- β cryomodule commissioned in March 2012



Current SCL operating gradients


- Average Eacc of medium and high beta cavities: 12 MV/m, 13 MV/m respectively

HB CM developed in-house and installed in slot 20 in summer 2012



SCL

- The availabilities have been 99.5% for the SRF system alone and 98% for the SCL including RF, HVCM, control, vacuum, etc. during the last 5 years. Average trip (downtime): < 1 trip/day (<5 min./day)
- Some cavities have shown performance degradation in FY15 and FY16-1
- Recovery of cavity performance to previously attained operating gradients
 - RF conditioning starting from low repetition rate
 - Several cavities recovered in February 2016
 - Thermal cycling
 - CM18 and 20d recovered during last maintenance down
 - So far, thermal cycling is successful except two cavities
 - More cryomodules are waiting for thermal cycling
 - Rework of some cryomodules to be done
- After studies with the plasma processing, in-situ plasma processing technique has been developed
 - First processing performed on CM19 in January with good results
 - Processing to be performed on more cavities in the linac tunnel



Performance improvement for the four cavities in cryomodule after in-situ plasma processing.


Outline

- SNS Overview
- SNS Accelerator Complex Operation and Performance
- Accelerator Systems and Components
 - Ion Source, RFQ, MEBT, DTL, CCL, and SCL
 - Subsystem Status, Performances, Issues, and Improvements
- **SNS Upgrade Project**
 - **Proton Power Upgrade (PPU) with Second Target Station (STS)**
- New Beam Test Facility
- Summary

Beam Power Upgrade to 2.8 MW (with Second Target Station)

- The STS concept proposed here is a short pulse, long wavelength configuration driven with a 10 Hz, 470 kW proton beam
- Beam power: 1.4 MW → 2.8 MW
- Beam energy: 1 GeV → 1.3 GeV
- Linac: 60 Hz (FTS: 50 Hz, 2 – 2.3 MW, STS: 10 Hz, 0.47 MW)
- RFQ output current: 33 mA → 46 mA, peak
 - (26 mA → 38 mA, average macro-pulse current)
- Chopping fraction 0.70 → 0.82
 - "J. Galambos (ed.), Technical Design Report Second Target Station, ORNL/TM-2015/24 (2015). "
- Biggest changes in the accelerator systems will be adding 7 HB cryomodules with 28 cavities and 3 HVCMS
 - Warm sections already in place with space for 9 CM's in the linac
 - Higher cavity performance (16 MV/m) than first production is needed

Proton Power Upgrade – 1.3 GeV



7 Cryomodules:

- CM25
- CM27
- CM28
- CM29
- CM30
- CM31
- CM32

5 HPRF Transmitters:

- 5 Transmitter Racks
- 10 HV (3-hole) Tanks
- 5 Transmitter Cooling Carts
- 28 LLRF Systems
- 28 Klystrons
- 28 Circulators
- 28 Water Loads
- 28 Waveguide Runs
- 112 Directional Couplers
- 14 Chase Inserts

3 High Voltage Modulators:

- 3 Utility Transformers
- 3 SCR Cabinets
- 3 Control Racks
- 3 Modulators (HVCMS)
- First two HVCMS:
 - 9 klystrons each
- Third HVCMS:
 - 10 klystrons

Supporting Infrastructure:

- AC Power Distribution
- Cable Routing
- Water Systems
- Marshalling Panels

Developments Impacting PPU/STS

SCL

- Fabricate seven new high beta cryomodules in-house and install to increase beam energy
- Install higher power input coupler for cooler FPC (inner conductor) needed to prevent end group heating
 - Klystrons will be operating to 700 kW to support higher beam current
 - High RRR end group material for cooling and/or thermal grounding of end groups
- Simplify the SRF cavity design based on lessons learned
 - No HOM couplers, no piezo tuners, etc.
 - Same Saclay tuners to be used as first production
- Perform plasma processing for other existing cavities


HVCM

- 3 additional modulators required for PPU upgrade
- Modify boost transformers in warm linac to achieve required higher output voltages, especially for 3.0 MW klystrons for DTL
- Reduction to a 9:1 klystron:modulator ratio for first 18 new cavities (2 HVCMs), 10:1 ratio for the last 10 new cavities at reduced power levels

Outline

- SNS Overview
- SNS Accelerator Complex Operation and Performance
- Accelerator Systems and Components
 - Ion Source, RFQ, MEBT, DTL, CCL, and SCL
 - Subsystem Status, Performances, Issues, and Improvements
- SNS Upgrade Project
 - Proton Power Upgrade (PPU) with Second Target Station (STS)
- **New Beam Test Facility**
- Summary

SNS Beam Test Facility (BTF) Layout



Beam Test Facility (BTF) Construction Completed



- The BTF has been built with the beam properties identical to the SNS front-end system
- The BTF will be used to validate the performance of the new spare RFQ, to study ion source improvements, and to support neutron moderator development and six-dimensional phase space beam measurements for SNS.
- The new RFQ has been fully RF tested and will be validated in the BTF with beam and will be installed in the SNS linac.

Summary

- After commissioning, SNS accelerator systems have been being tuned up for sustained operation at 1.4 MW beam power
 - SNS showed its capability of sustained operation at power levels up to 1.4 MW
 - System availability goal > 90% is still to be achieved with improvement of Target
- Ion source and LEBT in the front-end have been significantly updated to deliver more beam current with improved reliability
- Reliability of HVCMS have improved significantly
- Study started for PPU with STS project
 - 2.8 MW total beam power and 1.3 GeV beam energy
 - SCL will be updated with 28 more high-beta cavities (in 7 new cryomodules)
 - SNS has built own high- β cryomodule (March 2012) that was successful
 - 3 HVCM will be added for SCL
- A new BTF has been built and ready for test with beam through RFQ
 - Perform full beam test to validate the performance of the new RFQ, to study ion source improvements, and other developments for SNS