

Status and future upgrade Plan of J-PARC Accelerators

Michikazu Kinsho

J-PARC Center Japan Atomic Energy Agency (JAEA)

Transmutation Experimental Facility (TEF)-Phase II

3 GeV Rapid Cycling Synchrotron (RCS)

Materials & Life Science Facility (MLF)

400 MeV H- Linac

Main Ring

Neutrino Beam Line

to Kamioka (NU)

Hadron Experimental Hall (HD)

J-PARC Accelerators

High-intensity proton accelerators

Linac

- length: 249 m
- energy: 400 MeV
- beam extracted to RCS

and (Transmutation Experimental Facility)

□ Rapid-Cycling Synchrotron (RCS)

- circumference: 348 m
- energy: 3 GeV
- beam power: 1 MW (0.5 MW)
- beam extracted to MR and Materials and Life Science Experimental Facility

□ Main Ring (MR)

- circumference: 1,568 m
- energy: 30 GeV
- beam power: 750 kW/100kW (395 kW/ 42kW)
- beam extracted to Neutrino Facility, or Hadron Facility







History of beam delivery from Accelerators to Users

History of beam delivery to the MLF



History of MR beam power



Linac Status

Linac energy upgrade

Energy upgrade (from 181 MeV to 400 MeV) by installing ACS in 2013.



Linac energy upgrade

Energy upgrade (from 181 MeV to 400 MeV) by installing ACS in 2013.



Linac peak current upgrade

Ion Source and RFQ has been replaced in 2014

lon source



Status of the Ion Source and RFQ



RCS Status

1-MW trial at RCS

Experimental condition

- Injection beam condition
 - Injection energy : 400 MeV
 - Peak current : <u>45.0 mA</u>
 @ the entrance of RCS
 - Pulse length : 0.5 ms
 - Chopper beam-on duty factor : 60%
 ▶ 8.41 x 10¹³ particles/pulse, corresponding to <u>1010 kW</u> at 3 GeV
- Injection painting parameter; 100π transverse painting + full longitudinal painting

Circulating beam intensity over the 20 ms from injection to extraction measured by CT

8.41 x 10¹³ ppp : 1010 kW-eq.



There is no terrible beam loss, but some unnecessary beam losses was detected at the arc sections.

Beam loss in the high dispersion area (arc sections)



- The beam losses observed for the 944-kW (blue) and 1010 kW (red) beams can be interpreted as *longitudinal beam loss arising from a distortion of the RF bucket caused by the beam loading effect*.
- Such beam particles suffer from large momentum excursion and most of them are lost in the high dispersion area, not at the collimator section located in the dispersion-free section.
- This type of longitudinal beam loss has to be cured by beam loading compensation.
 But then the anode power supply in the RF system had no enough margin to complete sufficient beam loading compensation for the 1-MW beam.

We carried out the anode power supply upgrade using the 2015 summer maintenance period.

Result of the 1-MW trial in Oct. 2015

BLM signals at the high dispersion area (arc sections)



Longitudinal beam loss was well mitigated as expected by sufficient beam loading compensation after the RF power supply upgrade.

Beam loss at the collimator

BLM signals at the collimator section (dispersion-free straight section)



- ✓ The beam loss at the collimator section mainly arises from *foil scattering during injection*.
- The other beam loss, such as space-charge induced beam loss, was well minimized by injection painting even for the 1-MW beam.
- ✓ The remaining beam loss for the 1-MW beam was estimated to be < 0.1% (< 133 W in power) << Collimator limit of 4 kW.</p>
- ✓ RCS beam commissioning made big progresses in this beam test.
- 1MW operation is still ready !¹⁶

MR Status

Typical Operation Status for Fast Extraction



Slow extraction

After the long shutdown for 1 year and 11 months, beam operation resumed for users in the hadron experimental facility.



Mid –term plan of MR

• *FX*

The high repetition rate scheme is adopted to achieve the design beam intensity, **750** *kW*.

Cycle time will be increased from 2.48 s to 1.3 s by replacing PS's for main magnet (B, Q, S), RF cavities and some injection and extraction devices.

• SX

The beam power will be gradually increased toward **100** kW watching the residual activity.

Parts of stainless steel ducts are replaced with titanium ducts to reduce residual radiation dose.

Upgrade scenario

JFY	2014	2015	2016	2017	2018	2019	2020
	Li. current upgrade		New PS buildings				
FX [kW] (study/trial)	240-320	> 360	400	450	700	800	900
SX [kW] (study/trial)	-	30-40	50	50-70	50-70	~100	~100
Cycle time PS	2.48 s		Mass production		1.3 s	1.3 s	1.25 s
New magnet PS	R&D	Large scale prototype	S insta	allation/test			
High gradient rf system 2 nd harmonic rf system VHF cavity	Manufacture, installation/test						
		-			\rightarrow		
Ring collimators		Add.collim ators (2 kW)		Add.colli mators (3.5kW)			
Injection system	Kicker PS improvement, Septa manufacture /test						
Large aperture QDT					\rightarrow		
SX Local shields			Local sh	ields			
Ti ducts Ti chamber	Beam ducts		ESS				21

Requirements for New power supplies

• High repetition rate : 1.3 sec. cycle

- ✓ Issue : large power variation @ AC main grid
 - ✓ Not allowed by Electric Power Company
 - Energy recovery with Bank capacitor

Precise output current

- Issue : Noise in current measurement, Switching ripple
 - Low noise current measurement and digital control system
 - High switching frequency (> kHz)

New power supplies for 1.3 s cycle



Effect on the Energy Consumption



Energy transfer control between the capacitor bank and magnet has been succeeded.

R&D of new power supplies for 1.3 s sycle

Y. Kurimoto et. al. IEEE. TNS

24 bit A/D board and Isolation between analog and digital components





Succeed to measure current at ppm level

Low noise current measurement and digital control system

- 24 bit A/D board and Isolation between analog and digital components
 - Succeed to measure current at ppm level
- Digital control board for tracking error correction
 - Tracking error can be reduced down to 10⁻⁵

The test have enabled the manufacture to produce all components of new PSs



Mass production has been started.

High impedance rf system

A new type of the magnetic alloy (MA) core, FT3L(made by Hitachi Metal), is adopted to increase shunt impedance of the rf cavity. The core is processed by annealing with magnetic field.

Comparison of field gradient of rf cavities for proton synchrotron.



RF frequency (MHz)

- Performance of cavities depends on core materials: **ferrite** and **MA**.
- J-PARC already achieved very high field gradient.



- The first **FT3L** cavity has been operated stably for 20 month in the MR.

Four new FT3L cavities was installed in the 2015 summer shutdown. 25

Injection and FX septum systems

New injection septum magnet I and FX low field septum for the high repetition rate operation have been manufactured and now tested.



Injection septum magnet



FX low field septum magnet

To realize 1.3 sec. cycle operation, improvements of devices (PSs, RF cavity, Injection septum, ...) have been performed on schedule according to the upgrade scenario

Long-term upgrade plan

• Linac

for TEF

✓ Repetition : 50Hz for TEF

for higher power operation of RCS ✓ Peak current : >60mA ✓ Pulse length : >0.6ms

• RCS

Beam power : > 1MW

• MR

Beam power for neutrino : > 1MW

Transmutation Experimental Facility (TEF)





- R&D for technology to reduce the environmental impact of radioactive waste with neutrons
- Experimental facility of Accelerator Driven System (ADS) is now being designed with great efforts

Transmutation Experimental Facility (TEF) Current Condition of Facility Site





- R&D for technology to reduce the environmental impact of radioactive waste with neutrons
- Experimental facility of Accelerator Driven System (ADS) is now being designed with great efforts

Transmutation Experimental Facility (TEF)

250k)

H- Beam

TEF-P: Transmutation Physics Experimental Facility

Purpose : Reactor Physics Category : Critical Assembly Proton Power : 400MeV-10W Thermal Output : Less than 500W

TEF-T: ADS Target Test Facility

Multipurpose Area

Purpose : Material Irradiation Category : Radiation Application Proton Power : 400MeV-250kW Target Material : Lead-Bismuth

Critical Assembly

Laser Source

Charge exchange by Laser + foil 30

Spallation Target

Layout plan of L-TEFBT and L3BT line





LINAC status and Upgrade for TEF

TEF : Transmutation Experimental Facility

	status	design	plan		
peak current	30mA	50mA	complete		
energy	400MeV	400MeV	complete		
repetition	25Hz	50Hz	 1st stage : Upgrade of cooling water system ➢ Beam power limits ~133kW with beam chop 2nd stage : Upgrade of power supply of klystron ➢ Beam power up to 250kW without beam 		
beam			chop Installation of New devices		
separation			R&D started		

Long-term upgrade plan

 Linac for TEF
 ✓ Repetition : 50Hz for TEF

> for higher power operation of RCS ✓ Peak current : >60mA ✓ Pulse length : >0.6ms

RCS Beam power : > 1MW

• MR

Beam power for neutrino : > 1MW

Operation with beam intensity > 1MW in the RCS Space charge

Laslett tune shift at injection energy:

$$\Delta v = -\frac{r_p n_t}{2\pi\beta^2 \gamma^3 \varepsilon B_f}$$

$$r_p: \text{ classical radius of proton}$$

$$n_t: \text{ no. of protons in the ring}$$

$$\beta, \gamma: \text{ relativistic parameters}$$

$$\varepsilon: \text{ transverse painting emittance}$$

$$f_f: \text{ Bunching factor (0.4)}$$

E _{inj} (MeV)	ррр (х10 ¹³)	Beam power at E _{ext} (MW)	Δν	Comment
181	4.5	0.54 ←	-0.53	Achieved
400	8.33	1	-0.33	Achieved
400	10.8	1.3	-0.43	Reasonable
400	13.3	1.6	-0.53	Reasonable

Tune footprint simulated by ORBIT

Beam instability issue for high power operation

Source: Transverse impedance of the RCS extraction kicker magnets



Operation with beam intensity exceeding 1MW in RCS

Beam intensity ~1.5 MW is a next goal

Second neutron production target station is also under discussion.

Challenges:

• Linac

Peak current : >60mA Macropulse width : > 0.6ms

• RCS

Reinforcement of RF system using the FT3L cavity Charge stripping and instability due to kicker impedance will be issues but within reach.

Long-term upgrade plan

 Linac for TEF
 ✓ Repetition : 50Hz for TEF

> for higher power operation of RCS ✓ Peak current : >60mA ✓ Pulse length : >0.6ms

• **RCS** Beam power : > 1MW

• MR

Beam power for neutrino : > 1MW

High Intensity beam study of MR

High power trial with two bunches at the new betatron tune



Bunch number	repetition period (sec)	Beam power (kW)	Beam loss (kW)	Notes
2	2.48	132	0.42	achieved
8	2.48	530	1.7	estimation
8	1.3	1000	3.2	estimation

The MR has capability to reach 1MW with the high repetition rate operation₃₉

Summary

Status and operation

- Achieved beam power in user operation : 500 kW for the MLF users 395 kW and 42 kW for the T2K experiment and HD users, respectively.
- High power demonstration :
 - 1 MW eq. beam was achieved in the RCS
 - 132 kw eq. beam with two bunches in the MR
 - The MR has a capability to reach beam power ~ 1 MW with faster cycle operation (1.3 sec.).

• Mid-term upgrade plan

 The design power of 750 kW for the FX, and 100 kW for the SX will be achieved after the replacement of main magnet power supplies.

• Lon-term upgrade plan

- Linac : repition 50Hz for TEF, peak current > 60mA, pulse length > 0.6msec
- RCS : beam power : ~ 1.5MW
- MR : beam power for the FX : > 1MW