



Beam Commissioning of the HIE-ISOLDE post-accelerator

Jose Alberto Rodriguez, BE-OP-ISO, CERN on behalf of the HIE-ISOLDE project







- Introduction
- Beam commissioning stages
- Beam characteristics
- Physics campaign
- Summary and future plan



- Located at CERN, ISOLDE is one of the world leading research facilities in the field of nuclear physics
- Protons from the PS Booster at 1.4 GeV are transferred to the facility
- Approximately 50% of the protons accelerated in the PS Booster are delivered to ISOLDE (~ 3E13 protons per pulse every 1.2 s or multiples)



 $\models p (proton) \rightarrow ion \rightarrow neutrons \rightarrow \overline{p} (antiproton) \rightarrow \rightarrow \rightarrow proton/antiproton conversion \rightarrow neutrinos \rightarrow electron$

LHC Large Hadron Collider SPS Super Proton Synchrotron PS Proton Synchrotron

AD Antiproton Decelerator CTF-3 Clic Test Facility CNCS Cem Neutrinos to Gran Sasso ISOLDE Isotope Separator OnLine DEvice



CERN

CERN

- Radioactive Ion Beams (RIBs) are produced when the protons impact in one of the two targets in the facility
- The RIB of interest is selected in one of the separator lines (GPS, HRS) and transported to a low energy experimental station for study
- Alternatively, the RIB can be accelerated after it is accumulated and transversely cooled in the REXTRAP and charge bred in the REXEBIS









and a state of the

2.85 MeV/u

The REX normal conducting linac:

- Beam from the charge breeder with 5 keV/u energy is accelerated to 2.85 MeV/u
- Seven RF structures: f = 101.28 MHz (except for 9gap) with 10% maximum duty cycle





The HIE-ISOLDE super conducting linac and HEBT lines:

- Phase 1a of HIE-ISOLDE completed in 2015: first cryomodule (5 x QWR cavities, 1 x SC solenoid) and two high energy transfer lines
- QWR: copper substrate with niobium sputtered surfaces ($\beta_g = 0.103$, $E_{acc} = 6$ MV/m)
- Cryomodule: common insulation and beam vacuum





- Introduction
- Beam commissioning stages
- Beam characteristics
- Physics campaign
- Summary and future plan



REX diagnostics box:

- $\checkmark\,$ Beam commissioning started in June after the renewing many systems in REX
- ✓ Beam from the charge breeder was accelerated to 0.3 MeV/u in the RFQ and used to recommission the REX diagnostic box

CERN

✓ Beam transmission through RFQ was measured for different power levels and used to determine the operational settings of the RF structure



First HIE-ISOLDE diagnostics box:

- ✓ First beam with 0.3 MeV/u energy to FC and to the silicon detector in July
- Systematic tests confirmed that all the devices behave as planned
- BI expert applications also tested



CERN



Phasing of the RF systems in REX:

- ✓ Commissioning of the other RF systems started in July
- ✓ Several problems were discovered and solved during this time (phase shifters, cooling...)
- New operational settings for all RF cavities were determined using the silicon detector (necessary because of work on LLRF and connection to new reference line)
- ✓ Beam at 2.85 MeV/u ready for HIE-ISOLDE beam commissioning at the end of August



CERN

First High Energy Beam Transfer (HEBT) line:

- $\checkmark\,$ Beam drifted through CM1 to the end of the first HEBT line in mid-September
- ✓ Overall transmission ~ 76% after a few hours optimization. Transmission through REX ~ 88% (note DC beam before RFQ). Other losses concentrated in the dipoles (probably due to longitudinal beam mismatch)

FC	Transmission	\checkmark No mayor problems found with optical elements. FCs			
XRFQ.FC20	1.00	and silicon detectors			
XLN2.0300	0.88	✓ First observations seem to indicate that the optics Miniball			
XLN4.0300	0.90	model works well (systematic tests pending)			
XT00.0400	0.88	Station			
XT00.0700	0.84	✓ No need for strong steering (i.e. no alignment			
XT00.1000	0.84	problems)			
XT01.0400	0.76				
XT01.0900	0.76				
XLN2.0300 SRF Cavities SRF Cavities SRF Cavities	0000 ENTX XTV100000 CM2 (2016	VITATION OF THE AND OF			
JOLDE	Jose Alberto Rodriguez – IPAC 2016 – Busan, Kore				

SRF cavities:

- $\checkmark\,$ First acceleration using SRF cavities at the beginning October
- ✓ Two weeks of work to optimize the SRF systems (power and stability)
- ✓ All cavities phased using a silicon detector at the end of the tunnel ($^{12}C^{4+}$ at 4 MeV/u)

CERN

 $\checkmark\,$ Accelerated beam transported to the end of the first HEBT line by mid-October



Second High Energy Beam Transfer (HEBT) line:

- ✓ First beam to the end of the line in November (after physics campaign with RIBs was completed
- \checkmark Transmission to the end of the line ~ 79% without optimization
- ✓ No mayor problems found with optical elements and FCs
- ✓ First observations seem to indicate that the optics model works well
- \checkmark No need for strong settings for correctors
- ✓ Stripping foils tested (one of the six broken)







- Introduction
- Beam commissioning stages
- Beam characteristics
- Physics campaign
- Summary and future plan



Beam Characteristics:

Beam energy and energy spread:

Several options for beam energy measurements:

- Si detector: Time consuming / uncertainty in the absolute calibration
- Dipole magnet: Need fairly high beam current / uncertainty in the absolute calibration
- RF cavities: Need precise knowledge of the operating phase (i.e. time consuming)
- TOF system: Will be used together with the previous methods (will be available in 2016)
- Si detector after dipole magnet: Low beam current is sufficient / relatively quick measurements (will be available in 2016)





Jose Alberto Rodriguez – IPAC 2017 – Busan, Korea



Beam Characteristics:

Beam contamination:



- The silicon detectors can be used to estimate the beam contamination from the charge breeder
- We can use this information to adjust the separator and the timing of the TRAP / EBIS
- Unfortunately, this type of measurements can be very time consuming and cannot be conducted as often as desired
- The silicon detector are not useful to measure isobaric contamination from the target since the total energy is very similar





Beam Characteristics:

Time macrostructure:

• The limits in the maximum power in the SRF cavities and out of the temporary 9gap amplifier introduced constrains in the time macrostructure. Problem with couplers has now been solved and the new 9gap amplifier has been installed. It should not be an issue in the future.



 Slow extraction from the charge breeder using the new timing hardware was tested and used during the physics campaign

 New software tools are currently being developed and will allow better control of the time macrostructure this year







Jose Alberto Rodriguez – IPAC 2017 – Busan, Korea





- Introduction
- Beam commissioning stages
- Beam characteristics
- Physics campaign
- Summary and future plan



Physics Campaign:

- Short (5 weeks), but very useful, physics campaign at the end of 2015 (more information at TUPMR023)
- Two RIBs (⁷⁴Zn, ⁷⁶Zn) to Miniball experimental station
- Two energies: 4 MeV/u and 2.85 MeV/u (due to heating problem of the SRF couplers)
- In addition, stable beam were used for beam commissioning of the experimental stations

Beam	То:	Energy [MeV/u]	Time [hours]
²² Ne ⁷⁺	Miniball	2.85	~ 60
⁷⁴ Zn ^{25+,21+}	Miniball	2.85 / 4	~ 90
⁷⁶ Zn ²²⁺	Miniball	2.85 / 4	~ 90
¹⁴ N ⁴⁺	Scat. Ch.	2.85 / 4	~ 2
¹² C ⁴⁺	Scat. Ch.	4	~ 2
¹³³ Cs ³⁹⁺	SPEDE	2.85 / 4	~ 110









- Introduction
- Beam commissioning stages
- Beam characteristics
- Physics campaign
- Summary and future plan



Jose Alberto Rodriguez - IPAC 2017 - Busan, Korea

Summary and Future Plan:

- Cryomodule CM1 and two HEBT lines installed in 2015
- Hardware commissioning followed (problems with SRF couplers found)
- A reduced beam commissioning program was completed. Due to time constrains, focus only on items critical systems to start the physics campaign. Work still needed in:
 - Systematic tests of optical elements and some of the diagnostic devices
 - Better characterization of beam properties
 - Optics model benchmarking
- Short Physics campaign (5 weeks) completed in 2015





TUPMR023



