

SRF Operation at XFEL: Lessons Learned After More Than One Year



Denis Kostin

MSL, DESY, Hamburg, Germany

for the European-XFEL Accelerator Consortium

IPAC 2019, Melbourne, May 20th, 2019.



European XFEL – a great success story



Outline

1. INTRODUCTION

- Eu-XFEL: General Layout
- Eu-XFEL: SRF Technology
- Eu-XFEL: Timeline
- RF Power Distribution
- Fundamental Power Couplers

2. REACHING THE DESIGN ENERGY

- Reaching the Design Energy
- SRF Cavities: Performance
- SRF Cavities: Limits
- SRF Cavities: Operation


3. OPERATION

- Tunnel Radiation
- Cryogenics
- Cavity Piezo Drivers
- Eu-XFEL: Current Operation

4. OUTLOOK

- Possible CW Upgrade
- Summary

Eu-XFEL: General Layout



Length of accelerator: 1500 m

Length of facility: 3400 m


101 Cryo Modules (97 installed now)

8 SRF 9-cell cavities per CM

Beam pulse length	μs	600
Repetition rate	Hz	10
Max. # of bunches per pulse		2700
Min. bunch spacing	MHz	4.5
Bunch charge	nC	≤ 1
max. beam current	mA	4.5
Nominal beam DF	%	0.65
Average Gradient	MV/m	23.6


- 650 μs long RF pulse in gun and accelerating modules
- Operation energy 8 – 16.5 GeV
- LLRF takes into account electron beam induced fields
- Energy jitter over bunch train <10⁻⁴
- No beam losses

Eu-XFEL: SRF Technology




Cavity type	TESLA
Number of cells	9
Cavity length	1.035 m
Operating frequency	1.3 GHz
R/Q	1030 Ω
Accelerating Gradient	20 – 31 MV/m
Quality factor, Q_0	$\geq 10^{10}$
Q_{ext} (input coupler)	4.6×10^6 ($10^6 - 10^7$)
Operating temperature	2 K


Eu-XFEL: Timeline




Eu-XFEL: Timeline




Eu-XFEL: Timeline




Eu-XFEL: Timeline




Eu-XFEL: Timeline




Eu-XFEL: Timeline



Eu-XFEL: Timeline



RF Power Distribution



All CM were cold-tested in **Accelerating Module Test Facility (AMTF)**


Cavities operational limits:

- Quench
- Field Emission (X-ray monitor threshold 10^{-2} mGy/min)
- 31 MV/m – power limit (administrative)

E_{acc} measurement error ~10%

European XFEL


Cryomodule Waveguide Distribution System (WDS) tailored to match forward power to each cavity within practical limits



Fundamental Power Couplers

- Main coupler design for the Eu-XFEL linac is well established and proven.
- All of 25 Eu-XFEL RF stations 776 couplers are conditioned except
 - 4 FPCs were not conditionable and showing T70K overheating – shorted / disconnected from the RF source.
- Couplers operation stable since over two years of Eu-XFEL operation – no other shorted (not used) couplers.
- FPC cold window temperature (T70K) increase with high RF power on some couplers shows, that proper coupler cooling could be rather critical – currently it is not a problem for the operation.
- FPC conditioning (warm and cold) is important for the linac operation.

- **Eu-XFEL fundamental power coupler** consists of warm, cold and waveguide main parts. Coaxial coupler is made of copper and copper plated (10/30μm) stainless steel with two alumina TiN coated ceramic windows.
- Motorized antenna tuning ($\pm 10\text{mm}$) allows for Q_{load} adjustment ($10^6..10^7$). Operating Q_{load} is 4.6×10^6 .
- All FPCs are pre-conditioned up to 1 MW pulsed RF power up to 400 μs RF pulse length and up to 500 kW with 1.3 ms pulse, repetition rate is 10Hz.



Reaching the Design Energy

Maximum Gradient Task Force (MGTF)

- start on 21.06.2017
- 20 of 20 stations in L3 investigated
- 1 of 3 stations in L2 investigated
- 40 investigations done

17.6 GeV at TLD on 12.7.2018


- With 2.6 GeV after BC2
- Further investigations followed

17.6 GeV at TLD on 18.7.2018


- With design energy of 2.4 GeV after BC2

Energy gain due to MGTF: 1.9 GeV

- Nearly 11% of final energy
- Equal to about 2.4 L3 RF stations



SRF Cavities: Performance



Reached an average of 93.6% of AMTF performance

SRF Cavities: Limits



- Quench (soft quenching)
- Field emission (500 $\mu\text{Sv/h}$ neutrons)
- Power / missing piezo operation
- Other limitations → solved
 - Waveguide sparking
 - Too low klystron power
 - Cryogenics
- In some cases, there are potential energy gains from further optimization of the WDS

Detuned cavities (31.01.2019)

Reason of detuning	Number of cavities
After AMTF tests	5 (~0.6%)
After tests in XTL (coupler)	4 (~0.5%)
MGTF	12 (~1.5%)
Sum	21 (~2.7%)

- A4.M4.C4 coupler problem: T70K
- A6.M3.C1 cavity problem: high FE/X-rays (10MV/m limit)
- A6.M3.C5 MGTF: too much power to this cavity (higher V_{VS} without)
- A6.M3.C6 MGTF: too much power to this cavity (higher V_{VS} without)
- A7.M1.C7 MGTF: too much power to this cavity (higher V_{VS} without), degradation
- A7.M2.C3 MGTF: too much power to this cavity (higher V_{VS} without)
- A7.M2.C7 cavity problem: high FE/X-rays (11MV/m limit)
- A8.M4.C1 MGTF: too much power to this cavity (higher V_{VS} without)
- A8.M4.C4 MGTF: too much power to this cavity (higher V_{VS} without)
- A8.M4.C5 MGTF: too much power to this cavity (higher V_{VS} without)
- A10.M1.C3 cavity problem: low Eacc BD (no FE) (13MV/m limit)
- A12.M2.C2 MGTF: too much power to this cavity (higher V_{VS} without)
- A12.M3.C8 MGTF: too much power to this cavity (higher V_{VS} without)
- A12.M4.C1 coupler problem: T70K
- A14.M3.C5 MGTF: high cryo-losses (already at AMTF observed)
- A16.M2.C1 coupler problem: T70K
- A17.M3.C7 MGTF: too much power to this cavity (higher V_{VS} without)
- A18.M4.C4 wrong WG-distribution 31MV/m (FE limit at 23MV/m)
- A20.M4.C1 coupler problem: T70K
- A21.M3.C4 cavity problem: low Eacc BD (no FE) (14MV/m limit)
- A21.M4.C2 MGTF: too much power to this cavity (higher V_{VS} without), degradation


SRF Cavities: Operation



- Possible to reach 17.6 GeV.
- Quench limits of 76 cavities were determined operationally (1.3 per CM).
- 12 cavities are detuned to optimize the performance (max. energy).
- 1 RF station (A14) is limited by the cryo-load.
- 3 RF stations (A6, A9, A12) are limited by the tunnel radiation.
- Reached 93.6% AMTF test performance – within the error margins.

Tunnel Radiation

- Radiation (gamma and neutrons) measurement is an important tool to understand the machine operation.
- There are different techniques – Rad-FET, TLDs, BLMs, Gamma and Neutron Sensors – including a remote-controlled robot system (MARWIN).
- MARWIN measurement examples
- Radiation in the linac is almost entirely RF related (Field Emission / Dark Current).
- Radiation due to beam particle loss can be seen in collimation sections as expected
- Only three RF stations (A6, A9, A12) are limited by the radiation at max.energy.
- No degradation – radiation values do change with cavities accelerating gradient and tuning – understandable.



Cryogenics

- Eu-XFEL cryo-plant (4K) 2 years in the operation since successful commissioning

- the performance results comply within the error margin with the specification: 2K cryo-losses set to ~5 W/CM, measured <6.3 W/CM at 17.5GeV

- The 2K pressure stability is excellent

- 0.6% peak-to-peak, 0.3% RMS
- The cascaded pressure regulation in combination with the automatic heat load compensation improved the pressure stability significantly
- Even dynamic procedures (power ramping, RF-shutdown, etc.) can be compensated quite well without affecting the pressure stability drastically


- There are some problems with bearings of the cold compressor motors

- New motor design is being developed, improvements are being done as well
- The recovery effort after a cold compressor shutdown (e.g. bearing failure) is minimized by the automation and cryogenic system configuration

Eu-XFEL cryogenic system:

- | | |
|--------------------------|----------------------|
| 671 control valves | >100 level sensors |
| 2647 temperature sensors | 433 regulation loops |
| 800 pressure sensors | > 22000 records |
| 212 flow sensors | > 220000 properties |


2K cryogenic heat load at 17.5 GeV (July 2018)



Cavity Piezo Drivers

Test run at A24

Klystron forward power of arm1 and arm2



Vector Sum (VS)

Piezo driver electronics installed at all RF stations


Cable checking is scheduled now, then...

- Cable fixing
- Commissioning
- AC/DC feedback operation

Test operation at A24 since end of April



- Less forward power required for same VS voltage (-1.1%)
- Detuning kept stably around 0 Hz

Detuning



Eu-XFEL: Current Operation

run with 1 or 2 RF-stations off-beam as a spare



Current beam energy: 14 GeV – 2 RF-stations off-beam (user operation).

Next planned beam energy: 16.5 GeV – 1 RF-station off-beam (user operation).


European XFEL

Possible CW Upgrade

- Continuous Wave (CW) mode is the origin of the SRF accelerator technology. Eu-XFEL project was based on the Linear Collider (LC) technology (TESLA) operating in the pulsed RF power mode (10 Hz / 650 μ s beam pulse). Many FEL user experiments will get an advantage (or become possible) with CW mode operation.
- Possible beam parameters: 25 μ A (100 pC and 250 kHz) with 8 GeV (CW) and 12 GeV (long-pulse: $\sim$ 100ms).
- Several CMs were successfully tested in CW and long-pulse mode in CMTB at DESY.

The Upgrade Plan:

1. Replace the front-end cryomodules (17x)
 - Larger cooling capability
 - CW optimized cavities
2. Install CW capable RF sources
 - 1 $\times$ IOT per RF station
3. Double the cryo plant (cost driver)
 - 2.5 $\rightarrow$ 5kW
4. CW electron gun (preferred option: SRF gun).
5. The former front-end cryomodules can be installed at the end of the linac to lengthen L3 (+4 RF stations), no further action required in L3 (>1km).
6. The upgraded XFEL would be capable of short pulse, long pulse AND CW operation.



Summary

1. European XFEL operates since over two years – without major problems.
2. Important project milestones – **17.5 GeV** and **27000** bunches/s (no lasing) – achieved.
3. Current beam energy: 8 – 16.5 GeV (user operation).
4. Initial achieved station voltages were consistent with production module tests projections including errors.
5. MGTF carefully studied and tuned each station individually, eventually achieving >90% of projected estimate.
6. Currently running with 21 cavities detuned - 12 detuned as a result of the MGTF studies.
7. Tunnel radiation (dark current): currently considered safely within limits, but will continue to monitor/study.
8. Focus now on maintaining identified max. limits operationally - root causes analysis of trips, etc.
9. A possible CW operation upgrade is under study.

Acknowledgements

I want to express my gratitude to all colleagues from the European-XFEL Consortium contributing to and supporting the machine building, commissioning and successful operation.

Special thanks to my DESY colleagues: J.Branlard, W.Decking, M.Omet, T.Schnautz and N.Walker.



Thank You !