

Developments & Future Plans at ISAC/TRIUMF

P. W. Schmor
ISAC/TRIUMF


LINAC 2004

Tuesday, August 17, 2004

ISAC – an RIB ISOL FACILITY for Nuclear Astrophysics

- Driver
 - ◆ 500 MeV H- Cyclotron
- Target
 - ◆ Thick Target of a refractory element at an elevated temperature (2000C) which undergoes Nuclear Reactions [Spallation, Fragmentation, Fission] when Bombarded by the 500 MeV Protons
- Ion Source
 - ◆ Ionizes Target Volatiles
 - (High Radiation Environment with Impure Gas Input)
- Isotope Selector
 - ◆ Separates a Desired Isotope from Many in the Ionized Beam
- Accelerator
 - ◆ Provide Variable Energy Beams of a Selected Isotope (from Various Masses) to Experimental Stations
 - ◆ Experiments use Reverse Kinematics for Nuclear Astrophysics
 - Isotope is Projectile on H or He Target
 - Energy is Appropriate for Stellar Temperatures

SCIENCE OF RARE ISOTOPES



ISAC I & II

- ISAC (ISOL + ACCELERATORS)

- ◆ ISAC-I

- Funded in 1995
 - Low Energy
 - * **$E \leq 60 \text{ keV}$ & $A_{\text{max}} \approx 240$**
 - First RIB Experiment in November 1998
 - High Energy (Accelerated)
 - * **Variable Energy from 0.15 to 1.5 MeV/u for $q/A \geq 1/30$**
 - First Beam in December 2000

- ◆ ISAC II

- Funded in April 2000
 - Civil Funded April 2001
 - **Variable Energy from 1.5 to 6.5 MeV/u for $A \leq 150$**
 - First Beam Scheduled for Late 2005 (4.3 MeV/u)

- ◆ Completion & Upgrade Proposed for 2005-2010

ISAC II = ISOL &
POST-ACCELERATORS

High-Energy Experiments
ISAC I (2001)

Experiments
ISAC II

2007

High β
SCRF

2005

Med β
SCRF

S2

Low β
SCRF

S1

DTL2

DTL1

RFQ

$A/q \leq 30$

ISAC I
Low-Energy
Experiments
(1998)

Ion
Beam

2006

CSB

Isotope
Separator

Heated Tube
Ion Source

high-energy
proton beam

Thick/Hot
Target

Beam
Dump


Production
Accelerator

TRIUMF
500 MeV
Cyclotron
DRIVER

BEAM LINES AND EXPERIMENTAL FACILITIES

ISAC - I & ISAC - II EXPERIMENTAL HALLS

— Recent
— Future





TRIUMF Driver

500 MeV H⁻ Cyclotron

Provides Simultaneous,
Independent, Variable Energy,
Protons to Multiple Locations


Routinely Accelerates 275 μA


Capable of 400 μA



ISAC I


ISAC at TRIUMF






REMOTE HANDLING for ISAC TARGETS, ION SOURCES & MODULE COMPONENTS

HOT CELL AND REMOTE CRANE FOR MODULE & TARGET SERVICING



THERMAL ION SOURCE




ISAC I TARGET DEVELOPMENT





♦ ISOL Target Area

- * **Shielded for 100 μ A of 500 MeV Protons on Uranium**
- * **Dec 17, 1999 – 100 μ A on Mo Target**
- * **May 25, 2001 - 40 μ A on Nb Target**
- * **July 23, 2001 - 40 μ A on Ta Target**
- * **Oct 18, 2001 – 15 μ A on SiC Target**
- * **Sept 9, 2002 – 40 μ A on TiC Target**
- * **Nov 11, 2002 – 45 μ A on SiC Target**
- * **Fall 2005 – Actinide Target Tests**

ISAC TARGET EXPOSURE 2003

ISAC Beam Schedules 103, 104
Integral of Target Exposures






30Na & 74Rb Yield
vs Driver Current

SCHEMATIC of TIME DEPENDENCE for DRIVER CURRENT with HIGH POWER, ISOL TARGET TEMP. & RELEASED YIELD

- Optimum Driver Current Pulse Lengths
 - ◆ $\gg$ Half-life, Diffusion & Effusion Times
 - ◆ $\gg$ Thermal Time Constants
 - Typically several minutes
- Driver Current Stability
 - ◆ Operating Temperature is Determined by Driver
 - Yield, Effusion, Diffusion Determined by the Driver Current
 - ◆ With Significant Beam Heating
 - $\Delta RIB/RIB > \Delta I/I$



ISAC Mass Separator

Mass Separator Hall

$$\Phi = 135^\circ$$
$$\rho = 1000 \text{ mm}$$

High Voltage Platform


Pre-separator

First Image Slit

500 MeV 100 mA
protons

West Target Station


East Target Station




Ion Sources

- THERMAL
 - ◆ Primary Ion Source on 2 target modules
- RLIS (resonant laser ion source)
 - ◆ Initial online test scheduled for Sept. 2004
 - ◆ Initial user ^{62}Ga beam planned for Dec. 2004
- ECRIS (electron cyclotron resonance ion source)
 - ◆ Online & offline Commissioning of 2.45 GHz ECR
 - ◆ Online commissioning reproduces Ne ionization efficiency measured offline on ion source test stand
 - ◆ Initial experimental run with 8π & GPS in June 2004
 - ◆ Next experimental user scheduled for November 2004
- FEBIAD
 - ◆ Offline prototype nearly ready for testing
 - ◆ Online commissioning planned for Spring 2005
 - ◆ Goal is start experimental campaign in Summer 05
- OLIS [Off Line Ion Source for Stable Beams]
 - ◆ Microwave Ion Source for volatiles & metallic sputtering
 - ◆ Surface Ion Source Installed & Commissioned
 - ◆ Installation of heavy ion ECRIS under discussion


TRILIS - hardware development -



TiSa broadband tuning




TiSa doubling ϵ up to 25%




(status 04/2004)

3 TiSa lasers, 2 frequency doubling units in operation
beamtransport into ICB completed, off-line LIS start


ECR1 & TARGET MODULE



Drawing of the ECR with the magnetic field superimposed





ISAC EXPERIMENTAL HALL





LOW ENERGY STATIONS

β -NMR, OSAKA,
POLARIMETER




LTNO



ISAC-I Accelerator

- ❑ OLIS
 - ❑ Stable beams
- ❑ LEBT
 - ❑ All-electrostatic (2 keV/u)
 - ❑ 11.8 MHz multi-harmonic pre-buncher
- ❑ 35 MHz cw RFQ
 - ❑ $E=2 \rightarrow 153$ keV/u
 - ❑ $A/q \leq 30$
- ❑ MEBT
 - ❑ Stripping foil
 - ❑ 35 MHz rebuncher
- ❑ 105 MHz cw Variable Energy DTL
 - ❑ $E=0.15-1.53$ MeV/u
 - ❑ $A/Q \leq 6$
- ❑ HEBT
 - ❑ Diagnostic section
 - ❑ 11.8/35 MHz rebunchers

ISAC ACCELERATOR



ACCELERATOR TECHNOLOGY


DTL TANK 2




RFQ



DTL TRIPLET





INR
BUNCH
ROTATOR





MEBT REBUNCHER





COMPLETED DRIFT TUBE LINAC



Nuclear Astrophysics Experimental Stations



Beams Delivered to ISAC Experiments




ISAC II


ISAC-II Building




The ISAC - II Accelerator Floor




Linac Distribution




Refrigerator Room



Compressor Room




Buffer



ISAC II Components

- CSB [ECR based Charge State Booster]
 - ◆ Operating on Ion Source Test Stand with 1+ injection
- “S” Bend HEBT
 - ◆ 4 Dipoles in Magnet Measuring Lab
- He Liquifier
 - ◆ Ordered Compressors & liquifier system
 - ◆ Installation & Commissioning this Fall
- Cryogenic Distribution System
 - ◆ Warm system tendered
 - ◆ Cold System being Specified
- Experimental Hall HEBT
 - ◆ Concept not finalized
- Accelerator
 - ◆ First cryomodule cooled to LHe
 - ◆ Two additional cryomodules in fabrication
 - ◆ All 20 medium beta cavities fabricated





Charge State Booster & Mass Selector Location In Mass Separator Cave


TOLERANCES UNLESS OTHERWISE SPECIFIED		3	SEP 20-93	Preliminary optics corrected		Se	RB
FRACTIONS	$\frac{1}{2}$	REV	DATE	LOC	REVISION DESCRIPTION	BY	APP
DECIMALS	JUL .1						
	JUL .1						
ANGULAR	$\frac{1}{2}$						
SURFACE FINISH	μ in						
ALL DIMS IN INCHES		TRIUMF 4000 WESSBROOK MALL VANCOUVER, BRITISH COLUMBIA CANADA V6T-2A5 CANADA'S NATIONAL MESON FACILITY					
DESIGNED		Proposal 3					
DRAWN <i>Edw. Ant...</i>		CSB in Mass-sep hall					
CHECKED		ISAC					
REF DWGS:							

CSB Status

- CSB is producing highly charged ions on ion source test stand
 - ◆ Ar⁷⁺ & 8+ observed
 - ◆ Transmission losses due to background gas observed
 - Improvements to vacuum pumping planned
- ECR2 installed as 1+ injector
- Initial final optics installation scheduled for winter 2005 shutdown
- Final installation of CSB scheduled for winter 2006
- Commissioning planned for spring 2006


ISAC-II SC Linac

ISAC-II Cryomodules



Section	β_0 (%)	f_{RF} (MHz)	No.	E_a (MV/m)
Low β	4.2	70.7	8	5
Med β	5.7	106	8	6
	7.1	106	12	6
High β	10.4	141	20	6

Medium Beta Cavities



(a) Nominal ($\beta=7.1\%$)

(b) Flat ($\beta=5.7\%$)

freq=106.08MHz

$E_p/E_a \approx 5$


$H_p/E_a \approx 100 \text{ G}/(\text{MV}/\text{m})$

$U/E_a \approx 0.09\text{J}/(\text{MV}/\text{m})^2$

$\Gamma \approx 19\Omega$



High Beta Frequency Optimization [THP14]

Medium Beta Cryomodule





Medium Beta Cryomodules Assembly

- First (3rd in dtl line) Assembled & Successfully Cold Tested with rf Power, tuners, rf control system & Solenoid [MOP86]



Medium Beta Cryomodules Alignment


- Alignment Movement During Temperature cycling Measured with Wire Position Monitoring System & Telescope [MOP89]



Medium Beta Cryomodules

RF Tuning


RF Tuning Successfully Commissioned [MOP86, THP16, TUP77]



Medium Beta Cryomodules

RF Coupling

- RF Coupler Successfully Commissioned [MOP92, MOP88]



LINAC, Cryomodules & Cryogenics Status

- LINAC
 - ◆ First medium beta Cryomodule being Cold Tested
 - ◆ Liquid Helium test confirmed heat load estimates
 - ◆ Wire Position Monitor meets requirements
 - ◆ Solenoid field does not impact cavity performance
 - ◆ Rf frequency could be 'locked' with control system
- Cryomodules
 - ◆ #2 [1] & #3 [2] are being fabricated & assembled
- Cryogenics
 - ◆ Compressors & Liquifiers ordered
 - Commissioning scheduled for Fall 2004
 - ◆ Warm Distribution System Contract let
 - ◆ Cold Distribution System
 - Initial system will be installed in 2005

2005 -2010

ISAC Issues

- Cyclotron Stability & Sparking requires Improvement
 - ◆ RIB production requires stable driver beam
 - ◆ Cyclotron Refurbishing Planned
- Target Development Incompatible with Production & Science Program
 - ◆ High Power Target Development Facility Required
 - ◆ Must Be Independent of Experimental Program
- OLIS [off line ion source for stable beams]
 - ◆ Initially installed for commissioning & tuning accelerators
 - ◆ Has become essential to science program
 - ◆ Needs to have a more universal ion source
- 5 Year Proposal Submitted to Canadian Federal Government
 - ◆ Endorsed by Government Appointed Peer Review
 - ◆ Decision Expected in Feb 2005

ISAC PROPOSAL FOR NEXT 5 YEAR PLAN

- OPERATE ISAC I & II
- DEVELOP NEW TARGETS, BEAMS & ION SOURCES
- COMPLETE ISAC II
 - ◆ ACHIEVE DESIGN SPECIFICATIONS
 - Medium Beta Section Completed by end of 2005
 - * 4.3 MeV/u (Initial Experiments Begin)
 - CSB Commission early in 2006
 - * Extends Mass Range for Isotopes with $q/a = 1/7$
 - High Beta Section Completed in late 2007
 - * 6.5 MeV/u (3 Operating Experimental Stations & Beam Lines)
 - Low Beta & DTL2 Completed in late 2009
 - * CSB only required to provide $q/a = 1/30$ for difficult isotopes
 - * Provides full Mass Range & Multiple Charge Acceleration
- 2nd DRIVER BEAM & TARGET STATIONS
 - ◆ INSTALL TARGET/ION SOURCE DEVELOPMENT STATION
 - ◆ PERMITS FUTURE MULTIPLE SIMULTANEOUS EXOTIC BEAMS
- MULTIPLE SEPARATOR STATION CAPABILITY
 - ◆ SEPARATED RIBs TO MULTIPLE SIMULTANEOUS EXPERIMENTS
- ALLOW FOR FUTURE DOUBLE ACCELERATOR CHAIN

High Power Target Development


- Beam line 4 Extraction Front End Upgraded for 200 μA Operation
- New Underground Beam line to ISAC.
- ISAC Target Hall Extended to North

1. High Power Target Station


- ◆ Target Development
- ◆ Mass Separator & Yield Station

2. High Power Beam Dump

- ◆ Used for tuning Cyclotron for High Current Operation



ISAC at TRIUMF



ISAC Beyond 2010?

ISAC at TRIUMF

