

## THE DRIFT TUBE WELDING ASSEMBLY FOR THE LINAC4 DRIFT TUBE LINAC AT CERN

I. Sexton, A. Cherif, Y. Cuvet, G. Favre, J-M. Geisser, F. Mirapeix (DMP, Spain), S. Ramberger, S. Sgobba, T. Tardy, CERN, Geneva, Switzerland



27th Linear Accelerator Conference, LINAC14, International Conference Centre in Geneva, Switzerland on 1-5 September 2014.



The fabrication of the Linac4 Drift Tube Linac (DTL) required the welding assembly of 108 drift tubes (DT) which has been undertaken at the CERN workshop. The design of the DTL is particular in that it was

purposely simplified to avoid any position adjustment mechanism for drift tubes have been designed with tight tolerances and parts have been assembled with an optimised welding procedure. Two re-machining stages have been introduced in order to compensate for welding distortions.





The second stage concerns the assembly of the stem to the body. To ensure the required perpendicularity between the axis of the drift tube and the stem of ±1 mrad, a specific tooling fixture is used to hold and position the two elements.



future adjustments.

## Metrology

During the manufacturing and assembly phases, 29 geometrical tolerances were inspected for each body.









The third and final stage concerns the assembly of the cover to the body, carried out after the insertion of the PMQ.





Contact: <u>ian.sexton@cern.ch</u> (EN/MME/FW)