



Status of the European XFEL



Hans Weise, DESY




on behalf of the European XFEL Accelerator Consortium
work supported by the respective funding agencies of the contributing institutes; for details please see <http://www.xfel.eu>

Superconducting Cavities

2





One Kilometer of Cold Linac







- Photon energy 0.3 - 24 keV
- Pulse duration ~ 10 - 100 fs
- Pulse energy few mJ
- Superconducting linac 17.5 GeV
- 10 Hz (27 000 b/s)
- 5 beam lines / 10 instruments
 - Start version with 3 beam lines and 6 instruments
- Several extensions possible:
 - More undulators
 - More instruments
 -
 - Variable polarization
 - Self-Seeding
 - CW operation



Accelerator Complex with Challenging Parameter Set


Electron beam energy	17.5 GeV
Bunch charge	0.02 - 1 nC
Peak current	2 - 5 kA
Slice emittance	0.4 - 1.0 mm mrad
Slice energy spread	4 - 2 MeV
Shortest SASE wavelength	0.05 nm
Pulse repetition rate	10 Hz
Bunches per pulse	2700
Pulse length	600 μ s



State of the Art 3 Stage Bunch Compression

6

3 stage bunch compression: flexible and less sensitive to noise from RF system



$\sigma_{\sigma} = 2 \text{ mm}$
 $I_{\text{peak}} = 50 \text{ A}$
 $\sigma_E = 0 \%$
 $E = 130 \text{ MeV}$


$\sigma_{\sigma} = 1 \text{ mm}$
 $I_{\text{peak}} = 100 \text{ A}$
 $\sigma_E = 1.5 \%$
 $E = 130 \text{ MeV}$

$\sigma_{\sigma} = 0.1 \text{ mm}$
 $I_{\text{peak}} = 1 \text{ kA}$
 $\sigma_E = 1 \%$
 $E = 600 \text{ MeV}$

$\sigma_{\sigma} = 0.02 \text{ mm}$
 $I_{\text{peak}} = 5 \text{ kA}$
 $\sigma_E = 0.3 \%$
 $E = 2400 \text{ MeV}$



harmonic system






bunch compressor




beam diagnostics

X-ray Beamlines for Different Wavelengths with Different Time Structures




- 2 hard x-ray undulators and beam transport with 4 instruments
- 1 soft x-ray undulator and beam transport with 2 instruments
- all undulators planar and tunable




The Suite of Instruments


8




FXE Femtosecond
X-ray
Experiments




HED High Energy
Density Science




SPB Single Particle &
Biomolecules



MID Materials Imaging &
Dynamics



SQS Small Quantum
Systems




SCS Spectroscopy &
Coherent Scattering





More about experiments: <http://www.xfel.eu>

European XFEL Layout

9



Injector in Operation – First Beam in 12/2015



Dump

Transverse Deflecting Structure

Spectrometer

Diagnostic Section

Laser Heater

3.9 GHz Module

1.3 GHz Module

Gun




RF Gun Commissioning

a short beam diagnostics section upstream of a standard



XFEL 1.3 GHz accelerator module followed by a 3.9 GHz module

11




XFEL Injector Status as of 6/2016

(end of commissioning run)





- Injector installation finalized in Q4/2015
- 3.9 GHz module installed in 9/2015
- Injector cool-down started beginning of 12/2015
- First Beam on December 18th , 2015
- Successful commissioning during Q1/2016
- Emittance measurements done on a routine basis;
- Projected emittance as expected (1...1.5 mm mrad)
- Full bunch train length (2700 bunches) reached and beam stopped in injector beam dump
- Transverse Deflecting System operated
- Slice emittance measurements give 0.5 mm mrad for 500 pC
- Laser heater commissioning started




Slice Emittance Measurements with fast kickers and off-axis screens

13




slice emittances can be measured
and evaluated within 20 seconds
using fast kickers and off-axis



- center slices are reproducibly measured
- 0.6 mm mrad horiz. at 500 pC and 53 MV/m gun gradient
- the smallest slice emittance measured was 0.5 mm mrad at 60 MV/m



Slice Emittance Measurement Based on Quad Scan

Tomographic reconstruction of the hor. phase space scan



- Results from an **optics scan** with 5 quads and 17 different beam optics. The beam was analyzed on the last screen in the diagnostics section.
- The obtained data was used to **calculate slice emittances** and to reconstruct the hor. phase space of all bunch slices using a tomographic algorithm (MENT*). *MENT: Maximum entropy algorithm

Slice emittances along the bunch. This measurement led to a core slice emittance of 0.4 mm mrad. The gun was operated at 53 MV/m.




Tomographic reconstruction of the horizontal phase space for the center slice.


Emittance Measurements along Bunch Trains

15


- The TDS also allows to measure slice emittances along the bunch train.
- The behavior of the slice emittances along the bunch is reproducible over the bunch train. The smallest slice emittance is measured for the core of the bunch.
- The projected emittance and the mismatch parameter are almost constant over the bunch train.




- Projected emittance and mismatch parameter measurements for both planes along the bunch train.



Full Bunch Train Operation







- A dedicated injector beam dump system allows for full bunch train operation
- **24/7 operation** is used to test many operation procedures
- **Operation crew** is getting trained




Warm Beam Line Sections

Dogleg & BC0 in Front of Linac L1





- All girders are pre-assembled in clean rooms
- Tunnel installation requires local clean rooms

A real top-view of the Dogleg Section




Warm Beam Line Sections

Bunch Compressor Sections – Challenging Installation




Bunch Compressor BC1




Warm Beam Line Sections


Bunch Compressor Sections – Almost done

21







100 accelerator modules




800 accelerating cavities
1.3 GHz / 23.6 MV/m





- The accelerator tunnel (XTL) houses three cold linac sections separated by bunch compressors.
- Down to approx. 50 m behind the last module the complete beam vacuum system is particle free.
- 4 modules / 32 s.c. cavities are connected to one 10 MW klystron.
- 12 modules form a cryogenic string.
- At the XTL end a collimation and separation system is installed.

All Accelerator Modules Installed



Accelerator Module on its Way to the Tunnel



■ 1st module July 1st, 2014 – last module August 1st, 2016


The First and the Last Module

26




- In total 96 modules in 103 working weeks
- The initially projected rate was 1 acc. module per week.
- Variation in coupler availability was compensated by additional efforts at CEA / Iffu wrt. assembly rate.
- Gained experience with module testing was used to shorten test duration of module 40+ .

XFEL module installation rate XTL 2016-08-02



See this Conference WE1A02

The XFEL Village at IRFU / CEA Saclay




the XFEL Village

irfu

cea


saclay

28





Reference

Contributions to the European XFEL Modules




BINP Novosibirsk, Russia	• cold vacuum bellows • coupler vacuum line
CEA Saclay / Irfu, France	• cavity string and module assembly • cold beam position monitors • magnetic shields, superinsulation blankets
CIEMAT, Spain	• Superconducting magnets
CNRS / LAL Orsay, France	• RF main input coupler incl. RF conditioning
DESY, Germany	• cavities & cryostats • contributions to string & module assembly • coupler interlock • frequency tuner • cold vacuum system • integration of superconducting magnets / current leads • cold beam position monitors
INFN Milano, Italy	• cavities & cryostats • contributions to frequency tuners
Soltan Institute, Poland	• Higher Order Mode coupler & absorber

The last Process Line Welding on Sep 9, 2016




The End of Main Linac Section L3



XFEL Module Performance

32



vertical test (clipped at 31 MV/m)
module performance

- Module performance well above specs. and visible improvement with time
- Tunnel installation used sorting of modules based on AMTF performance
- XM98 as scavenger module


Remark:

Clipping at 31 MV/m is done due to max. available RF power; limit given by waveguide distribution.

	N_{cavs}	Average	RMS
VT	815	28.3 MV/m	3.5
CM	815	27.5 MV/m	4.8


Waveguide Tailoring was done for all Modules

33



Energy Reach of European XFEL Modules

34



maximum energy reach

- after tunnel installation *and*
- according to accelerator module test

	Installed (GeV)	Module (GeV)
CS1	1.	1.05
CS2	3.89	4.06
CS3	6.29	6.72
CS4	8.91	9.49
CS5	11.38	12.09
CS6	13.92	14.76
CS7	16.63	17.62
CS8	19.42	20.44
CS9	21.09	22.23

the maximum energy during FEL operation needs to respect the bunch compressor (BC) working points


- 2.4 GeV nominal BC2 energy leads to approx. 19.5 GeV
- higher BC2 energy (e.g. 3.3 GeV) allows for > 20 GeV

increased max. energy assures higher availability


Accelerator Modules at AMTF & WATF

35


- During the 2nd production year AMTF module testing was performed without any delay.
- During the end of production the major non-conformity was overheating at the 70k coupler window; all respective warm coupler parts were exchanged.
- Waveguide tailoring was done for all modules.
- Successfully repaired modules were retested at AMTF when needed.
- Not installed are
 - XM8 (leaky cryogenic line)
 - XM46 & XM50 (inacceptable cav.performance)
 - XM99 (leaky beam line)
 - XM100 spare module & replaced by XM-2



Couplers were the by far the most challenging single items in the supply chain of the modules



- A total of 800 RF power couplers was produced at three different vendors
- The largest fraction was procured by LAL Orsay and produced by Thales / RI
- Approx. 20% were procured from CPI
- RF conditioning of all couplers was done at LAL Orsay at a rate of 10+ couplers/week
- **Coupler delivery rate did not match the module assembly rate**
- Continuing quality and delivery issues needed to be addressed
- The coupler production is still not finished (non-conformities are addressed)
- Approx. 24 couplers are needed for the repair of modules



Tunnel Installation Process

37

- Optimized global process steps and sequence & daily improvements

Cryo-String

RF

Signal Cables


LWL

Ethernet

P.I.


Prep
Cond

TÜV



Process Management XTL Installation

- Improved process management and repetitive tasks helped to speed-up the installation.
- All groups work with the goal to close the tunnel around mid October.
- Some work will remain to be done on maintenance days / weeks.
- Full operation incl. CS1 – CS7
- CS8 hardware ready
- CS9 cabling etc. to be done (two RF stations only)




Post Linac Beam Lines upstream of XS1


39



- 200 m transport line (eq. to 4 + 12 modules)
- 200 m collimation



The Temporary Beamline uses Existing Module Suspensions (wherever possible)




Beamline Installation close to XTL Tunnel End

41

- All installation work will be finished by end of 9/2016




- All beam lines are suspended from the ceiling
- Engineering of 'hanging' system took long but result is very satisfying



Warm Beam Line Sections


Transport Line to XS1 Beam Dump

42



- All beam dumps available and XS1 dump installed
- Special vehicle to exchange activated dumps


Installation on Top of XS1 Dump Cave




- XS1 installation includes transport towards XTDs
- The safety magnet is installed at the upstream end



Shielding and Personnel Interlock




- Shielding and personnel interlock done recently.
- Final check of the personnel interlock scheduled for Oct. 17/18 (TÜV review).



Installation Activities


SASE Undulator Sections




45



- BINP and DESY teams are working in the northern branch
- Work expected to be finished beginning 10/2016
- A fully commissioned system will be available before end 2016
- The southern branch follows immediately




SASE Undulator Sections with special air conditioning hutch




Optical Elements and Photon Diagnostics

SASE1 Beamline



47



Installation Activities



Photon Beam Lines

48






Installation Activities



Photon Beam Lines




SASE1 and SASE3 Hutches Installation



SASE1 Stations FXE and SPB/SFX just prior to instrument installation



Summary and Outlook



- The fascinating time of accelerator module production / testing / installation comes to an end
- Tunnel closure is scheduled for 10/2016
- Technical commissioning continues after first cool-down
- Based on injector experience and accelerator module performance we are looking forward to reaching all design parameters
- **The milestone ,first lasing possible‘ is scheduled 6 months after ,tunnel closure‘**
- User operation will start in 2017
- Full performance is expected approx. 1.5 years after first lasing


more than 1000 participants
at the 2016 users' meeting




Contributors to the XFEL Accelerator

53

100 accelerator modules



800 accelerating cavities
1.3 GHz / 23.6 MV/m



Wroclaw University of Technology

