


# Beam commissioning results from the R&D ERL at BNL

Dmitry Kayran

Brookhaven National Laboratory

# BNL R&D ERL

- ✓ ERL construction was completed: May 2015
- ✓  $Q=0.55\text{nC}$ ,  $I=.26\text{mA}$  per 4 msec reached: June-July, 2015
- ✓ R&D ERL has been built to serve as the test bed for future projects at CAD.
- ✓ Many ERL components will be used for RHIC upgrade project: LEReC.








# R&D ERL: Installation and commissioning time line

*Strategy: Start commission of key components when systems installed and resources are available.*


(no beam)

- ✓ High power RF components installed and commissioned (2005-2007)
  - ✓ 1MW Klystron, 50kW RF PA, waveguides, controls, circulator, dummy load
- ✓ SRF 5-cell installed and cold emission test completed (2009)
  - ✓  $E_{acc}=18\text{MV}$ , 2 sec CW every 10 sec.
- ✓ 9.4MHz Laser system commissioned (2009)
- ✓ Digital LLRF system commissioned (2012)
- ✓ 2 K LHe cryogenic system/refrigerator commissioned (2012)
- ✓ SRF half-cell gun cold emission test w/o cathode (2013)
  - ✓  $E_{acc}=2\text{MV}$
- ✓ Conditioning of the SRF gun with a cathode stalk (Jan 2014)
  - ✓  $E_{acc}=1.25\text{MV}$
- ✓ Gun test beam line components installation completed
- ✓ Low power gun beam test approved (May 2014)




# First beam commissioning (June-Nov. 2014)

Cathode transport cart






First Injection line dipole stays off during gun beam tests.  
Straight line is used to check QE at the beginning and the end of every regular shift, and energy measurements.

RT solenoid wrapped around the v.pipe in situ due to problems with running HTS one.




# First attempt to run SRF gun with cathode (June 2014)

- ✓ Cathode dark current measured.



# First beam, old cathode Nov 2014.




Faraday cup signal (1MΩ termination)

## Set up

- Laser: 6.1 Watt, green,  
Pulse structure 7 μsec, every 500 μsec; 9.38MHz rep rate.
- RF: 1.2 MV, 500 ms, 1Hz;
- Beam:  
bunch charge: 7.7 pC,  
Average per RF pulse  
**photocurrent 1 uA.**   **dark current 38 nA;**
- Photocathode cold QE=2.7e-5 Very low!!!




# First beam test results meas. vs sim



# ERL beam commissioning job flow (cryogenic limited)

- ERL Cryogenic system is capable of providing 2K cold operation time of the SRF gun up to 16 hours in low power load mode.
- Then 8 hours hold at 4.5 K.
- After that it requires 1-2 days for helium recovery
- We can run the gun maximum four days per week



## Optimum schedule

Monday : Cool down the gun to 2 K, Insert cathode, stay at 2 K for 16 hours; then, hold 4.5 K over night

Tuesday : Cool down the gun to 2 K, stay at 2 K for 16 hours; then, remove cathode warm it up to 40 K over night;

Wednesday, the gun with stay at 45K cathode is out;

Thursday Cool down the gun to 2 K, Insert cathode, stay at 2 K for 16 hours; then, hold 4.5 K over night.


Friday, Cool down the gun to 2 K, stay at 2 K for 16 hours; then, remove cathode warm it up to 40 K over night

Saturday, Sunday, the gun with stay at 45K cathode is out


Beam time / Cryogenic time about 38%

# New “multipacting-free” cathode stalk has been designed and fabricated with Ta tip\*.

## New cathode stalk for high current operation



; Gun with new cathode stalk.



\*Wencan Xu et al., “Multipacting-free quarter-wavelength choke joint design for BNL SRF gun”, In Proc. of IPAC’2015, pp 1935-1937 (2015).



# Beam commissioning with new cathode June 2015.




Faraday cup signal (1M $\Omega$  termination)

## Set up

- Laser: 0.044 mWatt, green,  
Pulse structure 5  $\mu$ sec, every 500  $\mu$ sec; 9.38MHz rep rate.
- RF: 0.65 MV, 3 ms;
- eBeam:  
charge per macro bunch 0.8nC/47bunches=17pC  
dark current 4  $\mu$  A;
- Initial photocathode cold QE=1e-2 very Good!!!



# Solenoid scan to measure gun astigmatism (preliminary)




Ninja star shape




2 FPCs

Axial symmetric system or not?




Such asymmetry could be generated by quadrupole with focus length 64cm!!!. Located at FPC or solenoid imperfection. Required further investigation.

# Energy measurements using correctors and profile monitor



Beam shift at straight line profile monitor  
15.5 mm  
corrector changes  $\Delta l = 1.4\text{A}$   
Corresponds to beam energy  $KE = 1\text{MeV}$




RF voltage setting 1.02 MV



# Try Solenoid scan, Q=130pC

Beam image at profile monitor for different solenoid settings

Laser transverses profile




Power on cathode 3.49 W at 9.38 MHz, or  
372nJouls per laser pulse, FWHM=1.7mm

$$x_{rms}^2 = \langle x^2 \rangle = A \left( \frac{1}{f^2} \right) - 2AB \left( \frac{1}{f} \right) + (C + AB^2)$$


$$\varepsilon = \frac{\sqrt{AC}}{d^2}$$

Vertical normalized emittance 3.5 um  
Horizontal normalized emittance 2.6 um

# 10 Watts e-Beam for fault studies.



RF pulses structure 5 msec every 100msec



FC Flange temperature (blue) rises 3 °C per 30 minutes.




One single: RF pulse duration 5msec (magenta), laser pulses 4msec (green) and faraday cup signal 4 msec (yellow) 10 kOhm termination.

260 uA in 4 msec pulse at FC has been measured. With duty cycle 4% corresponds to 10.4 uA average current at beam dump. Beam with average power in order to 10 Watts has been provided for radiation survey to FC.

After these studies and completion of ARR DOE approval for full power gun-to-dump test commissioning has been received in July 2015.


# Average current and charge from Gun

Ie Window Markers Analysis




Average current and charge from the gun during fault studies measured by ICT and pulse counter .

# Gun to Dump test: first propagation




# Gun to Dump test: first propagation


Beam current measured by injection line DCCT (magenta) and by extraction line DCCT (green). 90% transport efficiency has been achieved.



# Typical cathode QE redaction during beam tests



# BPMs signal drifts and jumps




During commission significant jumps of trajectory.


It's very difficult to tune machine.

We suspect that ICT, DCCTs ceramic breaks are slow charged by halo or/and dark current and then sudden discharge.

The shielding for each ceramic break location has been designed it will be implemented where these elements are used in LEReC



# Cathode QE measurements in the SRF gun during beam tests



# Beam parameters measured



Parameter	Measured*
Kinetic Energy	1.2 MeV
Charge per bunch	0.55 nC
Cathode QE in the gun	1%
Current during RF pulse	350 uA
Average current	20 uA
Laser Rep. Rate	9.38 MHz
Average Laser power at the cathode	3.5 W
Laser Bunch Length	8.5, 22 psec
Norm. emittance x/y	2.5/3.5** um
Average dump power	10W @ FC

\*Listed parameters have been achieved in different modes of operation

\*\*Preliminary results

# Beam instrumentation tested with beam

virtual target  
inspection



BPM





beam Profile monitor


its




PMT Detectors



D. Kayran



Position measurements



LINAC'16 Sept 25-30 2016

# Summary and plans

---

- All ERL components have been installed by May 2015.
- The first test with “multipacting-free” Ta tip cathode took place in June, 2015.
- The highest charge from SRF gun .55 nC has been achieved (initial QE=1%).
- The max average current from this gun 22 uA has been demonstrated with 260uA in 4msec.
- The bunch is very asymmetric most likely due to solenoid imperfection. HTs solenoid fix is needed.
- Beam has been propagated from the gun to beam dump with SRF linac off.
- 90% injection to extraction current transparency routinely has been achieved.
- Cathode with QE 4e-4 level allowed us to commissioning ERL systems with bunch charge 30-50 pC.
- Ceramic break charge discharge requires shielding installation
- During first 3 months of beam commissioning we were able to test and cross calibrate most of the beam diagnostics which will be used for the next project LEReC.
- LEReC will use SRF gun as a booster cavity without cathode inserted. The 704 half cell gun as a booster cavity will be installed for LEReC commissioning in summer of 2017
- Future beam tests are planned to resume when LEReC cinstallation is completed in RHIC IP2 at the end of 2017.

---


# Acknowledgment for BNL R&D ERL team

Zeynep Altinbas, Dana Beavis, Sergey Belomestnykh, Ilan Ben-Zvi, Paul Bergh, Suresh Denarine, Jesse Fite, David Gassner, Lee Hammons, Robert Lambiase, Edward Lessard, Ramesh C. Gupta, Chung Ho, James Jamilkowski, Stephen Jao, Prerana Kankiya, Robert Kellermann, Nikolaos Laloudakis, Vladimir Litvinenko, George Mahler, Leonard Masi, Gary McIntyre, Wuzheng Meng, Robert Michnoff, Toby Allen Miller, John Morris, Igor Pinayev, David Phillips, Vadim Ptitsyn, Triveni Rao, Pablo Rosas, Scott Seberg, Thomas Seda, Brian Sheehy, Loralie Smart, Kevin Smith, Victor Soria, Andrew Steszyn, Roberto Than, Erdong Wang, Andreas Warkentien, Daniel Weiss, Huamu Xie, Wencan Xu, Alex Zaltsman  
and many others.

Thank you all!

- Back up slides


# ERL transformation to LEReC



# LReC upgrade

## LReC Phase-I: Gun-to-dump mode

electron beam energies 1.6-2MeV




BROOKHAVEN  
NATIONAL LABORATORY

Office of  
Science  
U.S. DEPARTMENT OF ENERGY

JULY 2014 2014

## Low Energy RHIC Physics program: Search for QCD phase transition Critical Point

Center of mass energies:  $\sqrt{s_{NN}} = 5, 6.3, 7.7, 8.8, 11.5, 14.6, 19.6, 27$  GeV



- Energies in black have been measured in the 2010 & 2011 & 2014 RHIC runs
- Because of large emittance and IBS at low energies the integrated luminosity is small
- We need to cool the ions to improve luminosity




BROOKHAVEN  
NATIONAL LABORATORY

Office of  
Science  
U.S. DEPARTMENT OF ENERGY


JULY 2014 2014

LReC will use SRF gun as a booster cavity without cathode inserted. The booster needs to operate CW at 2.2 MV of voltage. In 2013 this cavity has been commissioning for such operation. However after beam tests it was discovered that the cavity can run only at 1.6 MV of voltage. Cavity was opened and copper marks have been observed at niobium part of chock join. Presumably cavity has been contaminated during severe cathode stalk RF conditioning. This gun as a booster cavity needs to be install for LReC commissioning in summer of 2017. In summer of 2016 cavity has been sent for cleaning and testing.


# ERL components moved to LReC location



# LEReC requirement booster with Eacc=2.2 MV



# SRF Gun Cavity Parameters





BROOKHAVEN  
NATIONAL LABORATORY


*E* Systems, Inc.  
Advanced

RF frequency	703.6 MHz
Cavity active length	8.5 cm (0.4 cell)
Maximum energy gain	1.8 MeV
Maximum field at the cathode	26.7 MV/m
$E_{acc}$ at 2 MV	23.5 MV/m
$R/Q_{acc}$	96.2 Ohm
Geometry factor	112.7 Ohm
Cavity operating temperature	2 K
$Q_{ext}$	4.5E5
Frequency tuning range	1 MHz
Required RF power	54 kW
Installed RF power	65 kW

LEReC requirement  $E_{acc}=2.2$  MV




# Copper rings marks




Cavity was opened and copper marks have been observed at niobium part of chock join. Presumably cavity has been contaminated during severe cathode stalk RF conditioning. This gun as a booster cavity needs to be install for LEReC commissioning in summer of 2017.

# HTS solenoid lead damaged



From one side both HTS leads can be seen to be a uniform red color.



Main lead from other side it's different matter. Besides being discolored in spots, it's lifted up at one point. O