

Spoke Cavity Development and Beam Commissioning of 10 MeV Spoke-Based Proton Linac

Feisi He

On behalf of colleagues in IHEP SRF group
Institute of High Energy Physics (IHEP)




Outline


- Background
- Fabrication and quality control
- Post processing
- Vertical test statistics
- String and cold-mass assembly
- Cryomodule commissioning
- Operation with beam

Spoke cavities for CADS linac

Layout of ADS injector I






- IHEP is in charge of the CADS injector-I linac (14 spoke012 cavities), and the CM4 of the main linac (6 spoke021 cavities)





Spoke cavities for CADS linac (2)





	Spoke 012	Spoke 021	Spoke 040	Spoke 024	HWR 325
β_0	0.14	0.24	0.46	0.24	0.14
E_p/E_{acc}	5.0	4.4	3.9	4.0	4.6
B_p/E_{acc} $mT/(MV/m)^2$	6.9	9.4	9.2	6.4	4.8
G- Ω	60	71	104	81	73
R/Q- Ω	150	191	265	206	197

Note: E_{acc} normalized with $\beta_0 \lambda$;



Fabrication of IHEP ADS spoke cavities








Surface quality control

- Before final EBW it is the last chance to get easy access to the cavity inner surface
- Defect, e.g. pits in diameter 0.1mm, could be addressed by eye inspection. Sometimes magnifier or very light BCP helps to find defects.



Frequency control


- Frequency tuning is typically done by stacking parts together before EBW, and trim the cylindrical part after frequency measurement.





Pre-tuning of the cavities



- Pre-tuning is typically done after the bulk BCP
- A specific tooling was used to press the cavity to reduce frequency;
- High pressure gas in the cavity was applied to increase frequency





Post processing of Spoke cavities

- BCP in Ningxia OTIC; re-HPR and clean assembly in IHEP





VT results of the spoke012 cavities

- MP conditioned in 1 hour with variable coupler
- Eacc increased by 2 MV/m with better cooling
- 120C baking increases Q_0 by about 50-100%
- At 2K, Q_0 is 6 times higher, $B_p \sim 125$ mT achieved.





Spoke012 4.2K VT, Designed $Q_0 = 5 \times 10^8$ @ $E_{peak} = 31.5$ MV/m



String and cold-mass assembly

- String assembly in cleanroom
- 120C Low baking
- String attach to assembly tool
- Alignment
- Cryomodule assembly
- Leak check and cold shock
- Shipment to tunnel and alignment









CM1&CM2 cooling down

- It takes about 5-6.5 days to reach 4K stable operation
- Measured df/dp is about -130Hz/mbar for CM1 cavities, and -83Hz/mbar for CM2 cavities; LFD is about -13Hz/(MV/m)²; Q0 is not measured yet.

Cavity_ID	1	2	3	4	5	6	7	8	9	10	11	12	13	14
df_4KvsRT [kHz]	546	523	540	462	509	557	496	408	428	511	323	572	519	553
df/dp [Hz/mbar]	-157	-129	-134	-150	-131	-119	-91	-66	-47	-96	-82	-75	-97	-119
LFD [kHz]	-14	-12	-11	-13	-12	-10		-13	-13	-9	-10	-12	-9	-16




Static heat load of the CM1




- The maximum temperature difference on thermal shields were less than 40K during cooling down
- Heat load of 30W measured by liquid level and mass flow rate agree in 7%
- LHe pressure stability was improved from ± 0.6 mbar (TCM) to ± 0.05 mbar (CM1)

80K thermal shield





5K thermal shield







Spoke cavity conditioning

- Cavity conditioning at 4K typically takes 1-2 days
- Cavity was conditioned to 8MV/m before beam operation (FE for cav 1-4#, administrative for Cav5-14#)
- On CW beam operation of 2mA@10MeV mode, average cavity gradient is 6MV/m, i.e. $E_p \sim 27$ MV/m



Operation with beam

- Pulsed operation of 23 hours without trip
- CW proton beam of 1.6mA at 10MeV for 23 minutes





Thanks for your attention!