

I.Podadera^{1,2}, J. Aguilar³, F. Arranz², S. Becerril³, L. Bellan⁴, D. Bernardi⁵, B. Bolzon⁶, P. Cara⁷, J. Castellanos⁸, N. Chauvin⁹, S. Chel¹⁰, T. Dézsi^{9,10}, A. Ibarra^{1,2}, M. Ferreira¹¹, M. Garcia², J. Gutiérrez¹², V. Hauer¹³, D. Jiménez-Rey², W. Królas¹⁴, B. Kumar¹⁵, T. Lehman¹³, M. Luque³, L. Macià¹⁵, A. Madur⁶, J. Maestre³, C. Martins¹¹, G. Micchiché⁵, J. Molla², C. de la Morena², F.S. Nitti⁵, C. Oliver², A. Palmieri⁴, A. Pisent⁴, C. Prieto¹², Y. Qiu¹³, D. Regidor², D. Sánchez³, M. Sanmarti¹⁵, C. Torregrosa³, M. Weber^{1,2}, U. Wiacek¹⁴

¹ IFMIF-DONES España Consortium, Spain ⁴ INFN, Italy ⁷ Fusion for Energy, Germany ¹⁰ C3D Engineering Ltd., Hungary ¹³ KIT, Karlsruhe, Germany
² CIEMAT, Spain ⁵ ENEA, Italy ⁸ Universidad Castilla La Mancha, Spain ¹¹ Lund University, Sweden ¹⁴ IFJ PAN Kraków, Poland
³ University of Granada, Spain ⁶ Université Paris-Saclay, CEA, France ⁹ CER, Hungary ¹² EAI, Spain ¹⁵ IREC, Barcelona, Spain


*E-mail address: ivan.podadera@ifmif-dones.es

IFMIF-DONES Project

IFMIF-DONES is a facility to produce fusion relevant neutrons to test materials based on $\text{Li}(d,xn)$ stripping reactions of **40 MeV D+**



Located at Escúzar 18 km southwest from Granada city, Spain




The 5 MW Deuteron Accelerator

100 m long, 175 MHz, D+ 5 MW CW scLINAC

The **Accelerator Systems**: Injector, RFQ, MEBT, SRF LINAC, HEBT, RFPS and AS Ancillaries (ASA)

Main AS Challenges:

- High availability (>87%) over lifespan,
- Remote Handling,
- Materials damage and activation,
- High CW beam control and monitoring,
- Control of the Rectangular beam shaping for dpa volume and gradient optimization
- Machine, safety protection and diagnose at extreme environmental and beam conditions



MEBT	
Operating frequency	175 MHz
Input energy / Output energy	5.8 / 5.8 MeV/g
Particle type	D ⁺
Output beam current	140 mA
Nominal beam peak current	125 mA
Nominal duty cycle	100 %
Beam diameter length	238 cm
Re-buncher cavities L-Lit	380 kV
Compler maximum transmitted power	18 kW
Quadrupole magnetic field gradient	25 T/m
Steerer's strength (horizontal and vertical)	28 G/m

INJECTOR	
Ion type	D ⁺
Output beam current	140 mA
Output beam energy	100 keV
Species fraction D ⁺	99%
Beam extraction noise	1% rms
Duty factor	100%
Beam turn-off time	<10 μs

HEBT	
Beam energy	40 MeV
Beam emittance	0.30 mm mrad
Nominal beam peak current	125 mA
Nominal duty cycle	Up to 100%
RF bunching	Up to 100%
Beam footprint at Li Target	10x5 cm
GDTR Diapole	20
RF maximum power (DC<1%)	<80 kW

SRF LINAC	
Cavity	
Operating frequency	175 MHz
Nominal Accelerating Field (Eacc, norm)	4.8 MV/m
Q ₀ @ Eacc, norm	10 ⁹
Beam diameter	40 mm
Maximum power dissipation (p, Eacc, norm)	7 W
Frequency at cold during nominal test (cavity instrumented, no power coupler)	178.016 - 178.060 MHz
Frequency at cold during nominal test (cavity instrumented, no power coupler)	178.016 - 178.060 MHz
Working Temperature	4.48 K
Transmitted Power	100 kW CW
Cost	6.30 M€
Magnetic field Bz on axis	6 T
Chatters Field	3.8 mT/m
Quadrupole	8.2 G
Working Temperature	4.48 K

Accelerator commissioning

- **Tiered approach commissioning** alike other LINACs (LIPAc, SPIRAL2, ESS, SNS, LINAC4). To start four years later after T0- accelerator building construction (expected in 2024)
- **LIPAc commissioning** feedback (ongoing, see **TU2AA04** or **TUPORI029**) is a high value asset to optimize the IFMIF-DONES Commissioning
- **Hardware commissioning** (HWC) will be anticipated as much as possible to ensure readiness for beam:
 - Strategy to be followed for optimum commissioning of **RFQ** (RF conditioning), **SRF LINAC** (cryoplant and RF cavities) under analysis
 - **RFPS** and **Ancillaries** to be commissioned at earlier stage
- **Trade-off** between aggressive and conservative approach:
 - Validation of **integrated systems** right from first phase
 - Beam will be fully **characterized** at each phase to ensure smooth transition to the next phases
 - In each phase, **beam power** will be smoothly ramped up to minimize risks of machine damage or activation
 - **Proton** commissioning will be used only when strictly necessary
 - **RFQ** with a duty cycle high enough to emulate the nominal beam
 - Five cryomodules of the **SRF LINAC** commission in one-single stage

Beam commissioning stages

Timeline	Phase Description	HWC objectives	BC objectives	Challenges
T0	Start of Accelerator building construction			
T0+4	Phase 1- Injector 140 mA CW – 100 keV	<ul style="list-style-type: none"> • HV and plasma conditioning • Integration with AS Ancillaries and Control Systems (including Machine and Safety protection) 	<ul style="list-style-type: none"> • Check out all the injector, and ancillaries components • Full characterization of beam characteristics at RFQ interface point with protons and deuteron 	<ul style="list-style-type: none"> • First beam operation in the facility • Co-living with parallel installation and HWC activities
T0+5	Phase 2- RFQ/MEBT 125 mA 20% DC – 5 MeV	<ul style="list-style-type: none"> • RFQ Field check • RFQ RF Conditioning • Re-bunchers RF Conditioning 	<ul style="list-style-type: none"> • Check out all the RFQ, MEBT, diags and ancillaries • Tests all RFQ features • Beam characterization for SRF LINAC injection 	<ul style="list-style-type: none"> • RFQ conditioning (integration RFPS and 8-chain RFQ up to CW) • Ramp up beam to test all the RFQ features for nominal beam operation w/o activating systems
T0+7	Phase 3- SRF LINAC 125 mA 1% DC – 40 MeV	<ul style="list-style-type: none"> • Cryomodules cool down • Cavities RF conditioning • Solenoids field 	<ul style="list-style-type: none"> • Check out all the SRF LINAC transmission (including beam diagnostics tests) • Beam diagnostics @ different beam modes 	<ul style="list-style-type: none"> • Lossless transmission along the cryomodules using beam diagnostics • Stability of the cryogenics systems and RF cavities during beam power ramped up • Feedback from LIPAc will mitigate the risks by developing specific procedures
T0+9	Phase 4- AS+LS+STUMM 125 mA CW – 40 MeV	<ul style="list-style-type: none"> • Remote Handling procedures • Target diagnostics • Integration with Lithium and Test Systems 	<ul style="list-style-type: none"> • Provide nominal beam power to the lithium target for STUMM irradiation • Validate neutronics field with STUMM (Test Systems) • Test beam/lithium interaction • Optimize irradiation profile by tuning the accelerator • Validate the machine and safety protection systems 	<ul style="list-style-type: none"> • Target beam diagnostics • Tests HEBT Remote Handling equipment • Integrated operation with lithium target • Irradiation optimization • Alignment of all the systems during power ramp up
T0+10	IFMIF-DONES Operation			

IFMIF-DONES Programme is expected to start Construction Phase in short term!