



# CSNS-II superconducting linac design

Jun Peng

On behalf of the CSNS Accelerator Team & Collaboration  
Dongguan Campus, IHEP

*Special thanks to: Yu-liang Zhang, Wen-zhou Zhou, Zhi-ping Li, Xin-yuan Feng, Yan-liang Han*


*Linac 2022, 2 Sept. 2022*

- 1** Introduction
- 2** Accelerator status
- 3** Options of the linac for the CSNS power upgrade
- 4** Design of the superconducting linac
- 5** Summary

# CSNS overview

◆ The CSNS facility consists of an 80-MeV H- linac, a 1.6GeV rapid cycling synchrotron(RCS), beam transport lines, a target station, and 3 spectrometers.

Project Phase	I	II
Beam Power on target [kW]	100	500
Proton energy [GeV]	1.6	1.6
Average beam current [ $\mu$ A]	62.5	312.5
Macropulse.ave current[mA]	15	40
Macropulse duty factor	1.0	1.7
Linac energy [MeV]	80	300
Linac type	DTL	Spoke+ Elliptical
Target	1	1
Spectrometers	3	20



# CSNS accelerator performance


-Data from Yu-liang Zhang

## Key milestones(On schedule)


- 2015 start beam commissioning
- 2017 first beam on target
- 2018 end of beam commissioning  
start operation for user program(20kW)
- 2020 Reach full power(100kW)

## Power and Energy on Target

2017/11/01 00:00:00 - 2022/07/26 08:00:00



Beam Reliability Data




- The accelerator routinely operates with >90% availability in recent years
- From October 2021 to July 2022, the beam availability has been improved to more than 97%.

# CSNS Linac Status

**With 50% chopping**

流强显示



CT Display

2020-05-25 08:06:29

LEBT CT01	32.63	mA	RTBT CT02	1.585	E13
LEBT CT02	0.83	mA	RTBT CT03	1.587	E13
MEBT CT01	6.56	mA	MEBT Trans	100.3	%
MEBT CT02	6.58	mA	DTL Trans	99.6	%
LRBT CT01	6.55	mA	LRBT Trans	100.2	%
LRBT CT02	6.54	mA	EXT Trans	100.5	%
LRBT CT03	6.57	mA	RCS Trans	98.5	%
DCCT-INJ	1.608	E13	RTBT Trans	99.7	%
DCCT-EXT	1.584	E13	Linac Energy	80.271	MeV
RTBT CT01	1.591	E13	Beam Power	101.44	kW

FCT System

Phase	Amplit	Phase	Amplit	Phase	Amplit
MEBCT01	183.737	DTLCT01	41.11600	LRBCT01	175.313900
MEBCT02	183.883000	DTLCT02	113.787100	LRBCT02	176.287900
MEBCT03	171.318000	DTLCT03	130.712800	LRBCT03	175.207900
MEBCT04	7.887300			LRBCT04	15.079900
MEBCT05	172.791000			LRBCT05	3.487900

BPM System

Phase	
LRBTPM02	-83.522939
LRBTPM04	-4.009924
LRBTPM06	230.030600

**Measured energy: 80.3MeV**  
**Design energy: 80.1MeV**


LINAC BLM

2020-05-25 08:07:43



**Activation level:**  
**<7mrem/hr@30cm**

## Options of linear accelerator for CSNS II



### Main constraints:

- The tunnel length reserved for linac energy upgrade is 92m.
- To reduce space-charge effect in the RCS, beam energy output from the linac should be more than 300MeV.






The energy gain per meter > 2.4MeV/m

### Special requirements for linac energy upgrade

- ✧ Stable output beam energy, energy jitter  $\Delta E/E < 0.04\%$
- ✧ High availability (>95%)
- ✧ Quick installation, device and beam commissioning, recover user operation
- ✧ Technical risk/local expertise


Mini Workshop on CSNS Upgrade Program  
 Sept. 20, 2018, Beijing, China

# Scheme 1、Pi mode structure






# Superconducting linac


Scheme 2:



Scheme 3:





# Spoke cavities for CSNS II linac



electric field (left) and magnetic field (right)


The Main Parameters

Parameter	Design value
Frequency(MHz)	324
Beam tube aperture (mm)	50
$E_p/E_{acc}$	4.1
$B_p/E_{acc}(mT/MV/m)$	9.2
$\beta_0$	0.5
$G(\Omega)$	120
$R/Q(\Omega)$	410
$E_{acc}(MV/m)$	9



Spoke section from 80MeV to 180MeV

# Status of Prototyping




EM Design

2021.2-2021.6




Machine Design

2021.6-2021.8



Manufacturing  
Technique

2021.9-2022.3



Postprocessing


2022.4-2022.6





Vertical Testing

2022.6-

# Elliptical cavities for CSNS II linac



electric field



The Main Parameters

Parameter	Design value
Frequency(MHz)	648
N cell	6
$\beta_g$	0.62
Beam aperture(mm)	105/120
R/Q ( $\beta_g$ ) ( $\Omega$ )	309
$E_p/E_{acc}$ ( $\beta_g$ )	2.53
$B_p/E_{acc}$ ( $\beta_g$ ) (mT/(MV/m))	5.53
G( $\Omega$ )	177
Coupling Kcc%	1.35
$E_{acc}$ (MV/m)	15.8



-Data from Wen-Zhong Zhou




6 cells per cavity, 3 cavities per cryomodule

# Spoke – Elliptical energy transition


Normalized TTF curve, the intersection point is at  $\beta=0.592$  (~226MeV),

Accelerating field curve, the intersection point is at  $\beta=0.496$  (~142MeV)







Transition energy is 169MeV( $\beta=0.53$ )





# Beam dynamics- $\phi_s$ and $E_{acc}$



$$(\phi_s)_{648\text{MHz}} = 2 \times (\phi_s)_{324\text{MHz}}$$

$$k_{l0}^2 = \frac{2\pi q E_0 T \sin(-\phi_s)}{mc^2 \beta_s^3 \gamma_s^3 \lambda}, \quad \text{maximum variation per period} < 2\text{deg/m}$$


# Beam dynamics-*phase advance*






- Maximum zero-current phase advance per period is less than 90 degrees to avoid parametric resonances.
- Average phase advance per meter must be continuous.

# Beam dynamics-*lattice design*

Spokes,  $\beta_{opt}=0.5$



Elliptical,  $\beta_g=0.62$




The beam is equipartitioned when:

$$\frac{\epsilon_{nx}k_x}{\epsilon_{nz}k_z} = 1$$

# Beam dynamics-*Emittance*


—  $E_{zz'}$  —  $E_{yy'}$  —  $E_{xx'}$

TraceWin - CEA/DRF/Irfu/DACM





—  $Advz / k_{z0}$  —  $Advy / k_{y0}$  —  $Advx / k_{x0}$

TraceWin - CEA/DRF/Irfu/DACM



- The RMS emittance growth through MEBT+DTL+Spoke+Elliptical is 26%(horizontal), 32%(Vertical) and 32%(longitudinal).
- Tune depression is bigger than 0.4

# Beam dynamics-*Acceptance*



- In the normal conducting linac, the bore radius/RMS beam size is over 5.5.
- In the superconducting linac , the bore radius/RMS beam size is over 8.5.
- For the superconducting linac, the longitudinal acceptance is more than 144 times the area of the matched rms beam emittance at spoke injection.

# Error studies

- The start-to-end error analysis is performed – (MEBT, DTL, SC Linac)
  - Beam error from RFQ
  - MEBT & DTL
  - Super-Conducting Linac
- Nominal & 2\*Nominal Errors are studied

## Beam Errors @ RFQ Output

Errors		Values
Trans. Offset	$\Delta X, \Delta Y$ (mm)	0.5
Angle	$\Delta X', \Delta Y'$ (mrad)	1
Phase	$\Delta \text{phi}$ (deg)	1
Energy	$\Delta E$ (MeV)	0.01
Emittance	$\Delta \text{EmitX}, \Delta \text{EmitY}, \Delta \text{EmitZ}$	10%

## Cavity & Quads Errors from the MEBT and DTL


Errors		Values	
		Cavity	Quads
Trans. Offset	$\Delta X, \Delta Y$ (mm)	0.05	0.05
Angle	Rx, Ry, Rz (mrad)	3	3
Gradient	$\Delta G$ (%)	1	1
Phase	$\Delta \text{phi}$ (deg)	1	
Long. Offset	$\Delta z$ (mm)	0.1	

## Cavity & Quads Errors from the SC linac


Errors		Values	
		Cavity	Quads
Trans. Offset	$\Delta X, \Delta Y$ (mm)	1	0.1
Angle	Rx, Ry, Rz (mrad)	2	2
Gradient	$\Delta G$ (%)	0.5	0.5
Phase	$\Delta \text{phi}$ (deg)	0.5	
Long. Offset	$\Delta z$ (mm)	0.5	0.5

# Error Analysis Results

- Emittance growth rates are about 25%
- Beam loss rates are <0.01%
- RMS Energy jitters are 187keV(**0.063%@300MeV**) . (Debunchers are needed to compress the energy jitter)




-Data from Yan-liang Han



# Study of Debuncher System for CSNS-II Linac

## ■ 2-Cavity Debuncher System

-Data from Zhi-ping Li





### Principle:

1. Small Aperture
2. Small  $L1/L2$
3. Voltage of debuncher available ( $L1$  not too small)

### Momentum Jitter Compactor Ratio:

$$\delta_{p1}/\delta_{p0} = -\frac{l_1}{l_2} \sim -\frac{1}{4}$$

# Fault-compensation scheme for CSNS II linac



- The accelerating fields have about 25% margins for fault-recovery.
- The RF powers have nearly 100% margins for fault-recovery.
- The cavities are powered independently for retuning the  $\phi_s$  and the  $E_{acc}$ .

## Summary

- The CSNS is operating reliably at 125kW and is launching the power upgrade project.
- A superconducting linac has been designed for the CSNS power upgrade project.
  - The prototype of spoke cavity is under vertical testing. The design of the elliptical cavity begins.
  - 2 cavity debuncher system is adopted to compress the energy jitter.
  - A fault-compensation scheme is used to keep the linac energy stable. Dedicated algorithm is under developing.



Thanks For Your Attention!

