

Progress of **S**hanghai **H**igh repetition rate XFEL and **E**xtrême light facility

Bo Liu, for the SHINE team
Shanghai Advanced Research Institute, CAS
2022.08.30

Outline

- **Introduction to the SHINE project**
- **Design and Layout**
- **R&D and Construction Progress**
- **Summary**

SHINE — Shanghai Hard X-ray FEL Facility


Shanghai **H**igh repetitio**N** rate XFEL and **E**xtrême light facility (*SHINE*)

- SHINE is a high rep-rate XFEL facility, based on an 8 GeV CW SCRF linac, under development in Shanghai;
- This facility will be built in a 3.1 km long tunnel underground at Zhang-Jiang High Tech Park, across the SSRF campus;
- This XFEL facility has 3 undulator lines and 10 experimental stations in phase-I, and it can provide the XFEL radiation in the photon energy range of 0.4 -25 keV.
- This XFEL project was approved by the central government in 2017, and its groundbreaking was made in April, 2018, aiming at lasing in 2025.


This facility will be developed by Shanghai-Tech Univ., SARI and SIOM of CAS.

SHINE: General Parameters and Location

e-beam: 8 GeV
 Photon energy: 0.4-25 keV
 Pulse duration : 1-100fs
 Repetition : 1MHz
 Total length : 3.1km
 ca 30m underground



SHINE: A high rep-rate XFEL based on SCRF




➤ XFEL Facility +100 PW Laser Facility

| | Nominal |
|--------------------------|--------------------|
| Beam energy/GeV | 8.0 |
| Bunch charge/pC | 100 |
| Max rep-rate/MHz | 1 |
| Beam power/MW | 0.8 |
| Photon energy/keV | 0.4-25 |
| Pulse length/fs | 20-50 |
| Peak brightness | 5×10^{32} |
| Average brightness | 5×10^{25} |
| Total facility length/km | 3.1 |
| Tunnel diameter/m | 5.9 |
| 2K Cryogenic power/kW | 12 |
| RF Power/MW | 2.28 |

| FEL Line | Objective |
|----------------------------------|------------|
| FEL-I | |
| Photon energy/keV | 3-15 |
| Photon number per pulse @12.4keV | $>10^{11}$ |
| Max pulse repetition rate/MHz | 1 |
| FEL-II | |
| Photon energy/keV | 0.4-3 |
| Photon number per pulse @1.24keV | $>10^{13}$ |
| Max pulse repetition rate/MHz | 1 |
| FEL-III | |
| Photon energy/keV | 10-25 |
| Photon number per pulse @15keV | $>10^{10}$ |
| Max pulse repetition rate/MHz | 1 |

Layout of the SHINE accelerator



| Injector Parameters | Value |
|---|---------|
| Beam energy (MeV) | 100 |
| Bunch charge (pC) | 100 |
| Normalized emittance (95%, $\mu\text{m}\cdot\text{rad}$) | 0.4 |
| Slice energy spread (10^{-4})* | 0.1/0.5 |
| Bunch length, rms (mm) | 1 |
| Peak current (A) | 12 |


| | No. of CM's | Avail. Cavities | Powered. Cavities* | Gradient (MV/m) | Eout (MeV) | σ_z (mm) |
|-----|-------------|-----------------|--------------------|-----------------|------------|-----------------|
| L0 | 1 | 8 | 7 | 16.3 | 100 | 1.15 |
| L1 | 2 | 16 | 15 | 14.8 | 326 | 1.15 |
| HL | 2 | 16 | 15 | 13.1 | 265 | 1.15 |
| BC1 | - | - | - | - | 265 | 0.13 |
| L2 | 18 | 144 | 135 | 15.5 | 2229 | 0.13 |
| BC2 | - | - | - | - | 2229 | 0.006 |
| L3 | 24 | 192 | 180 | 15.5 | 5120 | 0.006 |
| L4 | 30 | 240 | 226 | 15.5 | 8734 | 0.006 |
| Dcp | - | - | - | - | 8725 | 0.006 |

 750kV VHF gun + Single cavity CM

+ 1.3GHz SCRF cryomodules: 75 + 3.9GHz SCRF cryomodules: 2

Beam Switchyard

One SRF Linac → Three FEL Lines




At least 3 LTU deflection branches and 1 straight dump line


- **LTU-2:** linac → FEL-II in Middle Undulator tunnel
 - 3.0° deflecting angle, +1.85m horizontal offset
- **LTU-3:** linac → FEL-III in West Undulator tunnel
 - 3.6° deflecting angle, -8.90m horizontal offset
- **LTU-1:** linac → FEL-I in Middle Undulator tunnel
 - 2.0° deflecting angle, -1.45m horizontal offset
- **LTD:** linac → Dump in middle of #2 Shaft

Fast vertical kicker Set + DC Lamberson Septum

- Bunch-by-Bunch beam distribution of 1 MHz beam
- ~ 1 mrad kick angle, ~17 mm Y-offset @ Lamberson




Lattice design for minimizing CSR induced emittance growth



Undulator Layout and FEL Schemes

Three undulator beamlines to cover the photon energy range 0.4-25keV, external seeding and self-seeding schemes have been adopted for fully coherent FEL generation:

- FEL-I (3-15keV) : SASE、self-seeding
- FEL-II (0.4-3keV) : EEHG/HGHG、self-seeding
- FEL-III (10-25keV) : SASE、self-seeding



Beam parameters:

100pC, 1.5kA

0.4 μ m-rad, 0.01% energy spread

10 End-Stations @ SHINE facility

FEL-I Hard X-ray End-stations

- **HSS:** Hard X-ray Scattering and Spectroscopy
- **CDS:** Coherent Diffraction Endstation for Single Molecules and Particles
- **SEL:** Station of Extreme Light
- **XFEL + 100 PW Laser System**

FEL-II Soft X-ray End-stations


- **AMO:** Atomic, Molecular, and Optical Science
- **SES:** Spectrometer for Electronic Structure
- **SSS:** Soft X-ray Scattering and Spectroscopy

FEL-III Hard X-ray End-stations

- **HXS:** Hard X-ray Spectroscopy
- **SFX:** Serial Femtosecond Crystallography
- **CDE:** Coherent Diffraction Imaging
- **HED:** High Energy Density Science







SEL: XFEL + 100 PW Laser System

The marriage of optical laser pulse with an intensity of 10^{23}W/cm^2 and intense XFEL will potentially open the gate for investigating high field vacuum **QED**



G. Mourou and T. Tajima

Layout of Beamlines and End-stations



Comparison of world-wide high rep-rate XFEL





| | European XFEL | LCLS-II | SHINE |
|-----------------|-------------------|--------------------|------------------|
| Facility site | Hamburg, Germany | Stanford, USA | Shanghai, China |
| Facility length | ~ 3.4km | ~2.0km | ~ 3.1km |
| Photon energy | 0.5 ~ 24keV | 0.2 ~ 5keV | 0.4 ~ 25keV |
| E-beam energy | 17.5GeV | 4GeV | ~ 8GeV |
| Rep. rate | 3000×10 Hz | 0.93MHz | 1MHz |
| Beam current | ~ 0.03mA | ~ 0.1mA | ~ 0.1mA |
| Budget | ~1.5 billion euro | ~1.045 billion USD | ~ 10 billion RMB |
| Time schedule | 2009-2018 | 2014-2022 | 2018-2025 |
| tunnel | 6-38m underground | Half-underground | 30m underground |
| Mode | Macro Pulse | Continuous wave | Continuous wave |
| FEL lines | 5 (3 initial) | 2 | 6 (3 initial) |

R&D and Construction Progress

- Groundbreaking was made on April 27, 2018. Construction of shafts is in good progress;
- Accelerator engineering design, technical infrastructure development, component prototyping and long-lead equipment procurements are underway;
- Beamline design optimization are being carried out, R&D of key optics component and Pixel array detector development are in progress;
- Technical and engineering design of high energy OPCPA, R&D of key laser technologies for SEL are in progress;
- ...

Development of the VHF Gun

The fabrication of the VHF electron gun developed by Tsinghua University has been completed.



| | |
|--------------------------------|-------------------------|
| Frequency | 216.67 MHz |
| Cathode gradient | 30 MV/m |
| Input power | 90.4 kW |
| Maximum surface electric field | 36.99 MV/m (2.5kilp) |
| Maximum surface power density | 28.45 W/cm ² |
| Voltage | 868 keV |
| Stored energy | 2.24 J |
| Quality factor Q_0 | 33717 |
| Shunt impedance | 8.34 M Ω |

High power test has been done. CW 70kW power has been input into the gun with maximum temperature increase less than 40°C. Mechanical tuners have been successfully applied in gun detuning.


Courtesy Tsinghua University team

Development of the VHF Gun


Test beamline has been constructed. The designed maximum beam energy is ~30 MeV.



Dark current test




~14 uA@72 kW




Photon-induced beam First beam

Beam energy is 788 keV
measured by the dipole
downstream the gun.



Development of the SHINE Cryomodule

- SHINE Linac consists of 75 1.3GHz cryomodules (CMs) for beam accelerating, and two 3.9GHz cryomodules for non-linear correction.
- The cryomodule design is based on the TESLA technology and refers to European XFEL and LCLS-II
 - Prototypes & infrastructures built for R&D and production
 - First standard 8-cavity (BCP refurbished) CM, RF tested in June 2022, has reached its main goal (>128 MV, >1.0E+10, <1 nA).
 - More standard 8-cavity (High Q) CMs, in preparation, include midT-baked and N-doped cavities.
 - High-Q technologies (N-doping& midT-baking) have been achieved on 1.3 GHz 9-cell cavities.



CM with 8 BCP'ed cavities under testing


More details in: TH1PA01
Dr. Yiyong Liu's talk on Thursday




R&D on High-Q 9-cell cavities

- ◆ High-Q technologies (both N-doping& midT-baking) have been achieved on SHINE 1.3 GHz 9-cell cavities, with $Q_0 > 2.7E+10$ @16-21MV/m and max Eacc > 25 MV/m in average, based on the new SHINE facilities co-built in Wuxi; and have been replicated by different companies, including RI and ZANON.

Cavities treated with SHINE facilities in Wuxi



First 2 cavities produced by RI with SHINE High-Q recipe



Permanent Magnet Undulators

| | FEL-I | | FEL-II |
|-------------------|----------------|--|---|
| Type | Planar | Planar | EPU |
| Periodic Length | 26mm | Double period: 75 mm&55mm Normal period: 55mm | 68 mm |
| Quantities | 42 | 14/22 | 4 |
| Segment Length | 4.0 m | 4.0 m | 4.0 m |
| Number of Periods | 152 | 71 for U55; 52 for U75 | 58 |
| Maximum Field | 1.02T | 1.25T for U55 1.5T for U75 | 1.5 T for H.&V. Mode bx=by=1.06T @circular mode |
| Minimum Gap | vertical 7.2mm | vertical 10.2mm | vertical gap 3mm center area \varnothing 7.2mm |
| Structure | Hybrid | Hybrid | APPLE-III |

EPU Prototype



Magnetic force cancellation (cancellation for F_x, F_y, F_z)

- Max load in F_y : before $-7t \sim +4t$ after $-2t \sim -2t$
- 4 center arrays APPLE-III
- 8 arrays for magnetic force cancellation

Magnetic performance

- bx/by peak field 1.5T @ planar mode **is achieved**
- bx=by=1.06T @ circular mode **is achieved**

Prototype Plan: Start shimming, will be finished in Sep. 2022



Permanent Magnet Undulators

PU Prototype U26 and U55&75


Planar Undulator U26

- 4 Four Servo Motors.
- Precision gap control with accuracy $\pm 1\mu\text{m}$.
- Max Taper 0.3mm for 4m undulator.
- Hybrid magnetic structure: peak field 1.02T@7.2mm



Double periods U55&75: similar design to U26

- Two periods arrays fixed on the same girder
- **Switch** 100mm between U55 arrays to U75 arrays **in x-direction**
- An optimized **phase delay** 15.9mm from U55 to U75 **in z-direction**
- **working logic**: U55 gap open \rightarrow switch x position to U75 center \rightarrow switch shift from -15.9mm to 15.9mm \rightarrow U75 gap close

Prototype: Start parts processing, will be finished in May. 2023



prototype U55&75




Total magnetic force in double period U55&75

Superconducting Undulator Prototype

- There are 504 horizontal racetrack coils with NbTi wire in one undulator.
- Five power supplies will be used, two for the end coils, three for the main coils including one for the “phase shifter” in the middle.
- There is no beam vacuum chamber.
- The thermal shield and the HTS leadings are cooled by 50K GHe, and the magnet is cooled by 4K LHe.
- The prototype has been assembled and will be tested in next two months.
- The magnetic fields will be measured by a Hall probe system with three Hall sensors, one temperature sensor and an optic system used to locate the 3D positions of the Hall sensors.


| | |
|------------------|-------------|
| Undulator Length | 4.5 m |
| Period Length | 16 mm |
| Magnetic Length | 4 m |
| Pole Gap | 5 mm |
| Beam Gap | 4 mm |
| Peak Fields | 0.68-1.58 T |



Kicker Prototypes





Lumped-inductance Kicker

| Key parameters of Lumped-inductance Kicker | | | |
|--|-------|-----------------|----------|
| Beam energy | 8 GeV | Bending angle | 0.1 mrad |
| Effective length | 0.5 m | Max. Rep. rate | 1 MHz |
| Aperture(H) | 10 mm | Field intensity | 5.3 mT |
| Aperture(V) | 16 mm | Peak current | 50 A |






Transmission-line Kicker.

| Key parameters of Transmission-line Kicker | | | |
|--|--------------|------------------|---------------|
| Beam energy | 8 GeV | Bending angle | 0.1 mrad |
| Effective length | 0.8 m | Max. Rep. rate | 1 MHz |
| Aperture(H) | 25 mm | Field intensity | 3.3 mT |
| Aperture(V) | 25 mm | Peak current | 67 A |
| LC section number | 20 | Kicker impedance | 12.5 Ω |
| Ceramic beampipe | $\Phi 15$ mm | LC parameter | 50nH/320pF |




Development of the Timing System

- Precise distribution and synchronization of the 1.003086MHz timing signals over a long distance of about 3.1 km
- Two prototype systems were developed.
- The **non-standard clock transmission** was proposed and verified.
- **Beam-synchronous trigger signal distribution**
 - Jitter between the slave node output and reference signal <10ps
 - Jitter between slave nodes outputs <5ps
- Random-event trigger signal distribution



Development of the Synchronization System



RF master oscillator (commercial, R&S)

- 8.2 fs rms jitter@[10Hz, 10MHz]

Optical master oscillator (commercial, Menhii)







- 16.8 fs rms jitter of lock to RMO

31-port PMF splitter distribution

- Temperature-stabilized platform
- Fiber length stabilizer(BOC)
- 4 ns motorized optical delay Line
- 1.1 fs short-term rms jitter
- 2 fs long-term drift



Laser oscillator locking

- Two-color balanced optical cross-correlator
- 8.7 fs short-term rms jitter
- 1.2 fs long-term drift




Development of the Beam Signal Processor


- A generic beam signal processor has been developed for SHINE, which is used for the measurement of stripline BPM, cold button BPM, cavity BPM, bunch charge, BAM, wire scanner, beam loss, and bunch length.
- 1U height stand alone structure based on an Zynq UltraScale+ MPSoC FPGA. Two FMC connectors support an four channel ADC board (14bits, 1GSPS) and a White Rabbit timing board.



Active Vibration Isolation Prototype





BBA model



Test of active vibration isolation prototype

- Goal: Vibration stability of quadrupole center (H/V, RMS, >1Hz) $\leq 0.15\mu\text{m}$
- Ground vibration is much higher than $0.15\mu\text{m}$
- Active vibration isolation prototype is tested. Vibration of dummy load is reduced by at least 30% compared with ground vibration and can reach $\leq 0.15\mu\text{m}$.



SHINE Cryo-plants

Bird view of SHINE





2 sets of 4kW@2K cyroplants (for SHINE main facility)


Cryogenic multi-channel transfer lines

1 set of 4kW@2K cyroplant (for SHINE main facility)
1 set of 1kW@2K cyroplant (for SHINE test facility)

SHINE Cryo-plants



1st Cryo-plant passed the FAT and will be shipped soon.





Compressor hall construction



1st Compressors arrived at site


Linac and FEL Undulator Tunnels


(5.9m diameter)





- Left: cross section of the linac tunnel
- Right: cross section of undulator tunnel

Groundbreaking on April 27, 2018







Summary

- SHINE is a high rep-rate hard X-ray FEL facility being developed in Shanghai, consisting of an 8 GeV CW SCRF linac, a 100PW laser system, 3 phase-I undulator lines and 10 end-stations;
- This hard X-ray FEL project started its civil construction in April 2018, aiming to achieve the first XFEL lasing in 2025;
- R&Ds of several key technologies and key components are still ongoing.
- Technical and engineering design is almost frozen, and mass production of several key components is in progress.

A perspective view of a long, brightly lit tunnel. The tunnel's interior is made of metallic, perforated panels that create a rhythmic pattern of light and shadow. A central track or walkway runs down the length of the tunnel, leading the eye towards a bright light at the far end. The overall atmosphere is clean, industrial, and futuristic.

Thanks for Your Attention !

谢谢!