

THE ESRF ACCELERATOR UPGRADE:

THE EXTREMELY BRILLIANT SOURCE (EBS) PROJECT

OVERVIEW AND ENGINEERING CHALLENGES

Philippe Marion, Jean-Claude Biasci, Loys Goirand, Yves Dabin

marion@esrf.fr





This presentation is given on behalf of many ESRF contributors.

A specific acknowledgement must be mentioned to **Pantaleo RAIMONDI** who proposed the project and is the EBS project manager.

The contribution of Loys GOIRAND and Jean-Claude BIASCI should be underlined as technical coordinators of all EBS engineering projects and of Yves DABIN for expertise and modeling works.







- The ESRF Extremely Brilliant Source (EBS): context, time schedule, expected gain.
- Engineering challenges



The ESRF is a third generation light source

- Location: Grenoble, France
- Staff: 600
- Start User Mode 1994







Sol 6

THE CURRENT ESRF





42 Beamlines (including 12 Bending Magnet Beamlines)

Energy	6.04	GeV
Storage ring circumference	844	m
Multibunch current	200	mA
Horizontal emittance	4000	pm.rad
Vertical emittance	4	pm.rad

emittance ~ *beam size x beam divergence emittance = cst along the ring*



THE EBS PROJECT: MAIN FIGURES



The **Extremely Brilliant Source** Project: Design and Build **a new storage Ring** to be installed in place of the existing one, with the following objectives and parameters:

- Substantially decrease the Store Ring Equilibrium Horizontal Emittance
- Increase the photon source brilliance and its coherence fraction
- Green light in June 2014. Installation in 2019-2020. Budget: 100 ME
- > Must fit in the same tunnel : same circumference as much as possible
- IDs at same locations: keep Beamlines where they are
- Re-use injector complex



THE EBS PROJECT: MAIN FIGURES



The **Extremely Brilliant Source** Project: Design and Build **a new storage Ring** to be installed in place of the existing one, with the following objectives and parameters:

- Substantially decrease the Store Ring Equilibrium Horizontal Emittance
- Increase the photon source brilliance and its coherence fraction
- Green light in June 2014. Installation in 2019-2020. Budget: 100 ME
- > Must fit in the same tunnel : same circumference as much as possible
- IDs at same locations: keep Beamlines where they are
- Re-use injector complex

e⁻ beam properties

	Now	EBS	
Energy (GeV)	6.04	6	
Multibunch current (mA)	200	200	
Circumference (m)	844.39	843.98	
Horizontal emittance (pm.rad)	4000	140	reduced b factor 29
Vertical emittance (pm.rad)	4	5	

emittance ~ *beam size x beam divergence emittance* = *cst along the ring*



GAIN IN PHOTON BEAM BRILLIANCE & COHERENT FRACTION



EBS MASTER PLAN (2015-2020)



The EBS Major Milestones

	2015	201	6	2017		201	8		2019	2020	
Planning	SOND	JFMAMJJ	ASOND	J F MA MJ J	ASOND	J F MA MJ J	ASOND	JFMAN	MJJASOND	JFMAMJJ	ASOND
User Service Mode (USM)											
Design, Procurment											
Production											
Assembly											
Dismantling											
Installation											
Machine Commissioning											
Beamline Commissioning											
Friendly Users											

Courtesy of Pantaleo Raimondi





The EBS Major Milestones





Courtesy of Pantaleo Raimondi



The EBS Major Milestones

- Pre-assemble fully equipped girders before end of 2018
- Shutdown for dismantling / installation from 01/2019 to 12/2019



Courtesy of Pantaleo Raimondi



The EBS Major Milestones

- Pre-assemble fully equipped girders before end of 2018
- Shutdown for dismantling / installation from 01/2019 to 12/2019
- Start Storage Ring commissioning: 12/2019



02/12/2019 – Start of storage ring commissioning phase_

May-July 2020 – Friendly Users

25/08/2020 – Start of USM

Courtesy of Pantaleo Raimondi



MEDS 5







Design completed

- Manufacturing contracts placed
- Pre-series components delivery planned from September to December 2016





Design completed

Manufacturing contracts placed

Pre-series components delivery planned from September to December 2016

> Prototypes: Girder, Al vacuum chambers, Absorbers, RF fingers, ... :

Satisfactory results obtained after optimisation (see details in dedicated presentations)



012



> Standard cells Magnets, Girders, Supports, Vacuum chambers, Absorbers:

Design completed

Manufacturing contracts placed

Pre-series components delivery planned from September to December 2016

Prototypes: Girder, Al vacuum chambers, Absorbers, RF fingers, ... :

Satisfactory results obtained after optimisation (see details in dedicated presentations)

Injection zone (<u>see poster from Trevor Mairs</u>), Diagnostics, collimators, Assembly & handling tools:

Design in progress





Design completed

Manufacturing contracts placed

Pre-series components delivery planned from September to December 2016

> Prototypes: Girder, Al vacuum chambers, Absorbers, RF fingers, ... :

Satisfactory results obtained after optimisation (see details in dedicated presentations)

Injection zone (<u>see poster from Trevor Mairs</u>), Diagnostics, collimators, Assembly & handling tools:

Design in progress

> Temperature induced position drifts of girders, magnets and BPMs:

Modeling and mock up tests in progress (see details in dedicated presentation)





Design completed

Manufacturing contracts placed

Pre-series components delivery planned from September to December 2016

> Prototypes: Girder, Al vacuum chambers, Absorbers, RF fingers, ... :

Satisfactory results obtained after optimisation (see details in dedicated presentations)

Injection zone (<u>see poster from Trevor Mairs</u>), Diagnostics, collimators, Assembly & handling tools:

Design in progress

> Temperature induced position drifts of girders, magnets and BPMs:

Modeling and mock up tests in progress (see details in dedicated presentation)

>Infrastructure adaptations:

Some contracts placed / some CFTs in progress







Courtesy of Pantaleo Raimondi

ESRF





Courtesy of Pantaleo Raimondi

ESRF



- The ESRF Extremely Brilliant Source (EBS): context, time schedule, expected gain.
- Engineering challenges



PRESENT LATTICE VS NEW ESRF LATTICE

ESRF storage ring = 32 cells Each cell = 26.4m long (21.2m arc + 5.2m insertion device)

Present ESRF lattice

Double Bend Achromat = (2 dipoles + 15 quad. sext.) per cell

ID length = 5 m (standard) / 6m / 7m





PRESENT LATTICE VS NEW ESRF LATTICE



ESRF storage ring = 32 cells Each cell = 26.4m long (21.2m arc + 5.2m insertion device)

Present ESRF lattice

Double Bend Achromat = (2 dipoles + 15 quad. sext.) per cell ID length = 5 m (standard) / 6m / 7m

ESRF EBS lattice

Hybrid 7 Bend Achromat = (4 dipoles + 3 dipoles-quad + 24 quad., sext., oct.) per cell ID length = 5 m







PRESENT LATTICE VS NEW ESRF LATTICE



ESRF storage ring = 32 cells Each cell = 26.4m long (21.2m arc + 5.2m insertion device)

Present ESRF lattice

Double Bend Achromat = (2 dipoles + 15 quad. sext.) per cell ID length = 5 m (standard) / 6m / 7m

ESRF EBS lattice

Hybrid 7 Bend Achromat = (4 dipoles + 3 dipoles-quad + 24 quad., sext., oct.) per cell ID length = 5 m





31 magnets per cell instead of 17 currently

Free space between magnets (total for one cell): 3.4m instead of 8m today !!



EBS – ENGINEERING CHALLENGE #1 = LACK OF SPACE





See at 14:20 today presentation by L. Goirand: "EBS Vacuum chambers and contact fingers"

ESRF





Source stability specification: EBS vs "old" ESRF

		Average e- rms beam size [µm]	Beam position stability required = 0.1x e- beam size [µm]	
EDO	Н	26	2.6	U - Uarizanta
EBS	V	4	0.4	V = Vertical
	Н	310	31.0	
	V	9	0.9	





Source stability specification: EBS vs "old" ESRF

		Average e- rms beam size [µm]	Beam position stability required = 0.1x e- beam size [µm]	
	Н	26	2.6	II – Horizopta
ER2	V	4	0.4	H = Horizonia V = Vertical
	Н	310	31.0	
	V	9	0.9	

Still much more critical in V than in H (factor 6).

In V, EBS is 2.2 times more demanding than old ESRF.



BPMs position stability requirements

Target specification for the position stability of e- Beam Position Monitors in Vertical:

Over 8 hour (Thermal + ground drifts): < 1µm RMS Over 1-100Hz (Vibration): < 200nm RMS

- Works in progress on the air temperature stability
- BPM stability will be measured on a mock up of a complete girder
- Careful management of ground drifts





BPMs position stability requirements

Target specification for the position stability of e- Beam Position Monitors in Vertical:

 $< 1 \mu m RMS$ Over 8 hour (Thermal + ground drifts): < 200nm RMS Over 1-100Hz (Vibration):

- Works in progress on the air temperature stability
- BPM stability will be measured on a mock up of a complete girder
- Careful management of ground drifts

Magnets static position requirements

Alignment specification requested by accelerator physicists: Magnet to Magnet and Girder to Girder: Horizontal: < 50µm < 50µm

Challenging specification for the initial alignment considering all sources of errors of the alignment process.

Vertical:

- Careful management of thermal drifts required
- Careful management of ground drifts required

See today at 10:10: "Thermal stability of the new ESRF EBS" by B. Tampigny























Magnets and Girders: Vibration stability. Sensibility to random magnets displacements





ESRF

Example: Combined Dipole-Quadrupole magnets

A novel design with an open shape, curved poles shapes and precise shape tolerances

- Combined dipole quadrupole (0.54T and 37T/m), 3 magnets per cell (x 32 cells)
- High accuracy mechanical assembly : 80µm tolerance on poles surfaces to be preserved after opening – closing and with magnetic forces.
- Mechanical design proposed by ESRF, recently finalised with magnets supplier.





The poles are curved to follow e- orbit and vacuum chamber. Individual pole shape tolerance 40µm.



The European Synchrotron

Courtesy of Gael Le Bec, Francois Villar



ESRF EBS Overview & Engineering challenges - P. Marion - MEDSI 2016 - 11-16 September



➤The EBS project (new ESRF storage ring) will enable x30 reduction the e- beam horizontal emittance. The design of the standard sections of the new storage ring is now completed and the main manufacturing contracts started.



CONCLUSION



The EBS project (new ESRF storage ring) will enable x30 reduction the e- beam horizontal emittance. The design of the standard sections of the new storage ring is now completed and the main manufacturing contracts started.

>The main engineering challenges are:

 Extreme compactness/lack of space which obliged to multiple design iterations and to complex vacuum chambers.

Static precision requirements: 2.2 times lower value than old ESRF (in vertical)
⇒ Demanding but achievable.

 \Rightarrow Modeling and measurements of thermal drifts of magnets and BPMs on a mock up in progress.

Vibration stability of magnets required: 2.2 times more demanding than old ESRF
⇒ Girders and magnets supports designed for maximum stiffness.
1st resonant frequency = 51Hz measured on prototype girder.

 Manufacture of some magnets and vacuum chambers within the requested tolerances. We are impatient to inspect the pre-serie parts in the coming months...



CONCLUSION



The EBS project (new ESRF storage ring) will enable x30 reduction the e- beam horizontal emittance. The design of the standard sections of the new storage ring is now completed and the main manufacturing contracts started.

>The main engineering challenges are:

 Extreme compactness/lack of space which obliged to multiple design iterations and to complex vacuum chambers.

Static precision requirements: 2.2 times lower value than old ESRF (in vertical)
⇒ Demanding but achievable.

 \Rightarrow Modeling and measurements of thermal drifts of magnets and BPMs on a mock up in progress.

Vibration stability of magnets required: 2.2 times more demanding than old ESRF
⇒ Girders and magnets supports designed for maximum stiffness.
1st resonant frequency = 51Hz measured on prototype girder.

 Manufacture of some magnets and vacuum chambers within the requested tolerances. We are impatient to inspect the pre-serie parts in the coming months...

➢ Most beamlines are compatible and some already optimised for the new source. However, to fully exploit the new source and explore new scientific ideas, the ESRF Upgrade program includes the construction of 4 new beamlines and the refurbishment of 7-9 beamlines in 2017-2022. No rest for the engineers !!





- This presentation is given on behalf of many ESRF contributors.
- A specific acknowledgement must be mentioned to **Pantaleo RAIMONDI** who proposed the project and is the EBS project manager.
- The contribution of **Loys GOIRAND** and **Jean-Claude BIASCI** should be underlined as technical coordinators of all EBS engineering projects and of **Yves DABIN** for expertise and modeling works.

