

# PROGRESS ON THE MAGNETIC PERFORMANCE OF PLANAR SUPERCONDUCTING UNDULATORS


**MATTHEW KASA**  
Magnetic Devices Group  
Advanced Photon Source

**ON BEHALF OF:**

Chuck Doose  
Joel Fuerst  
Efim Gluskin  
Yury Ivanyushenkov

October 11, 2016  
North American Particle Accelerator Conference  
Chicago, IL





**5300**  
researchers  
each year

## ADVANCED PHOTON SOURCE


- 7 GeV Synchrotron Radiation Facility
- Researchers come to the APS from:
  - 50 states plus Puerto Rico and the District of Columbia
  - 33 countries
  - 150 companies
  - 250 universities




# TALE OF TWO UNDULATORS



Assembled cores before winding and epoxy impregnation



Cold mass assembly ready for installation



End view of the cold mass assembly installed into the cryostat

Parameter	Value
Cryostat length, m	2.06
Magnetic length, m	1.1
Undulator period, mm	18
Magnetic gap, mm	9.5
Beam vacuum chamber vertical aperture, mm	7.2
Undulator peak field, T	0.97
Undulator parameter, K	1.63
Operating Current, A	450


SCU Specifications

- Two undulators with identical parameters were constructed. Both were wound with 0.6 mm NbTi
  - SCU18-1
  - SCU18-2
- Lessons learned from the SCU18-1 assembly were used to improve the quality of the magnetic performance of SCU18-2


# UNDULATOR FIELD QUALITY




Precision machined core



Precise placement of the superconductor [2]



Cross section of epoxy impregnated winding [2]



Magnetic gap

- Three main factors influence the repeatability of the peak magnetic field from one undulator period to the next
  - Precise machining and repeatability of the winding groove [1]
  - Quality of the winding [2]
  - Uniformity of the magnetic gap
- One figure of merit that is typically used is the RMS phase error from Hall probe field scans
  - Goal was to achieve phase errors  $<5^\circ$  RMS over the entire operating range without magnetic shimming



[1] E. Trakhtenberg, M. Kasa, Y. Ivanyushenkov, "Evolution of the Design of the Magnet Structure for the APS Planar Superconducting Undulators," this conference.

[2] E. Gluskin, "Development and Performance of Superconducting Undulators at the Advanced Photon Source," Synchrotron Radiation News, Vol. 28, Iss. 3, 2015.





# SCU18-1 ASSEMBLY



- Cores were precisely machined and wound
  - Groove width and depth within 50  $\mu\text{m}$ , RMS error of 15  $\mu\text{m}$
  - Periodicity of the winding grooves within 30  $\mu\text{m}$ , RMS error of 10  $\mu\text{m}$
  - Flatness of the pole side within 30  $\mu\text{m}$ , RMS error of 10  $\mu\text{m}$
- After winding and epoxy impregnation each core developed a bow of  $\sim 100 \mu\text{m}$  resulting in an increased gap at the ends of the assembly
- At the time there was no method of accurately measuring and correcting the magnetic gap



# SCU18-2 ASSEMBLY

- Similar machining and winding precision was achieved
- Similar bowing of the cores after winding and epoxy impregnation
- This time we had the ability to accurately measure and correct the magnetic gap before installation into the cryostat
  - Capacitec Gapman Gen3 portable electronic feeler gage, 0.254  $\mu\text{m}$  resolution,  $\pm 5 \mu\text{m}$  accuracy
  - External clamps and extended gap spacers







# HALL PROBE FIELD SCANS


- Noticeable improvement in the uniformity of the peak fields

	Mean (T)	Std. Dev. (T)
SCU18-1	0.9650	0.0050
SCU18-2	0.9630	0.0022




# 7 GEV ELECTRON TRAJECTORY FROM HALL PROBE MEASUREMENTS






# RMS PHASE ERRORS OF SCU18-1 AND SCU18-2



Helmholtz-like coil – 1<sup>st</sup> Integral



Dipole coil – 2<sup>nd</sup> Integral

Parameter	Unit	SCU18-1	SCU18-2
I1y	G-cm	20*	25*
I1x	G-cm	35	200
I2y	G-cm <sup>2</sup>	25,000*	12,000*
I2x	G-cm <sup>2</sup>	5,000	35,000
Normal Quadrupole	G	60	65
Skew Quadrupole	G	20	135
Normal Sextupole	G/cm	100	100
Skew Sextupole	G/cm	150	120
Normal Octupole	G/cm <sup>2</sup>	60	40
Skew Octupole	G/cm <sup>2</sup>	20	20

\*With correction coils energized

# 1<sup>ST</sup> AND 2<sup>ND</sup> FIELD INTEGRALS AND INTEGRATED MULTIPOLES

- Correction coils available for the vertical 1<sup>st</sup> and 2<sup>nd</sup> field integrals
- Integrated field measurements will be verified by beam based measurements



AFTER THE SUCCESSFUL IMPLEMENTATION OF GAP CONTROL MEASURES WE WERE ABLE TO CONSTRUCT A 1.1 M LONG SUPERCONDUCTING UNDULATOR WITH PHASE ERRORS OF  $\sim 2^\circ$  OR LESS OVER THE ENTIRE OPERATING RANGE.

SCU18-1 HAS BEEN IN OPERATION ON THE APS STORAGE RING SINCE MAY 2015 AND SCU18-2 WAS RECENTLY INSTALLED IN SEPTEMBER 2016.

DURING THIS TIMEFRAME, A 1.5 M LONG SCU WAS BUILT AND TESTED WITH A LIMITED IMPLEMENTATION OF THE GAP CONTROL MEASURES. THIS DEVICE ACHIEVED PHASE ERRORS OF  $\sim 5^\circ$  OR LESS. THERE ARE FUTURE PLANS TO TEST THIS DEVICE WITH ALL OF THE GAP CONTROL MEASURES IN PLACE.

**THANK YOU!**