

Towards an International Linear Collider



Barry Barish

Caltech / GDE

25-June-07



The GDE Plan and Schedule

2005

2006

2007


2008

2009

2010

Global Design Effort

Project



Baseline configuration



Reference Design

LHC
Physics



Engineering Design



ILC R&D Program



Expression of Interest to Host




International Mgmt

RDR ILC Schematic

- 11km SC linacs operating at 31.5 MV/m for 500 GeV
- Centralized injector
 - Circular damping rings for electrons and positrons
 - Undulator-based positron source
- Single IR with 14 mrad crossing angle
- Dual tunnel configuration for safety and availability

~31 Km





RDR Design Parameters

Max. Center-of-mass energy	500	GeV
Peak Luminosity	$\sim 2 \times 10^{34}$	$1/\text{cm}^2\text{s}$
Beam Current	9.0	mA
Repetition rate	5	Hz
Average accelerating gradient	31.5	MV/m
Beam pulse length	0.95	ms
Total Site Length	31	km
Total AC Power Consumption	~ 230	MW



RDR Design & “Value” Costs

The reference design was “frozen” as of 1-Dec-06 for the purpose of producing the RDR, including costs.

It is important to recognize this is a snapshot and the design will continue to evolve, due to results of the R&D, accelerator studies and value engineering

The value costs have already been reviewed twice

- 3 day “internal review” in Dec
- ILCSC MAC review in Jan

Σ Value = 6.62 B ILC Units

Summary

RDR “Value” Costs

Total Value Cost (FY07)
4.80 B ILC Units Shared

+

1.82 B Units Site Specific

+

14.1 K person-years
 (“explicit” labor = 24.0 M person-hrs
 @ 1,700 hrs/yr)

1 ILC Unit = \$ 1 (2007)



Assessing the RDR

- **Reviews (5 major international reviews + regional)**
 - **The Design:** “The MAC applauds that considerable evolution of the design was achieved ... the performance driven baseline configuration was successfully converted into a cost conscious design.”
 - **The R&D Plan:** “The committee endorses the approach of collecting R&D items as proposed by the collaborators, categorizing them, prioritizing them, and seeking contact with funding agencies to provide guidelines for funding.
 - **International Cost Review (Orsay):** Supported the costing methodology; considered the costing conservative in that they identify opportunities for cost savings; etc.
- **Final Steps**
 - The final versions of Executive Summary, Reference Design Report and Companion Document will be submitted to FALC (July), ILCSC and ICFA (August).



On track ... but what about Orbach?




“Completing the R&D and engineering design, negotiating an international structure, selecting a site, obtaining firm financial commitments, and building a machine could take us well into the mid-2020s, if not later,”

- **Our technically driven timeline is**
 - **Construction proposal in 2010**
 - **Construction start in 2012**
 - **Construction complete in 2019**
- **What do we need to do to achieve our timeline?**



Technically Driven Timeline






Engineering Design Phase


- **ILC Engineering Design**
 - We have a solid design concept in the reference design, but it is immature and needs engineering designs, value engineering, supporting R&D and industrialization.
- **GDE will be reorganized around a Project Management Office to reach this goal**
 - M. Ross, N. Walker and A Yamamoto – PM “Troika” + high level engineering managers in the project office
 - Central management will have authority to set priorities and direct the work
 - Resources for the engineering design and associated R&D appears feasible
 - Investments toward Industrialization and siting
 - Anticipate LHC results by ~2010. We are committed to be ready at that time!



Technically Driven Timeline



Double Tunnel



- Three RF/cable penetrations every rf unit
- Safety crossovers every 500 m
- 34 kV power distribution



Conventional Facilities

**72.5 km tunnels ~ 100-150 meters
underground**


13 major shafts \geq 9 meter diameter

**443 K cu. m. underground excavation:
caverns, alcoves, halls**

**92 surface “buildings”, 52.7 K sq. meters
= 567 K sq-ft total**






Civil Construction Timeline





On-surface Detector Assembly

CMS approach




CMS assembly approach:

- Assembled on the surface in parallel with underground work
- Allows pre-commissioning before lowering
- Lowering using dedicated heavy lifting equipment
- Potential for big time saving
- Reduces size of required underground hall



Technically Driven Timeline






Americas Fermilab Sample Site

Situation : *in solid rock, close to existing institute, close to the city of Chicago and international airport, close to railway and highway networks.*

Geology : *Glacially derived deposits overlaying Bedrock. The concerned rock layers are from top to bottom the Silurian dolomite, Maquoketa dolomitic shale, and the Galena-Platteville dolomites.*


Depth of main tunnels : *Average ~ 135 m*





Preconstruction Plan for Fermilab


Central Area fits inside the Fermilab boundary



**Site Characterization
of the Central Area can
be done**



Technically Driven Timeline



R & D -- Industrialization

The Task Forces

- The Task Forces were put together successively over a period of five months:



S0/S1-Cavities, Cryomodule



S2 -Cryomodule String Tests



S3 -Damping Rings



S4 -Beam Delivery System



S5-Positron Source


S6-Controls, not yet active

S7-RF

- Working in close collaboration with the Engineering and Risk Assessment team.



Technically Driven Timeline








Cavity Gradient – Goal

- Current status: Nine 9 cell cavities have been produced with gradients > 35 MeV/m. Not reproducible and needs several attempts at final processing.
- Goal: After a viable cavity process has been determined through a series of preparations and vertical tests on a significant number of cavities, achieve 35 MV/m at $Q_0 = 10^{10}$ in a sufficiently large final sample (greater than 30) of nine-cell cavities in the low power vertical dewar testing in a production-like operation e.g. all cavities get the same treatment.
 - **The yield for the number of successful cavities of the final production batch should be larger than 80% in the first test. After re-processing the 20 % underperforming cavities the yield should go up to 95%. This is consistent with the assumption in the RDR costing exercise.**

Cavity Gradient – Results




KEK single cell results:
 2005 – just learning
 2006 – standard recipe
 2007 – add final 3 μm fresh acid EP
Note: multi-cells are harder than singles

- Intermediate goal
 - Achieve 31.5 MV/m average operational accelerating gradient in a single cryomodule as a proof-of-principle. In case of cavities performing below the average, this could be achieved by tweaking the RF distribution accordingly.
 - Auxiliary systems like fast tuners should all work.
- Final goal
 - Achieve > 31.5 MeV/m operational gradient in 3 cryomodules.
 - The cavities accepted in the low power test should achieve 35 MV/m at $Q_0 = 10^{10}$ with a yield as described above (80% after first test, 95% after re-preparation).
 - It does not need to be the final cryomodule design




Module Test – Results






Technically Driven Timeline




- Ensure the e- cloud won't blow up the e+ beam emittance.
 - **Do simulations (cheap)**
 - **Test vacuum pipe coatings, grooved chambers, and clearing electrodes effect on e-cloud buildup**
 - **Do above in ILC style wigglers with low emittance beam to minimize the extrapolation to the ILC.**





Technically Driven Timeline



String Test – Goal

- Build 1 RF unit (3 cryomodules + 1 Klystron) to fully check:
 - What gradient spread can be handled by LLRF system. This test should be done with and without beam loading.
 - For heating due to high frequency HOMs.
 - Amplitude and phase stability.
 - Static and dynamic heat loads.
- To partially check:
 - Reliability
 - Dark current
 - for degradation or other weaknesses
- The ILC cryomodule is enough different than that of the TTF that a new system test is warranted.




Rough S2 Schedule

Phase	Completion date	Description
0	2005	TTF/FLASH, not final cavity design, type 3 cryomodule, not full gradient, has beam
0.5	2008	Extra tests at TTF/FLASH with same type cryomodules as phase 0
1	2008	1 cryomodule, not final cavity design, type 3 cryomodule (and/or) STF type cryomodule, not full gradient, no beam
1.1	2009	1 RF unit, not all final cavity design, not all type 4 cryomodules, not full gradient, beam not needed for tests, but should be built so it and the LLRF are debugged for the next step
1.2	2010	1 RF unit (replacing cryomodules of phase 1.1), final cavity design, full gradient, type 4 cryomodules, with beam
1.3	2011	1 RF unit (replacing cryomodules of phase 1.1), final cavity design, full gradient, type DFM cryomodules, with beam
1.4	2011	Tunnel mockup above ground. 1 RF unit perhaps built with parts taken from earlier tests. Includes RTML and e+ transport, no beam
2	2013	N RF units at one site (of the final ILC?) as a system test of final designs from multiple manufacturers, no beam
3	2013	XFEL




Technically Driven Timeline




Producing Cavities



4th generation prototype ILC cryomodule




Subdivision	Length (m)	Number
Cavities (9 cells + ends)	1.326	14,560
Cryomodule (9 cavities or 8 cavities + quad)	12.652	1,680
RF unit (3 cryomodules)	37.956	560
Cryo-string of 4 RF units (3 RF units)	154.3 (116.4)	71 (6)
Cryogenic unit with 10 to 16 strings	1,546 to 2,472	10
Electron (positron) linac	10,917 (10,770)	1 (1)





Technically Driven Timeline




Concept of IR hall with two detectors

may be
accessible
during run

The concept is evolving
and details being
worked out


accessible
during run

Platform for electronic and
services (~10*8*8m). Shielded
(~0.5m of concrete) from five
sides. Moves with detector. Also
provide vibration isolation.





Technically Driven Timeline



Achieving our ILC Timeline

“The other issues”

- We need to begin a campaign to prepare the way for submitting a winning proposal in about 2010.
 - Science Motivation is very strong, but we need LHC results for validation (~2010)
 - Must convince broader HEP and science communities on the ILC
 - Must engage the global governments to take ownership and develop international governance
 - Must develop a siting strategy
- The key to maintaining our timeline will be working these issues in parallel with developing an engineering design and completing the R&D