Measurements of Compression and Emittance Preservation after the First LCLS Bunch Compressor Chicane

K. Bane, Y. Ding, P. Emma, J. Frisch, Z. Huang, H. Loos, F. Sannibale, K. Sonnad, G. Stupakov, J. Wu, M. Zolotorev, *SLAC*, Stanford, CA 94309, USA, E. Prat, *DESY*, Hamburg, Germany

LCLS Injector Layout



System Status

- Most results without X-band, and without CSR bunch length monitor.
- Operation at 200pC low charge design point.
- X band system commissioned ~1 week ago, only have preliminary results
- CSR bunch length monitor saw first signals Saturday – no results yet.

- Use mm-wave gap monitor

 Note: this is the injector bunch compressor, second bunch compressor to be installed downstream later this year

Chicane is Motor Controlled with BPM, OTR Screen, & Collimator



Residual Dispersion Measurements & Correction



Additional Magnet Errors



- With constant magnet currents, move chicane magnets, look for orbit change downstream of compressor.
- Have found assembly problem with dipole will be corrected.

CSR Simulation* Through BC1

Bunch charge = 0.2 nC

 $\gamma \varepsilon_x$: 1.8 \rightarrow 2.7 μm



Assuming 1 keV initial rms energy spread, calculated in tracking.

* Using *Impact-T* and *Elegant*

Example Emittance Measurement with Quadscan on OTR Screen after BC1 Chicane



Measured and Simulated Emittance after BC1 vs. RF Phase Before BC1











Post-BC1 OTR Screen Images with and without Compression X-band adjusted for maximum compression



The total optical camera signal increases by up to 100-times for the case at right (COTR?) Could corrupt measurements at high compressions

Overall Status

- Measured emittance growth from compression matches model
- 1.7mm-mr (integrated) at 200pC, need 0.8 slice.
 System not optimized yet
- Commissioning X-band compression linearization now – should eliminate narrow "spike" on bunch, reduce CSR growth at strong compression
- Interesting evidence for Coherent Optical Transition Radiation (not directly useful for FEL)