



2011 PARTICLE ACCELERATOR CONFERENCE


March 28 - April 1, 2011 • New York, U.S.A.

PROGRESS ON SUPERCONDUCTING RF FOR THE CORNELL ENERGY- RECOVERY-LINAC


Matthias Liepe

Assistant Professor of Physics

Cornell University



The Cornell Energy Recovery Linac



- Cornell is developing the technology for an Energy Recover Linac (ERL) based x-ray light source.
- An ERL injector prototype has been developed, fabricated, and is currently under commissioning.
- Design work on the main linac cryomodule has started.


Outline

- Superconducting RF for the ERL injector
 - Challenges and solutions
- Superconducting RF for the ERL main linac
 - Challenges and solutions
- Summary and outlook



Superconducting RF for the ERL Injector

The High Current Cornell ERL Injector



Nominal bunch charge
 Bunch repetition rate
 Beam power
 Nominal gun voltage
 SC linac beam energy gain
 Beam current

 Bunch length
 Transverse emittance

design parameters

77 pC
 1.3 GHz
 up to 550 kW
 500 kV
 5 to 15 MeV
 100 mA at 5 MeV
 33 mA at 15 MeV
 0.6 mm (rms)
 < 1 mm-mrad

Achieved so far



77 pC
 50 MHz and 1.3 GHz
 125 kW
 350 kV
 5 to 15 MeV
 25 mA




World record for CW injector current!

ERL Injector: Technical Components

Superconducting RF for the ERL Injector



The Cornell ERL Cryomodule




- Number of 2-cell cavities 5
- Acceleration per cavity 1 – 3 MeV
- Accelerating gradient 4.3 – 13.0 MV/m
- R/Q (linac definition) 222 Ohm
- Q_{ext} $4.6 \times 10^4 - 4.1 \times 10^5$
- Total 2K / 5K / 80K loads: **30W / 60W / 700W**

- Number of HOM loads 6
- HOM power per cavity **40 W**
- Couplers per cavity 2
- RF power per cavity **120 kW**
- Amplitude/phase stability $10^{-4} / 0.1^\circ$ (rms)
- ICM length 5 m

ERL Injector Module Assembly at Cornell

Beamline in clean room




Gate valve internal to cryomodule

Cleanroom assembly fixturing

Vacuum vessel interface flange

1100 aluminum
80K shield

Cold mass assembly




5K manifold

2K 2-phase pipe


Magnetic shield II

80K shield



Beam entrance
gate valve

1100 aluminum
80K shield



Instrumentation
ports


RF coupler ports

ERL Injector SRF: Key Challenges

1. Limit emittance growth of the very low emittance beam in the injector module (essential for ERL x-ray performance)
2. Support high beam current operation up to 100 mA with short (2 ps) bunches
3. Transfer up to 100 kW of CW RF power per cavity to the beam
4. Provide excellent RF field / energy stability

Emittance Preservation and Cavity Alignment



- Avoid transverse kick fields:
 - Symmetrized beam line in injector module



- Excellent cavity alignment ($\pm 0.5\text{mm}$ required, **$\pm 0.2\text{mm}$ achieved**)


Fixed High Precision Cavity Support and Alignment

- High precision supports on cavities, HOM loads, and HGRP for “self” alignment of beam line
- Only very rough initial alignment is needed when beamline is assembled in clean room
- **Cavity string is aligned to ± 0.2 mm after cool-down!**






High Current Operation and HOMs

- HOM damping and HOM spectra measurements confirm excellent damping with **typical Qs of a few 1000**
- Total HOM power measurement gives longitudinal loss factor in good agreement with ABCI simulations
- Successfully operated injector SRF module with **beam currents of 25 mA**
 - ΔT of HOM absorbers small ($< 0.5\text{K}$). **Module should easily handle operation at $> 100\text{ mA}$.**




SRF Cavities and High RF Input Power


- SRF cavities meet gradient spec and have transferred >25 kW cw each to the beam
- Individual input couplers processed up to 25 kW cw
- Prototypes tested **up to 60 kW cw**, 80 kW pulsed



LLRF Field Control and Field Stability



Cornell digital LLRF control system



Excellent field stability achieved: amplitude: $\sigma_A/A < 2 \cdot 10^{-5}$

(in loop measurements)

phase: $\sigma_P < 0.01$ deg



2011 PARTICLE ACCELERATOR CONFERENCE

March 28 - April 1, 2011 • New York, U.S.A.



Superconducting RF for the ERL Main Linac

Cornell ERL Main Linac


Cavities per cryomodule	6
Cryomodules per linac	35 / 29
# linacs	2
# cavities	384
# cryomodules	64
Cryomodule length [m]	9.82
Linac length [m]	344 / 285
Total active length [m]	~310
Module Filling factor	0.49
Final energy [GeV]	5.0
Gradient [MV/m]	16

 = 0.25m Cold-warm transition

- 5 GeV total, 384 cavities
 - 13 MV per cavity (~16 MV/m)
 - 64 identical cryomodules, each with 6 cavities and a single quadrupole magnet
- Two continuous linac sections:



Cornell ERL Main Linac Cryomodule



- Number of 7-cell cavities 6
- Acceleration gradient **16.2 MV/m**
- R/Q (linac definition) 774 Ohm
- Qext **6.5×10^7**
- Total 2K / 5K / 80K loads: **76W / 70W / 1500W**



- Number of HOM loads 7
- HOM power per cavity 200 W
- Couplers per cavity 1
- RF power per cavity **5 kW**
- Amplitude/phase stability 10^{-4} / 0.05° (rms)
- Module length 9.8 m

Main Linac SRF: Key Challenges


1. Support efficient CW cavity operation with high dynamic cryogenic loads
2. Support high beam current ERL operation up to 2x100 mA with short (2 ps) bunches
3. Efficiently operate the SRF cavities at a high loaded quality factor $Q_L \geq 6.5 \times 10^7$ while still achieving excellent RF field stability.

Main Linac Cryomodule Design



- Fixed, high precision supports for the cavities and the HOM loads
- One thermal shield at ~40K
- Cryogenic manifolds sized for high dynamic heat loads
- Three layers of magnetic shielding



Magnetic Shielding at Residual Resistance




Axial magnetic field on axis, B_z





$B < 3 \text{ mG} \rightarrow \text{contribution to } R_{\text{res}} < 1 \text{ n}\Omega$

ERL Main Linac Cavity: RF Design (I)




Coupler kick compensation



Cell shape optimization for high R/Q of fundamental mode and strong HOM damping




ERL Main Linac Cavity: RF Design (II)





- Relaxed cavity shape tolerances:
 - increase the HOM frequ. spread
 - increase the risk of trapped HOMs
- Solution:
 - use several classes of cavities, which are small, controlled variations of the baseline 7- cell cavity design
 - yields threshold current >4 times above design value



ERL Main Linac Cavity: Mechanical Design and Prototyping



- Cavity was optimized for low microphonics
- Stiffening rings between the cells
 - reduce sensitivity of the fundamental mode frequency to changes in the LHe bath pressure (main source of cavity microphonics)
- Prototype cavities under fabrication
 - will be tested without and with beam in test/prototype cryomodules.




Precision of cell shape (± 0.2 mm)


HOM Beamline Loads and RF Absorbing Materials

Two reliable RF absorbing materials meeting all specifications have been identified:





- graphite loaded SiC,
- carbon-nanotube loaded ceramics



HOM Damper




SiC Absorber Ring




ERL Main Linac: Other Components


5 kW Input Coupler



Cold Magnet




Frequency Tuner



- Simplified 5 kW CW input coupler
- Superconducting magnet package
- Cold tuner (slow and fast piezo driven)

LLRF Field Control and Operation at Very High Loaded Q

- Demonstrated **highly efficient operation** of a full 9-cell cavity at **very high loaded quality factors up to $2 \cdot 10^8$** (Test of Cornell's LLRF system at HoBiCaT at HZB)




- **Exceptional field stability:** $\sigma_A/A < 1 \cdot 10^{-4}$, $\sigma_\phi \sim 0.01^\circ$
- **Fast RF field ramp** up in 0.5 s to high fields with piezo tuner

Active Microphonics Compensation

Piezo feedback on cavity frequency (ERL injector cavity):

⇒ **Reduced rms microphonics by up to 70%!**

⇒ **Important for ERL main linac, where $Q_L > 5 \cdot 10^7$ and $P_{RF} \propto \Delta f$!**






Summary and outlook


Summary and Outlook

- ERL injector cryomodule:
 - Designed, constructed, and successfully tested
 - **Cryogenics, cavity alignment, cavity voltage, input couplers, LLRF field control, and HOM damping all meet or exceed specs**
 - 25 mA cw beam accelerated to 5 MeV; should easily support 100 mA operation



Summary and Outlook

- ERL main linac cryomodule:
 - Module design well underway
 - Cavity design optimized for high currents and efficient cavity operation; cavity fabrication has started
 - Plan:
 - One cavity test module: starting 2012, including beam test
 - Full prototype main linac module in ~4 years



End

Thanks for you attention!