

High current SRF cavity at BNL


Wencan Xu

Brookhaven National Lab

Outline

- SRF Requirements of eRHIC
- BNL1 cavity in ERL prototype
- High current BNL3 cavity design
- HOM coupler design for BNL3cavity
- Mechanical design
- Summary

eRHIC: requirements



Electron beam Parameters	eRHIC
Bunch charge [nC]	3.5
Beam current [mA]	50
RMS Bunch Length[mm]*	2
Beam energy [GeV]	5-30
Number of Passes	6
Operation mode	CW

*bunch length maybe changed to 4mm.



HOM damping requirement

- Monopole: 7.3kW/cavity
- Dipole: $Q_{ext} \sim 40,000$
- Quadrupole: $Q_{ext} \sim 10^7$

- High current multipass ERL: HOM damping
- All in the existing RHIC tunnel : High “real estate gradient”: 12.3MV/m for eRHIC.

See: TUOAN4 in detail

BNL1: HOM damping





❖ Enlarged beam pipe

- Fundamental mode: attenuated in the beam pipe;
- HOMs: Propagate out of the cavity and are damped at room temperature with ferrite;

❖ Ferrite provides extremely good HOM damping, however, it also dramatically decreases the “real estate gradient”.

❖ However, very strong cavity-to -cavity coupling was found in the prototype model.

BNL1: CW operation




- The BNL1 cavity performed well during the vertical test ($Q_0 \sim 10^{10}$ at 20 MV/m)
- However, **12 MV/m** was observed to be the threshold at CW mode, due to the **AlMg₃ seal** located between the NbTi and stainless steel flanges on the beam pipe.
- Quasi-CW operation mode: Test showed that the cavity can safely (thermal stability) run **18 MV/m** with a **6.25% duty factor**.

See: TUP272, TUP56 in detail

Comparison of BNL1 and BNL3

BNL1 design:



BNL3 design:






Table I: 704 MHz 5-cell cavities at BNL

Parameters	BNL I	BNL III
Geometry Factor	225	283
(R/Q)/cell [Ω /cell]	80.8	101.26
E _{peak} /E _{acc}	1.97	2.46
B _{peak} /E _{acc} [mT/MV/m]	5.78	4.26
Length (cm)	152 + Two ferrite dampers	160
Beam pipe radius (mm)	120	110
Coupling factor [%]	3.00	3.02


2-stage HOM coupler design for eRHIC



- Between the two notches, $s_{21} < -65$ dB, 1st HOM is 0.82GHz, $S_{21} = -23$ dB,
- It still has good damping at high frequency
- Capacitors can be added to the transmission line to reduce the thermal conduction



See: TUP60 in detail

2-stage HOM coupler-model test







- The test by transmission line verified the design.
- Because of the big diameter ($D=72\text{mm}$) of the HOM couplers, the transmission line's diameter is so big that some HOM appears.

2-stage HOM couplers – on cavity




- We decided to have three HOM couplers at each end: to reduce power propagating through each HOM coupler, and also damping the HOMs better.

Impact of tapering into a waist



- * The waist's impact on loss factor is negligible with quasi-symmetric structure.
- * Cross-talk is also avoided by the waist.

Mechanical Design



- Three HOM couplers at each side of cavity;
- Cavity flange to flange length: 1.6 m;
- Radius of Stiffeners: 10.45 cm ($R_{iris} = 7.5$ cm)

Mechanical Characteristics

Parameters (2 K)	Results
Tuner[kHz/mm]	157.5
Tuning range[kHz]	+/-700
Frequency tuning sensitivity[kHz/lbf]	0.160
Lorentz detuning coefficient $k[\text{Hz}/(\text{MV}/\text{m})^2]$	1.36
Helium Pressure sensitivity[Hz/mbar]	26
First mechanical mode with LHe vessel[Hz]	162.2

Summary

- We got lots of experience during the operation of the BNL I cavity in ERL prototype.
- BNL3 cavity has been designed for the high current SPL and ERL-based machine- eRHIC.
- A new prototype HOM coupler for high current SRF cavity has been designed and tested.
- Mechanical analysis of BNL3 cavity has been done and copper prototype will be completed next month.

Thank you