




STATUS OF INJECTION COMPLEX VEPP-5

A.Starostenko
BINP, Novosibirsk

Outline

- ❑ General Description and layout
- ❑ Design of Linacs
 - Electron gun
 - Acceleration structures
- ❑ Results of linac's commissioning
- ❑ Design of Damping Ring
- ❑ Results of damping ring commissioning
 - Injection angle measurement
 - Closed orbit correction
 - Lattice correction
- ❑ Summary

General Description and layout



Klystron Gallery

Transfer line to VEPP-4M


Transfer line to VEPP-2000




Design of Linacs base parts

200kV Electron gun


$I_{\max} = 6,4\text{A}$ $N_e = 2 \cdot 10^{11}$ (e-)
(September.19.2014)



$I_{\max} = 7,4\text{A}$ $N_e = 2,2 \cdot 10^{11}$ (e-)
September.26.2014




Disk-loaded travelling wave accelerating structure



Accelerating structure




Accelerating cell




Operational frequency	2855.5 MHz
Internal cell diameter $2b$	83.75 mm
Iris diameter $2a$	25.9 mm
Iris thickness t	6 mm
Period D	34.99 mm
Operational mode of oscillation θ	$2\pi/3$
Relative phase velocity β_p	1
Relative group velocity β_g	0.021
Section length L	2.93 m
Total number of cells (incl. 2 WTT)	85
Unloaded quality factor Q_0	13200
Shunt impedance R_{sh}	51 MOhm/m
Time constant $\tau_{0a}=2Q_0/\omega_0$	1.471 μ s
Attenuation (by field) $\alpha=1/(\tau_{0a}v_{gr})$	0.108 m^{-1}
Filling time $T_f=L/v_{gr}$	0.465 μ s


Results of linacs commissioning



- Number of e⁻ on conversion target - $1.5 \cdot 10^{10}$ /pulse
 - Energy of e⁻ on conversion target – 275 MeV
 - Energy of e⁺ at the end of linac - 420 MeV
- Number of e⁺ at the end of linac - $6 \cdot 10^8$ /pulse
 - Position conversion coefficient - 0.14 / GeV




Electron beam on phosphor screen after the tenth acceleration section



Energy spectrum and number of electrons on spectrometer after second acceleration section


Design of Damping ring

2d model of damping ring



Beam energy	510 MeV
Perimeter	2740 cm
RF Frequency	700 MHz
Damping time	18 msec
Horizontal emittance	$2.3 \cdot 10^{-6}$ rad·cm
Vertical emittance	$0.5 \cdot 10^{-6}$ rad·cm

3d model of damping ring and extraction line



Damping ring



Results of damping ring commissioning


Damping ring and positrons

Maximum current e+	70mA ($4 \cdot 10^{10}$)
Storage rate	$2.5 \cdot 10^8/c$
Injection rate	12.5 Hz
Energy of e+	420 MeV

Damping ring and electrons

Maximum current e-	160mA ($9 \cdot 10^{10}$)
Energy of e-	360 MeV
Storage rate	$1.8 \cdot 10^9/c$

30 mA in nine separatrices






Synchrotron radiation in damping ring



Synchrotron radiation in damping ring after detuning of sextupole lens

Injection angle measurement





Vertical DC Septum 3F3 3D3 Kicker 3D2 Phosphor screen LK4



$$\begin{pmatrix} x \\ x' \end{pmatrix} = \begin{pmatrix} R_{11} & R_{12} \\ R_{21} & R_{22} \end{pmatrix} \begin{pmatrix} x_0 \\ x'_0 \end{pmatrix} \Rightarrow \begin{cases} R_{11}(I_1)x_0 + R_{12}(I_1)x'_0 = x_1 \\ R_{11}(I_2)x_0 + R_{12}(I_2)x'_0 = x_2 \end{cases}$$

Change 3F3 current (two iterations) and calculate transport matrix(Septum to luminophore LK4)

Closed orbit correction





Closed orbit correction was done with respect to the quadrupole magnetic centers. To do so closed orbit responses to the gradient variations of the individual quadrupoles.

Lattice correction


Corrected beta functions in VEPP 5 Damping ring (after four iterations)

Uncorrected beta functions in VEPP 5 Damping ring



First betatron tunes were set to the project values. After that software “sixdsimulation” developed for VEPP-2000, was applied to correct linear lattice . It took 4 iterations to correct linear lattice by fitting the model to the experimental data composed of closed orbit responses to the all dipole correctors, dispersion, and betatron tunes. **After last iteration the fitted model didn't show significant variation from the ideal configuration.**

Project beta functions in VEPP 5 Damping ring



Summary

The VEPP-5 Injection Complex should be running with project parameters in the near future. Damping ring of the Complex stores the electron beams of 350 MeV today. Storage rate is $3 \cdot 10^9$ electrons per pulse and maximum store current is 160 mA, which exceeds design parameters. Beam transfer line to the BINP colliders is completely assembled and ready for beam accepting. The Damping ring optics were tuned to improve the Complex stability.

Thanks all

17.09

