


STATUS OF SUPERCONDUCTING ISAC-II AND ELINAC ACCELERATORS, AND SRF ACTIVITIES AT TRIUMF

V. Zvyagintsev, Z. Ang, K. Fong, T. Junginger, J. Keir, A. Kovesnikov, C. Laforge, D. Lang, R.E. Laxdal, Y. Ma, N. Muller, R. Nagimov, D.W. Storey, E. Thoeng, B. Waraich, Z. Yao, Q. Zheng

TRIUMF Canada's National Laboratory for Particle and Nuclear
Physics,
Vancouver, BC V6T 2A3, Canada





- **ISAC-II**
 - Layout
 - Cavities
 - Operation
- **eLinac**
 - Introduction
 - Cavity
 - Cryomodules
 - RF System
 - Cryogenics
 - Commissioning
- **SRF Developments and External Projects**
 - RF Deflector Cavity for ERL eLinac
 - VECC: ICM2, IOT Transmitter
 - FRIB: Variable Test Coupler development and production
 - RISP: QWR and HWR unjacketed tests, RI QWR jacketed tests. Balloon Spoke Cavity Development.
 - uSR
 - Vertical EP, T-map, Induction oven
- **Summary**




ISAC-II: Heavy Ion SC Linac

Design goal for the final energy equivalent to acceleration of $A/q=6$ beam with input energy 1.5 MeV/u to 6.5 MeV/u is achieved in 2010. ISAC-II supports a full physics program with both stable and radioactive beams being delivered. Stable beams of $^{16}\text{O}^{5+}$, $^{15}\text{N}^{4+}$, $^{20}\text{Ne}^{5+}$ and radioactive beams (and their stable pilot beams) of ^{26}Na , $^{26}\text{Al}^{6+}$, $^{26}\text{Mg}^{6+}$, $^6\text{He}^{1+}$, $^{12}\text{C}^{2+}$, $^{24}\text{Na}^{5+}$, $^{24}\text{Mg}^{5+}$, $^{11}\text{Li}^{2+}$, $^{22}\text{Ne}^{4+}$ including $^{74}\text{Br}^{14+}$




HELIUM COMPRESSOR



EL. 289.00'

ISAC-II QWR Cavities




Phase-I
Zanon (Italy)

Phase-II
PAVAC (Canada)

	flat	round	donut
f(MHz)	106.080	106.080	141.440
RsQ(Ohm)	20.1	19.1	26.0
β_0	0.064	0.075	0.112
TTFo	0.870	0.898	0.936
Ep/Ea	5.2	4.7	4.9
Bp/Ea(mT/(MV/m))	10.3	10.1	10.0
U/Ea2 (J/(MV/m) ²)	0.100	0.094	0.067

All cavities are specified for CW operation at 7W power dissipation with acceleration voltage 1.08MV corresponding to 30MV/m electric and 60mT magnetic peak field.





Cavity Production at PAVAC




BCP Etching at TRIUMF

BCP 1:1:2
 HF, HNO₃, H₃PO₄



Pre-weld etching ~20um

~10°C
 ~1um/min
 ~100um etch




Differential etching for
 frequency compensation
 Differential sensitivity for 1/2
 2 kHz/um for


We have MP only at start –
The strongest level is 3 order of magnitude less than operating level

Simulation by MultP-M code **Measured**


E_{av} kV/m	Cavity region	E_{av} kV/m
12.0 – 26.0	accelerating gap, donut – coax outer conductor	10 – 24
27.0 – 33.0	donut – coax outer conductor	28 – 33
35.0 – 54.0	coax line donut – end cap	42 – 50
58.0 – 193.0	donut – end cap	77 – 80



Simulation – Multp - MEPhI




Pulse conditioning



Most efficient - Driven CW

Cavity Performance 2013-2015

The linac cavities operate with an average gradient corresponding to a peak surface field of 32 MV/m for Phase-I and 28.5 MV/m – Phase-II without any discernible reduction in performance.




Less performance of Phase-II cavities:

- BCP 60um instead of 100um to mitigate risk of leak in welding
- Q-disease after 1h in 150-50K region while 10h for Phase –I cavities

Q-disease tests

Phase-II cavity test (typical)





Q-disease data from cavity#21 test

time@100K hours	Qo	Ea@7W MV/m
0	1.2E+09	6.72
1.19	6.76E+08	5.97
2.69	4.91E+08	5.43
5.8	2.83E+08	4.60
10.73	2.26E+08	4.34

Soaking of H for rf surface with subsequent performance degradation when cavity in the range 100-200K


Phase-I cavities



Significant degradation of Q even after 1h of soaking means big content of H in the material of Phase-II cavity (PAVAC)

For Phase-I (Zanon) critical soaking time was 10h

Cavities failures



Cavities failures don't stop operation. Since every cavity has an independent RF system, we can compensate the performance of the unavailable cavities by increasing the gradient in other cavities (at power dissipation $>7W$).



- Mechanical transmission failure
 - Bellows for - universal joints
 - Replace Phase-I to Phase-II couplers
- Cables failure due to RF glow discharge – 3/8" to 1/2" ANDREW – it's sufficient

Upgrades for ISAC-II

In a process

- Couplers
- Cables
- Phase-I tube to solid state RF amplifiers
- LLRF software upgrade




Future plans

- Deagassing of Phase-II cavities to mitigate Q-disease



- The ARIEL project will allow an increase in the radioactive ion beam (RIB) hours with the addition of a new electron linac driver of 50 MeV (0.5 MW), a new proton line from the 500MeV cyclotron and new production target stations. Accelerated electrons can be used to generate RIBs via the photo-fission process. The electrons are stopped in a converter to generate bremsstrahlung photons for fission in actinide target material. An electron beam intensity and energy of 10 mA and 50 MeV is required for a fission rate of 10^{13} fissions/sec.

eLinac SRF Specifications


- The ARIEL E-Linac SRF specification – dominated by RF beam loading
 - 10mA at 50MeV - 0.5 MW CW
 - CPI 75kW VWP 3032 coupler to deliver 50kW CW -> 10 couplers
 - 2x 50kW couplers per cavity -> 5 cavities
 - 10MeV energy gain per cavity
 - 10W at 2K -> $Q_0=1e10$
 - Reduce trapped HOMs
 - Large (90mm) single chimney sufficient for CW operation up to 50W
 - One cavity in ICM and 2 in ACM




E-Linac Accelerator Vault – Phase I






Cavity Design



	TRIUMF	DESY	TRIUMF/DESY
Frequency [MHz]	1300	1300	-
R_{sh}/Q [Ohm]	1000	1030	3% less
Geometric factor G [Ohm]	290	270	7% more
E_p/E_a	2.1	2.0	5% more
B_p/E_a [mT/(MV/m)]	4.4	4.2	5% more
Cell coupling [%]	2.0	1.9	




TRIUMF e-LINAC cavity is similar to 1.3GHz 9 cell DESY TESLA cavity. 2 symmetrically opposed 75kW CPI couplers




4 9-cell cavities fabricated at PAVAC



RF Power Couplers




The CPI VWP 3032 75kW CW Coupler



Handling
 Assembly in clean room
 Keep sealed with filtered
 N₂ gas

Baking
 • 100°C 7 days
 • 10°C/hour
 • N₂ filtered gas flow to 'warm' assembly

Injector Cryomodule



Houses




- one nine-cell 1.3GHz cavity
- Two 50kW power couplers

Features


- 4K/2K insert with JT valve on board
- Scissor tuner with warm motor
- LN2 thermal shield – 4K thermal intercepts via syphon
- Two layers of mu-metal
- WPM alignment system

Accelerator Cryomodule

- The ACM uses same basic design as ICM but with two 1.3GHz nine cell cavities each with two 50kW power couplers
- There is one 4K/2K insert identical to the ICM




Cryogenics



- 4K liquid at 1.3 Bar delivered in parallel to cryomodules from supply dewar
- 4K levels are regulated by LHe supply valve
- 2K levels are regulated by JT valve in each CM
- 2K pressure is regulated by 2K exhaust valve on each CM and trunk valve upstream of SA pumps



RF System Phase-I

- For Phase I we specify two 290 kW CW CPI VKL7967A klystrons with 65 kV, 10 A DC AMPEGON power supply (KPS)
- In the future, for Phase II one of these klystrons will drive next cryomodule
- We are looking for a cost effective 1.3GHz power source at ~150kW for the ICM



Cryomodule strategy

- Jacket and install ARIEL1 cavity in ICM
- Jacket and install ARIEL2 cavity in ACM together with a dummy cavity
- ACMuno
 - Dummy cavity has all interface features including helium jacket and DC heater
 - All helium piping and beamline interconnects will be final
 - ACMuno allows a full cryogenics engineering test plus two cavity beam acceleration to 25MeV
- Installed the cryomodules for a combined beam test in Sept. 2014 – cryogenic engineering and funding milestone




Dummy cavity

RF System Phase-I for Commissioning

RF System modification

- 'Dummy' waveguide branch of variable power divider has been terminated with RF load
- The variable power divider has been tuned for full transmission to the Cavity waveguide branch




ICM and ACMuno Assembly



ICM top assembly

Assembly of both
CMs proceeds
through summer of
2014



ACMuno – ready for cooldown Sept. 1

ACMuno assembly

High Power RF Installation


- Installed
 - Two CPI 290kW CW 1.3GHz klystrons
 - Two 600kW 65kV klystron power supplies from Ampegon
- Each klystron reaches specification at the factory and tested at TRIUMF
- Delivered power into a cold cavity – 25kW pulsed and 18kW CW



ICM Cold test results

Parameter	Estimated	Measured
4K static load (no syphon), W	2	3
4K static load with syphon, W	6	6.5
2K static load, W	5	5.5
77K static load	100	<130
2K production efficiency	82%	86%

- ✓ Cryogenic engineering matches design expectations
- ✓ Syphon loop performance characterized – works well – optimized in off-line cryostat tests



ACMuno First Cold test results


Parameter	Estimated	Measured
4K static load with syphon, W	7	6.4
2K static load, W	7	6.5
77K static load, W	100	TBD
2K production efficiency	82%	TBD

- ✓ Cryo-engineering looks good – static loads as expected – cooldown straightforward
- ✓ Initial RF tests – CW performance limited to 7MV/m and pulsed performance to 10MV/m by multipacting in couplers – no field emission to 10MV/m





A. Koveshnikov, et al., “Integration and Commissioning of the ARIEL e-Linac Cryogenic System at TRIUMF”, ICEC-ICMC2014

ICM, ICM2 and ACMuno Measured Q-values



ARIEL cavities installed in ICM, ICM2 and ACMuno meets specification $Q_o = 1e10$ at $E_a = 10$ MV/m

ICM and ACMuno gradient




A SC RF DEFLECTING CAVITY FOR THE ARIEL e-LINAC SEPARATOR

The future ERL extension of ARIEL e-Linac requires separating the bunches for either the ERL or RIB at the end of the linac at 650 MHz



RF Dipole Cavity
TE11-like mode

HOM
Dumper


$V_{rf} = 0.3 \text{ MV}$
 $P_{rf} = 0.2 \text{ W @ } 4 \text{ K}$



RF Coupler




Parameter	Value	Units
Frequency of the operating mode	650	MHz
Frequency of the first HOM	935	MHz
Cavity length	177	mm
Cavity diameter	210	mm
Nominal (Max) cavity voltage, V_{\perp}	0.3 (0.6)	MV
Shunt Impedance, R_{\perp}/Q	625	Ω
Geometry Factor, G	99	Ω
$R_{\perp}R_s$	6.2×10^4	Ω^2
Peak electric field, E_p	9.5 (19)	MV/m
Peak magnetic field, B_p	12 (24)	mT





Cavity fabrication
development for
TRIUMF
machine shop

CHARACTERIZATION OF SRF MATERIALS AT THE TRIUMF μ SR FACILITY




The method is used to characterize the sample superconducting state, particularly the transition from Meissner state to mixed state at different external magnetic fields.




Since 2010 the SRF group at TRIUMF has been using the μ SR technique to characterize materials and processing techniques typical for the SRF community using the TRIUMF surface muon beam

ICM2 Cryomodule for VECC




Production efficiency of 85% 2 K can be achieved

ICM2 meets specification of $Q_0=1e10$ at $E_a=10MV/m$



Einj	MeV	0.3
Eout	MeV	10.4
Ea caculate by beam energy	MV/m	11.93714
Ppm	dBm	3.76
Ea caculate by pick up signal		11.09019
pick up Q		4.97E+10



Stable operation at $E_a=12MV/m$ was achieved during beam test in Sep 2016




Copy of eLINAC Injector cryomodule ICM2 was made at TRIUMF for VECC project and successfully commissioned online in 2016

IOT Transmitter for VECC ICM


CPI IOT VKL 9130A
30kW CW 1.3GHz in Bruker
Transmitter was
Installed at TRIUMF in 2012



2 pairs of 4kW 1.3GHz
couplers for SLAC LCLSII
project were conditioned




TRIUMF Power Coupler
Test Station: 4 pairs of
50kW CPI VWP 3032 were
conditioned



Transmitter and
IOT shipped to
VECC (India) in
July 2016

SRF tests of RISP QWRs and HWRs at TRIUMF



QWR



BCP



HPR





HWR




Happy Team


RISP QWR 4K Q-Eacc Curves



BALLOON VARIANT OF SINGLE SPOKE RESONATOR FOR RISF



Ballon shape effectively suppresses the MP by moving barriers to lower field levels and narrowing them



Parameters	Value	Units
Frequency	325	MHz
β_z	0.3	1
$L_{eff} = \beta\lambda$	0.277	m
E_p / E_{acc}	3.8	1
B_p / E_{acc}	6.1	mT/(MV/m)
R/Q	233	Ω
G	93	Ω




Parameters	Beam Tube	Value	Units
Stress @ 1bar	Fixed	35.9	Mpa
	Free	36.1	
df/dp	Fixed	-9.5	Hz/mbar
	Free	1.6	
LFD	Fixed	-1.9	Hz/(MV/m) ²
	Free	-10.9	
Tuning	N/A	444	kHz/mm
	N/A	18.2	kN/mm
	N/A	129.8	MPa/mm

The cavity prototype fabrication is under preparation

Variable Test Couplers for FRIB


Variable test couplers were developed at TRIUMF for FRIB QWR and HWR SRF 2K-4K 'jacketed' tests

- 100 W CW 500 W in pulse mode at DF=10%
- 80-350 MHz
- 50mm stroke
- Cooling with LN2






1st two Couplers were successfully used for FRIB cavities tests
2nd batch of 4 couplers was shipped to FRIB in Nov 2016

SRF Technology Developments



Induction Oven:
Degassing, N-doping



Multimode test cavities

- ISAC-II is in 24/7 operation since 2006
- eLINAC phase-I of 1st stage consisting of 2 SC 9-cell cavities in ICM and ACMuno has been commissioned with 23 MeV beam test
 - 1st stage completion of ACM with 2nd cavity is expected in 2017
- eLINAC ICM2 has been fabricated and commissioned at TRIUMF
- TRIUMF is running SRF developments and uSR material study
- Work for External projects
- RISP
 - SRF tests of QWR and HWR prototypes – completed
 - Balloon Spoke cavity fabrication preparation is in a process
- FRIB
 - Couplers for QWR and HWR test – designed. 6 couplers delivered to MSU
- SLAC
 - 4 power couplers has been conditioned



TRIUMF: Alberta | British Columbia | Calgary |
 Carleton | Guelph | Manitoba | McGill | McMaster |
 Montréal | Northern British Columbia | Queen's |
 Regina | Saint Mary's | Simon Fraser | Toronto |
 Victoria | Winnipeg | York



Diversification de l'économie
de l'Ouest Canada



Ressources naturelles
Canada



Thanks!