

RuPAC 2016 – Tuesday 22th November 2016



Status of IFMIF-EVEDA RFQ

Enrico Fagotti on behalf of the INFN IFMIF-EVEDA collaboration





Outline

- Introduction
- **RFQ construction results**
- \circ CW RF tests in Italy
- $\circ~$ Installation and tuning in Japan



Outline



- **RFQ construction results**
- \circ CW RF tests in Italy
- $\,\circ\,\,$ Installation and tuning in Japan



IFMIF facility: two, high power CW drivers, each delivering a 125 mA deuteron beam at 40 MeV (5 MW power) hitting a liquid lithium target in order to yield neutrons (10¹⁷s⁻¹) via nuclear stripping reactions.



IFMIF EVEDA

Funded within the Broader Approach to Fusion: construction of a 9 MeV **125 mA cw deuteron accelerator** (LIPAc, Linear IFMIF Prototype Accelerator) to be built in Rokkasho, (Japan), based on a high power RFQ followed by a Half Wave Resonator superconducting linac





IFMIF-EVEDA Linear Ifmif Prototype Accelerator



Date 22/11/2016

Computer Simulation &

emote Experimentation Building

DEMOR&D Building



MEBT setup

Injector under commissioning





RFQ assembled and tuned

RF power system under completion

Diagnostics Plate set up

Date 22/11/2016

IFMIF

RuPAC 2016 E. Fagotti STATUS OF IFMIF-EVEDA RFQ



Outline

Introduction

• RFQ construction results

 \circ CW RF tests in Italy

 $\,\circ\,\,$ Installation and tuning in Japan



IFMIF-EVEDA RFQ





Input/output Energy	0.1 – 5	MeV
Duty cycle	Cw	
Deuteron beam current	125	mA
Operating Frequency	175	MHz
Length (5.7 λ)	9.78	m
Vg (min – max)	79 – 132	kV
R0 (min - max) ρ/ R0=.75	0.4135 - 0.7102	cm
Total Stored Energy	6.63	J
Cavity RF power dissipation	550	kW
Power density	86	kW/m
Power density (average-max)	3.5 – 60	kW/cm ²
Q0/Qsf=0.82	13200	
Shunt impedance (<v^2>)L/Pd</v^2>	201	kΩ –m
Frequency tuning	Water temp.	



RFQ components

18 modules

Each module approx. 550 mm and 600 kg. Modules assembled and aligned in 3 SMs (separately transported to Japan)

Local Control system PLC and EPICS, for cooling and vacuum systems, temperature and RF probes.

The cooling system Removes 800 kW and assures dynamic RF frequency tuning

Vacuum system 10 sets, based on cyogenic pumps (in cyan) guarantee 5*10⁻⁷ mbar with beam loss gas load

RF Power

8 RF systems and power couplers, 200 kW each. (RF system by Ciemat and final couplers by JAEA)



Modules construction



18 modules in three supemodules

- High energy SM built by Cinel, Padua (Italy),
- Intermediate energy built internally by INFN,
- Low energy attributed to RI Koln (Germany), concluded by INFN



Design choises

- High beam current requires high focusing parameter B, and ramped high voltage
- The **four vane resonator** was the only possible solution for such high intervane voltage
- The mechanical design is based on a brazed structure and metal sealing to guarantee the necessary high reliability.
- These two choices determined many aspects of the design (for example 316LN stainless steel for most of the interface points).
- 550 mm long modules to increase the number of possible manufacturer



Geometrical tolerances

The **electrode machining** can be very accurate and for this RFQ it was verified with continuous scanning CMM of each of the 72 electrodes (0.02 mm max error on each module modulation geometry was achieved).



CMM machine at

INFN Padova



- Max Deviat.: 10.5 µm The **beam axis accuracy** requires a precise alignment of the quadrupole center module after module (**better than**) **0.1 mm**).
- To keep the frequency within the tuning range and the **voltage** law along the 5.7 λ structure requires guaranteed electrode displacements below 0.05-0.1 mm (depending on modulation amplitude).

IFMIF



- Large pieces with final tolerances of 0.05 mm in beam region
- Vacuum oven in INFN LNL, metrology and precision machining at INFN Padova
- Single step brazing procedure was developed and used for most of the modules.







Modules Quality Assurance

Additional opening for frequency correction





All the measured values are such that $|DR_0| < 0.1 \text{ mm}$, with an average value on all the modules of 0.046 mm for the RF measured data and of 0.05 mm for the mechanical measurement data.

IFMIF



Outline

- Introduction
- **RFQ construction results**
- OW RF tests in Italy
- $\circ~$ Installation and tuning in Japan



High power tests at Legnaro



- A 500 kW test stand able to test 4 RFQ modules, to test at full power density the structure (200 kW RF power)
- The test was necessary to validate the design during the module construction
- Max field (1.8 Ekp and max power density 86 kW/m) have been demonstrated







INFN couplers (200 kW cw)

- Developed by INFN for the power test
- They will be used at Rokkasho for the first RFQ operation.





Baking







High Power Test

Date 22/11/2016

RuPAC 2016 E. Fagotti STATUS OF IFMIF-EVEDA RFQ

Nominal performances demonstrated



INFN

Field configuration (pick up reading) at different RF level



Cavity power (calorimetric measurements) vs. cavity voltage. The yellow circled dot corresponds to the nominal voltage level.Q0=12500, i.e. 173 kW vs. 132 kV





On 27 February '15 RFQ remained 5 hours at nominal field level. It corresponds to the yellow circle in fig above.

IFMIF

Resonant frequency control

- Resonant Frequency Control (RFC) achieved: cavity frequency driven by coolant temperature (16 kHz/⁰C external channels)
- RFC was kept active for more than 1.5 hours at 100 kW CW, with frequency oscillation lower than 2 kHz.



IFMIF



Outline

- Introduction
- **RFQ construction results**
- CW RF tests in Italy



RFQ shipment to Rokkasho (Japan)





Data extrapolated from the shock recorder mounted on SM2

- The three SMs were completely assembled at LNL, filled with nitrogen
- Rubber spacers and wood supports were used for vibration dumping
- Shock recorders, Shocklog 298, were screwed on the top of each SMs.



IFMIF



- RFQ arrived in Rokkasho divided into three SuperModules (SMs).
- Each SM was successfully vacuum tested after arrival.



• SMs were installed in provisional position, centred on beam axis but moved 3 m away from the LEBT. Final alignment transversal precision was less that 0.05 mm.





- SM1-SM2 vacuum test was successful
- A 0.03 mm maximum misalignment between SMs (+0.1 mm beam dynamics requirements) was obtained
- SM2-SM3 connection revealed a problem related to bad helicoflex sealing



Al component assembly and tuning

 108 aluminum tuners and 2 dummy end plates were assembled on the RFQ for tuning purpose.





Date 22/11/2016

IFMIF

INFN

RuPAC 2016 E. Fagotti STATUS OF IFMIF-EVEDA RFQ

Measured spectrum after field tuning



IFMIF

From dummy to final



INFN







IFMIF

INFN Quad. & Dip. Modes with Al and Cu tuners





Date 22/11/2016

IFMIF



Tuning results

- The final measured frequency was equal to 174.989 MHz, equivalent to 175.014 MHz, if one takes into account the rescaling to nominal 20°C temperature and the effects of vacuum and beam loading (-1°C degree water temperature correction necessary).
- Quality factor was measured $Q_0 = 13200 \pm 200$ that is 82% of SUPERFISH value (low tuner losses).
- The excellent shunt impedance of the design was achieved:
 - Rsh=201 k Ω *m





- After helicoflex substitution between SM2 and SM3, and after solving minor vacuum leakages RFQ was repositioned in the final position at the end of the LEBT.
- Final alignment of the entire RFQ guaranteed that each module axis is aligned with the previous and the following modules within ±0.05 mm. Moreover first and last modules are within ±0.03 mm respect to accelerator nominal axis.
- Finally RFQ was vacuum tested and after few hours pumping reached a 9x10⁻¹¹ mbar-l/s leak rate.





Date 22/11/2016

IFMIF



Next steps

- Before the end of 2016 control system, vacuum system and power couplers will be installed and RFQ will be baked-out.
- Installation will be completed with cooling system before the end of February 2017.
- Phase B will start on May 2017.



Thank you