# **NICA Ion Collider at JINR**



1111

Evgeny Syresin on behalf of team Veksler and Baldin Laboratory for High Energy Physics Joint Institute for Nuclear Research

-----

# NICA: <u>Nuclotron based Ion Collider fAcility</u>



Heavy ions: ESIS+HILac (Au<sup>31+</sup> 3.2 MeV/n)+ Booster+Nuclotron

Polarized p<sup>↑</sup> and d<sup>↑</sup> beams, protons and light ions (z/A>0.3): SPI (LIS or DP)+ Linac LU-20 (5MeV/n)+ Nuclotron Construction of new light ion linac (LILAC at 7 MeV/n)+medium energy proton acceleration sections (13 MeV)+ SC sections (20 MeV)

# NICA accelerators Collider

The Collider ring 503.04 m long has a racetrack shape and is based on double-aperture (top-to-bottom) superconducting magnets at maximum dipole field 1.8 T;

The major parameters of the NICA Collider are the following: - magnetic rigidity =  $45 \text{ T} \cdot \text{m}$ ;

-ion kinetic energy range from 1 GeV/u to 4.5 GeV/u for  $Au^{79+}$ ;

-energy of polarized deuterons is 6 GeV/u, protons – 12 GeV,

- vacuum in a beam chamber: 10<sup>-11</sup> Torr;
- zero beam crossing angle at IP;
- 9 m space for detector allocations at IP's;

Average luminosity  $10^{27}$  cm<sup>-2</sup>·s<sup>-1</sup> for gold ion collisions at  $Vs_{NN} = 9$  GeV.

The luminosity in the polarized mode is up to  $10^{32}$  cm<sup>-2</sup>·s<sup>-1</sup>.

Commissioning – 2022 First technological run- end of 2022





# NICA collider parameters

Ring circumference, m	503,04		
Number of bunches	22		
Rms bunch length, m		0.6	
Beta-function in the IP, m	0.6		
Betatron tunes, Qx/Qy	9.44/9.44		
Ring acceptance	40 π·mm·mrad		
Long. acceptance, $\Delta p/p$	±0.010		
Gamma-transition, $\gamma_{tr}$	7.088		
Ion energy, GeV/u	1.0	3.0	4.5
Ion number per bunch	<b>3.2</b> ⋅10 <sup>8</sup>	<b>2.9·10</b> <sup>9</sup>	<b>3.1·10</b> <sup>9</sup>
Rms dp/p, 10 <sup>-3</sup>	0.7	1.4	1.9
Rms beam emittance, h/v,	1.3/1.3	1.3/1.1	1.3/1.0
(unnormalized), $\pi$ ·mm·mrad			
Luminosity, cm <sup>-2</sup> s <sup>-1</sup>	0.8e25	0.8e27	1e27
IBS growthe time, sec	160	460	2000



### NICA Stage II-a (basic configuration):

- 1. Injector chain: KRION => Booster => BTL BN => Nuclotron
- 2. BTL Nuclotron => Collider
- 3. Collider equipped with
- RF-1 (barrier voltage system) for ion storage
- RF-2 in a reduced version: 2 cavities per ring instead 4 (50 kV RF amplitude instead 100 kV)
- 1 channel of S-cooling per ring (cooling of longitudinal deg. of freedom)

Result: 22 bunches of the length  $\sigma \sim$  2 m per collider ring that 5e25 cm<sup>-2</sup>·s<sup>-1</sup>.



## NICA Stage II-b (full configuration):

### Collider

- + RF-2 systems in the project version
- + RF-3 systems in the project version
- + S-cooling (transverse)
- + E-cooling

Result: 22 bunches of the length  $\sigma$  ~ 0.6 m per collider ring that 1e27 cm  $^{-2} \cdot s^{-1}$ .

# Nuclotron-Collider beam transport channel

Parameters of pulsed magnet elements

**WEA01** 

RUPAC 21

A. Tuzikov

Magnetic element	Number	Effective length, m	Max. magnetic field (gradient), T (T/m)	MA AN-
Long dipole	21	2	1.5	
Short dipole	6	1.2	1.5	
Quadrupole Q10	22	0.353	31	
Quadrupole Q15	6	0.519	31	ASIA
Steerer	33	0.466	0.114	







Magnets delivery in JINR in February 2021

Nuclotron-Collider transfer line is under delivery and construction by Sigma Phi The JINR-SigmaPhi contract schedule:

November 2021 – delivery of first part of power supplies, beam diagnostics, support stands; start of the channel mounting.

January 2022 – delivery of vacuum equipment.

July 2022 – delivery of second part of power supplies, beam profile monitors, command and control system.

September 2022 – start of commissioning of the channel equipment.

**December 2022 – commissioning of the channel with a beam.** 

# Collider beam injection and dump systems



QF, QD – quadrupole; MC – multipole; KM – kicker; SM - septum

## <u>Septa</u>

- Technical design development is in progress. The main crucial items are low-inductive feedthroughs for current pulses of order 50 kA.
- Power supply based on semiconducting switches is being developed.
- Construction until October 2022
- Installation November 2022



Length, m	2.5
Max magnetic field, T	0.42
Gap, mm	35
Septum thickness, mm	3
Pulse shape	semisinusoidal
Pulse duration, μs	~ 10

### Septum cryostat module



# Collider beam injection and dump systems

## <u>Kickers</u>

	injection	dump
Length, m	4	4
Max magnetic field, T	0.05	0.11 •
Pulse duration, ns:		
rise	200	130 •
plateau	200	1700
fall	200	>10000
After-kick amplitude, plateau level	≤1.5%	-
After-kick duration, ns	≤160	-

- Technical design development is in progress.
- **Construction until October** 2022
- **Installation November 2022**

## Simplified model of kicker chamber



### Injection kicker pulse (simulation)



# Joining of the magnets





### **Collider magnets assembly and testing**

Cryogenic-tests per year:2017201820192020202160587672150

Collider dipoles: **100** % tested Collider quadrupoles: **35%** tested

2016

20



### WEB01

	total	prod. %
Dipole magnet coil	80+1	100
Quadrupole magnet coil	46+24	100
Corrector magnet coil	124+4	75
Final focus quadrupole coil	12	20
Vertical bending magnet coil	8	20
Dipole magnet heat screen	80+1	100
Quadrupole magnet heat screen	46+12	100
interconnections' heat screen	181	50
Cryogenic by-pass heat screens	2	20
Heat screens (ref. mag.& feed b-x)	2	80
Temperature sensor @ cold	900	100

### **SC-magnets constructed at JINR**

	Dipole magnets	45
Synchrotron booster	Quadrupole magnets	56
	Dipole correction magnets	24
	Multipole correction magnets	8
Synchrotron Nuclotron	Commissioned since March 1993	180
	Dipole magnets	85
	Quadrupole magnets (arch)	50 (4)
Collider	Quadrupole magnets (doublet)	30 (0)
	Dipole magnets BV	10
	Quadrupole magnets LFF	16
	Multipole correction magnets	136 (75)
	Total:	640

- magnets were produced - magnets are produced - designed magnets

## Line for assembling and cryogenic testing of SC-magnets D. Nikiforov

### Main production areas:

- Incoming inspection zone
- SC cable production hall
- > SC coils production hall
- Area for assembling the magnets
- Area for the magnetic measurements under the room temperature
- Leakage test area
- Area for mounting the SC-magnets inside cryostats
- > Cryogenic tests bench





# 460 magnets for NICA projects

**WEB01** 

## Cryogenic tests of Collider dipole magnets and quadrupole lenses

RUPAC 21, A. Shemchuk



Measurements for the NICA collider magnets: dipoles



Parameter	2.3 kA	6.89 kA	10.44 kA
Leff	26	55	92
BL	27	55	75
α	25	24	22
<b>b</b> <sub>2</sub>	172	172	172
b3	160	58	172
<b>b</b> 5	172	172	34
<b>b</b> 7	172	172	172
<b>a</b> <sub>2</sub>	171	172	172
a3	172	172	172

# Number of dipole magnets with parameters less than in specification



At prilaminary measurement interpretation the angle between median plane and magnet axis is by 5 time larger than project value. It became to an increase COD from 2-5 mm

to 5-10 mm





Measurements for the NICA collider magnets:



quadrupoles



# **Collider power supply system**



RUPAC 21, V. Karpinsky WEC01

**Power supplies:** 

 Main power supplies
 2 completes with 3 power supplies

2. Additional power supplies (10V x 300A) -88.

3. Energy evacuation keys -12

4. High power
commutation
equipment
5. Transformers 6/0,4
kV - 2.



## **Collider power supply sustem**



#### Three main power supplies





Constructed by LM Invertor (Moscow) Delivery to JINR

#### Energy evacuation keys



#### Prototype was constructed and tested

### Additional power supplies (10B x 300A)





2 prototypes from 3 were constructed and tested

### Storage of ion beams in RF bucket





E=3 GeV/n,  $\sigma_p$ =1E-4,  $\sigma_l$ =10 m 3 D model of RF1 station

Ion Beam dynamics in NICA collider, S.Kostromin **TUB01** Maximal voltage – 5 kV Two rectangular barriers each with phase length- $\pi/12$ Stack phase zone–  $\pi$ . Kicker fronts (2 x 200 ns)  $0.54\pi$ Kicker plato -200 ns= $0.27 \pi$ **Injection zone** = kicker fronts+ kicker plato=0.81  $\pi$ =203.7m



Dependence of momentum spread and ion intensity on number of injection cycles.



### **3D model of RF2 station**



**Bunching beam by RF2** 

Number of RF2 cavities per ring -4, RF2 voltage -25 kV

RF2 bunching at 3 GeV/n

 $U0_{Rf2}$ =1.5 kV,  $U_{Rf}$ =100 kV at RF2 frequency variation 10 kHz/s, cooling time 30 s, for initial  $\sigma_p$ =3.7E-4, at t=17,5 s and additional cooling during 40s



### Dependence of momentum spread at adiabatic Rf2 bunching and cooling after 17,5 s.







 $tt_{2k4} = 9.9$   $U02(t_{2k4}) = 1 \times 10^5$   $U03(t_{2k4}) = 8 \times 10^5$ 

 $tt_{k5} = 209.7$   $U02(t_{k5}) = 1 \times 10^5$   $U03(t_{k4}) = 8 \times 10^5$ 





 $E= 3 GeV/n, U_{Rf2}=100 \text{ kV}, \quad U0_{Rf3}=21.8 \text{ kV}, \\ U_{Rf3}=800 \text{ kV} \text{ at RF3 frequency variation} \\ 25.7 \text{ kHz/s} \quad \text{cooling time 100 s, for initial} \\ \text{rms bunch length } \sigma=1.7 \text{ m after R2 bunching} \\ \end{array}$ 





**RF3 Bunching** Number of RF3 cavities per ring -8, RF3 voltage-125 kV



**3D model of RF3 station** 

<d/dp>



<dz0>,m t,sec Dependence of ratio of number of ions captured in parasitic separatrix to number of ions captured in central separatrix on rms bunch length.





### **RF1 cavity in BINP**

### Two RF1 cavities delivered in JINR in 2019

### Barrier bucket RF1 and harmonic RF2-RF3 cavities



**RF1 cavity in JINR** 



RF3 cavity and amplifier in BINP (16 RF3 cavities for extension configuration, Installation in end of 2022)





RF2 cavity and amplifier in BINP (4 RF2 cavities for base configuration 2022 4RF2 cavities for extension configuration, installation in 2022)

## Electron Cooling System of NICA Collider, Ions <sup>197</sup> Au<sup>79+</sup>



HV Electron Cooler for NICA Collider Design and construction at BINP Installation at NICA in 2022

Parameter	Value
Electron energy, MeV Energy instability, $\Delta E/E$	0.2 – 2.5 ≤ 1·10 <sup>-4</sup>
Electron beam current, A	0.1 - 1.0
Cooling section length, m	6.0
Solenoid magnetic field, T Field inhomogeneity, ∆B/B	0.05 − 0.2 ≤ 1·10 <sup>-5</sup>











Dependence of cooling time and IBS on ion energy Start of mounting – January of 2022 First beam tests – Spring 2023 22



# **NICA Stochastic Cooling**

- Beam accumulation
- Longitudinal emittance reduction during the bunching
- Luminosity preservation (IBS counteraction)

Longitudinal cooling method	Filter	
Passband, GHz	0,7 - 3,2	
Beam distance from pickup to kicker, m	183,5-191,5	
Phase advance from pickup to kicker, deg	1340-13	60
Ion Energy <sup>197</sup> Au <sup>79+</sup> , GeV/u	3,0	
Slip-factor from pickup to kicker	0.0294	
<b>Revolution slip-factor</b>	0.0362	
Pickup/kicker coupling impedance, $\Omega$	200/80	0
Gain, dB	75 – 79	
Peak power at kicker, W	3×200	
Pickup/noise temperature, K	300/40	







Start of mounting – Spring of 2022 First beam tests – Autumn 2022

# **SCS Parameters**

## RUPAC 21, I. Gorelyshev TUB06

### **Collider diagnostics** Total <u>number of diagnostic devices in one ring (2 arcs + 2 straigh</u>t sections):

Pick-up near F lenses (X)	24
Pick-up near D lenses (Z)	24
Pick-up in straight sections (X/Z)	20
Parametric current transformer (Bergoz)	1
Fast current transformer (Bergoz)	2
Betatron tune measurements (Q-meter)	1
Ionization profile monitor	3
Strip pick-up monitor	2
Schottky-pick-up	1
Beam loss monitors (for both rings)	68







Start of mounting – Winter of 2022 First beam tests – Autumn 2022

## **Collider building**



Improvement of accelerator and detector equipment parameters during project development after 2013 required increasing power consumption, power of water cooling system, sizes of Collider building and essential increasing of quantity of engineering equipment. As a result the collider power consumption was increased from 4 to 9 MW, water cooling power from 2.9 up 5.6 MW, building square from 19900 to 30800  $m^2$ .

Installation of arc magnets is planed to start in October-November 2021

Thank you for your attention!