



FRIB Project: Moving to Production Phase

Kenji Saito
On behalf of FRIB, MSU

MICHIGAN STATE
UNIVERSITY



U.S. DEPARTMENT OF
ENERGY

Office of
Science

Outline

- FRIB Project
- Challenges in the FRIB SRF
- Status of the SRF hardware production, not included cryomodule production
- Plans for ramping to full production
- For future large proton/ion SRF Linac projects
- Summary

S. Miller FRAA 06

Acknowledgments

I would like to thank to many FRIB people and other collaborators for preparing this talk:

H. Ao, B. Barker, B. Bird, N. Bultman, E. Burkhardt, F. Casagrande, J. Casteel, S. Chandrasekaran, C. Compton, J. Crisp, K. Davidson, K. Elliott, A. Facco**, F. Feyzi, A. Fox, A. Ganshyn, P. Gibson, T. Glasmacher, Z. He, K. Hosoyama***, W. Hartung, L. Hodges, K. Holland, L. Hodges, M. Ikegami, S. Jones, G. Kiupel, B. Laxdal****, S. Linda, Z. Li, I. Malloch, M. Masuzawa***, D. Maxwell, E. Metzgar, D. Miller, S. Miller, D. Morris, D. Norton, J. Ozelis*, J. Popielarski, L. Popielarski, A. Rauch, M. Reaume, R. Rose, T. Russo, S. Shanab, M. Shuptar, S. Stark, M. Thrush, G. Velianoff, D. Victory, K. Witgen, J. Wei, G. Wu*, M. Xu, T. Xu, Y. Yamazaki, Q. Zhao, Z. Zheng, Y. Zhang*

** FNAL, **INFN-LNL Italy, *** KEK Japan, ****TRIUMF Canada.*



FRIB Project Overview

- Goal of the FRIB: Create cutting-edge nuclear physics by the various isotope produced by an 200 MeV/u ion driver linac.
- Build a 200 MeV/u@ 400 kW SRF high intensity heavy ion linac in MSU campus.
- DOE/MSU jointed project under Cooperative Agreement, project cost shared by both, total cost \$730M.
- CF construction started in March 2014
- Accelerator system construction started October 2014
- Completion of Infrastructure in SRF highbay in November 2015
- Early beam commissioning to be 2017 – 2020 starting with the Front End
- Final completion in 2022

FRIB tunnel




2014 Dec.

FRIB accelerator building site



2015 June




2015 August

SRF highbay




2015 March

FRIB SRF Linac Goal and Features



- Delivers FRIB accelerator as part of a DOE-SC national user facility with high reliability & availability
- Three folded SRF linac (~500 m)
- Accelerate ion species up to ^{238}U with energies $> 200 \text{ MeV/u}$
- Provide beam power up to 400 kW satisfy beam-on-target requirements
- Future energy upgradability $> 400 \text{ MeV/u}$ by filling vacant slots





Features:

- Heavy ion beam **intensity frontier machine**, e.g. $5 \times 10^{13} \text{ } ^{238}\text{U/s}$, 250 times higher than ATLAS
- **All SRF** from low beta to medium beta section and **2K operation**
- Large nuclear physics user (~1300 users) facility

FRIB SRF Linac

All SRF cavities from beta 0.041 to 0.53, four type cryomodules, one cavity - one RF source (semiconductor amp.), high gradient CW operation at 2K

| | | | | |
|---|--------|--------|--------|--------|
| Cavity Type | QWR | QWR | HWR | HWR |
| β_0 | 0.041 | 0.085 | 0.285 | 0.53 |
| f [MHz] | 80.5 | 80.5 | 322 | 322 |
| V_a [MV] | 0.810 | 1.80 | 2.09 | 3.70 |
| E_{acc} [MV/m] | 5.29 | 5.68 | 7.89 | 7.51 |
| E_p/E_{acc} | 5.82 | 5.89 | 4.22 | 3.53 |
| B_p/E_{acc} [mT/(MV/m)] | 10.3 | 12.1 | 7.55 | 8.41 |
| R/Q [Ω] | 402 | 455 | 224 | 230 |
| G [Ω] | 15.3 | 22.3 | 77.9 | 107 |
| Aperture [m] | 0.036 | 0.036 | 0.040 | 0.040 |
| $L_{eff} \equiv \beta\lambda$ [m] | 0.153 | 0.317 | 0.265 | 0.493 |
| Lorenz detuning [Hz/(MV/m) ²] | < 4 | < 4 | < 4 | < 4 |
| Specific $Q_0@VT$ | 1.4E+9 | 2.0E+9 | 5.5e+9 | 9.2E+9 |
| Q_L | 6.3E+6 | 1.9E+6 | 5.6E+6 | 9.7E+6 |




FRIB Cryomodule Designs and Features

Example for 0.085QWR and 0.53HWR, 0.041/0.085 both QWRs and 0.29/0.53 both HWRs are similar

S. Miller FRAA 06

0.085QWR
Cryomodule




0.53HWR
Cryomodule


Includes
8 QWRs and
3 solenoids

Local magnetic shield

Includes
8 QWRs and
1 solenoids



Design of CM0.041 and CM0.29 are in WFO Jlab




FRIB Cryomodule Features

- **Local magnetic shield:** cost reduction for magnetic shielding and reliable shielding
- **Bottom-up supported design:** optimized for mass-production and efficient precision-assembly
- **2K operation:** enhanced cavity performance and less micro-phonics by stable pressure control

Main Hardware of FRIB SRF and Scope

| Cavity Type | Frequency & Cavity type | Quantity of Cavities | Quantity of Modules | Quantity of Solenoids |
|----------------------|-------------------------|-----------------------|----------------------|-----------------------|
| $\beta=0.041$ | 80.5 MHz, QWR | 12 + 4 spare | 3 + 1 spare | 6 + 2 spare |
| $\beta=0.085$ | 80.5 MHz, QWR | 88 + 8 spare | 11 + 1 (Marching CM) | 33 + 3 spare |
| $\beta=0.29$ | 322MHz, HWR | 72 | 12 | 12 |
| $\beta=0.53$ | 322MHz, HWR | 144 | 18 +1 (Matching CM) | 18 |
| Marching Cryomodules | | 12 + 4 spare | 0.085 CM 3 +1 spare | n/a |
| | | 3 + 1 spare | 0.53 CM 1 | |
| Total | | 332 + 16 spare | 48 + 3 spare | 69 + 5 spare |



(1) Cavities




(2) QWR/HWR power couplers



(3) QWR/HWR Tuners



(4) QWR/HWR Magnetic shields



(5) SC 25/50cm solenoid packages

SRF Technical Challenges in FRIB SRF and Resolution

▪ First Large Scale SRF LINAC $\beta = 0.041$ to 0.53

S. Miller FRAA06

- Four different types of cryomodule:
0.041QWR, 0.085QWR, 0.29HWR, and 0.53HWR
- How to manage so many different components.
- Other labs help FRIB: Jlab for 0.041/0.29 MC design, ANL for coupler and tuner designs

▪ Solenoid in the cryomodule

S. Chandrasekaran et al. TUPB102

- FRIB is challenging to build compact SRF Linac with high beam quality
- Detail investigation cavity/solenoid fringe field interaction
- Designed solenoid package well optimized fringe field

▪ Tighter Alignment Tolerance

S. Miller FRAA06

- Smaller cavity bore diameter: 36 mm (0.041QWR), 40 mm (other type of cavity)
- Longitudinally tolerance 1 mm and transversely 0.5 mm
- Innovated bottom-up supported design cryomodule

▪ Narrow Band width 30 – 40 Hz, Cavity Frequency Control in the Production

C. Compton WEBA03

- Stack up tuning, innovated virtual EBW welding
- Developed deferential etching (QWR)
- Puck height control

▪ High Gradient Cavity Operation at 2K

L. Popielarski et al. TUPB022

- Eacc = 5 – 8 MV/m, Ep = 27 - 34 MV/m, Bp = 55 - 69 mT, Cavity design with lower Bp/Eacc ratio
- Developed high QA control procedure




FRIB Requirements for SRF Hardware and Validation Status

| Hardware | Hardware Detail | Requirement | Validation | Comment |
|------------------|---|---|--|-------------------------------------|
| Cavity | 0.041QWR (80.5MHz) | $E_{acc} = 5.29 \text{ MV/m @ } Q_o = 1.4 \times 10^9$ | Done | 2 K operation |
| | 0.085QWR (80.5 MHz) | $E_{acc} = 5.68 \text{ MV/m @ } Q_o = 2.0 \times 10^9$ | Done | 2 K operation |
| | 0.29HWR (322 MHz) | $E_{acc} = 7.89 \text{ MV/m @ } Q_o = 5.5 \times 10^9$ | Done | 2 K operation |
| | 0.53HWR (322 MHz) | $E_{acc} = 7.51 \text{ MV/m @ } Q_o = 9.2 \times 10^9$ | Done | 2 K operation |
| Coupler | QWR (80.5 MHz) | 4 kW @CW | Done (Dewar integration test) | Working in ReA |
| | HWR (322 MHz) | 8 kW @CW | Done (Bench mark test) | KEK/SNS type |
| Tuner | QWR | Tuning range 30 kHz Tuning resolution 0.8 Hz | Done (ReA, ReA3 CM, ReA6-1) | Tuner plate + puck at bottom flange |
| | HWR, ANL type Pneumatic tuner | Tuning range 120 kHz Tuning sensitivity 1.5 Hz | Done (Dewar integration test) Continued design update | ANL type pneumatic tuner |
| Magnetic Shield | Local shielding | $\mu > 10000 @ 25 \text{ K}$ Remnant field at high H_{RF} area of the cavity $< 15 \text{ mG}$ | Done (ReA, ReA3, ReA6-1) | Local magnetic shield at 25K |
| Solenoid Package | Main Solenoid (25cm/50cm) with bucking coil | 8 T (NbTi) | Done (ReA, ReA3, ReA6-1) | 4.5 K Operation |
| | Steering dipole | 0.03 Tm (25 cm), 0.06 Tm (50cm) | Done (ReA, ReA3, ReA6-1) | 4.5 K Operation |

- Cavity preparation: BCP, Hydrogen degassed at 600 °C for 10 hr, and no 120 °C baking so far
- Solenoid: 8 T main solenoid with bucking coil to cancel the fringe field, X-Y beam steering dipoles

FRIB Cavity Design Validation

Processed by BCP, enough margin against FRIB requirements





- Pushed away high Q-slope by improved RF cavity design with lower Bp/Eacc.
- Less field emission by FRIB develop high pressing QA control

Validation Test of 90° Bend QWR FCP


Confirmed stable operation for long run

Validation

- 80.5 MHz QWR couplers are adjustable, not variable
Adjustment is a possibility only for a microphonics mitigation Pumping slots were added on the outer conductor to evacuate in insulation vacuum
- QWR coupler with 90° bend was successfully tested on a ReA3 QWR at MSU
- Succeeded long run operation in VT
 - Total load: 23W
 - Static load 12W
 - Cavity dynamic load 12W
 - Heat load < 1W,
 - Stable operation for 24hr continuous
 - No heat up



Heat load measurement of FCP





ReA6-1 CM Integration Validation

- Validated the alignment tolerance by Bottom up supported design
 - Confirmed alignment within 0.5 mm in transverse
 - Twice cool down/warm up and confirmed reproducibility
- Validated stable operation of the integration system: Cavities/FPCs/Tuners/Solenoid package
 - Demonstrated stable operation 24 hr
 - Confidence for band width control
- Validated local magnetic shield benefits (A4K)
 - Meets FRIB remnant field < 15 mT
 - Needless of degaussing process
 - Very small field around cavity short area under 8T solenoid package operation, expected no Q-drop at cavity quench

S. Miller FRAA 06

S. Chandrasekaran et al. TUPB102



| Process | Fluxgates (mG) | | | | Hall probes (mG) at beam port facing solenoid (low sensitivity at small fields) | | | | | | | |
|-----------------------------------|----------------|-------------|------------------|-------------|--|-------------|--------------|-------------|--------------|--------------|-------------|--------------|
| | Top of cavity | | Bottom of cavity | | In | | | | Out | | | |
| | In | Out | In | Out | ③ | | | | | | | |
| | ① | | ② | | X | Y | Z | Mag. | X | Y | Z | Mag. |
| After cool down (shield T=24.5 K) | 2.5 | 8.1 | 3.0 | 209.3 | -850 | -370 | 240 | 958 | 0 | 1000 | 1000 | 1414 |
| During solenoid operation | -161.6 ±1.2 | -361.2 ±2.1 | 1659.5 ±20.7 | 872.0 ±20.2 | -6253 ±979 | -3000 ±2438 | -11350 ±1382 | 13596 ±2246 | -55000 ±2800 | -29900 ±2524 | -91100 ±860 | 110849 ±1459 |
| After solenoid operation | 30.7 ±0.6 | 27.6 ±1.2 | 15.9 ±1.2 | 290.9 ±0.3 | 770 ±800 | 4317 ±833 | 3133 ±289 | 5434 ±835 | 5400 ±2800 | -1967 ±1701 | 7733 ±1097 | 9906 ±1999 |
| After full degauss | 4.2 ±0.7 | 8.7 ±1.1 | 0.5 ±1.7 | 207.6 ±1.6 | 103 ±907 | 4133 ±1828 | 2667 ±2060 | 5058 ±2519 | 1933 ±2483 | -4000 ±3378 | -2767 ±3402 | 6719 ±1588 |
| After CM warm-up | 0 ±0.1 | -5 ±0.1 | 0.6 ±0.1 | 205 ±0.1 | 16708 ±83 | 13845 ±67 | 7278 ±51 | 22887 | -22061 ±90 | -1836 ±62 | -5217 ±74 | 22744 |



Facility for Rare Isotope Beams
U.S. Department of Energy Office of Science
Michigan State University


Production Strategy, Validation, and Production Status

- **Development phase: Produce 2 articles with MSU, Technology transfer to vendor for build to print, and vendor certification**
- **Preproduction phase: Produce 10 articles by the vendor own, judge the mass-production capability of the vendor, develop issues in mass production and resolve them.**
- **Production phase: Mass-production**

| Component | Status, V(Validation), VC (Vendor Certification) | | | | Delivery and Needed Date |
|----------------------------------|--|---|---|---|--|
| Nb materials | NbTi flange (done), Nb sheets (done), Seamless pipes (done) | | | | FRIB production Nb material has been done |
| Cavity with Helium jacket | 0.041QWR Vendor A | | | Production (19) done | All 0.041QWRs has been delivered |
| | 0.085QWR Vendor B/C | Development (2) Done V, VC | Preproduction (10) Delivered 10, done all | Production (102) Started mass-production | Needs 8 by 1 st Sep. 2015 (FRIB first 0.085CM) |
| | 0.285HWR Vendor D | Development (2) Done V, VC | Preproduction (10) Delivered 3 | Production (72) | Needs by Aug. 2017 |
| | 0.53HWR Vendor D | Development (2) Done V, VC | Preproduction(10) Delivered 10 | Preproduction (138) | Need by Apr. 2016 |
| Fundamental Power Coupler | QWR parts Vendors | QWR FPC (2) Done V, VC | Preproduction (8) Delivered 8 Aug. 2015 | QWR FPC(104) | Needs 8 by 1 st Sep. 2015 (FRIB first 0.085CM) |
| | HWR Vendor E | Development (2) Done V, VC | HWR FPC (2) to be delivered Oct. 2015 | HWR (217) | Need by Apr. 2016 (FRIB 1 st CM) |
| Tuner | QWR Vendor F | Development (8) Done V, ReA3 | Production(112) Delivered (8), tuning plates | | Needs by Sep. 2015 |
| | HWR Tuner | Development (2) Done by integration test but still finalizing design | Production (217) | | Need by Jun. 2016 (FRIB 1 st 0.53CM Prototype)) |
| Solenoid | 25cm Vendor G | Development (1) Done V | | Production (6) | Need by March 2017 |
| | 50cm Vendor G/MSU | Development (1) Done V | Preproduction (4) in MSU, completed for preproduction CM Other in vendor G | Production (62) | Need 3 by Sep. 2015 for FRIB first 0.085 CM |

Delivery Examples of SRF Components


So far, ~ 50 cavities delivered



Infrastructure for FRIB Production

SRF Highbay, constructed by MSU fund, ready for cavity test in Sept. 2015

- FRIB is finalizing infrastructure for the production in SRF Highbay fund by MSU
- Functionalities of the SRF Highbay
 - Acceptance inspection, working already
 - Dimensional inspection by CAM
 - Cold shock test, Leak check
 - Cavity processing and assembly, working already
 - Large cleanroom
 - Cavity etching (BCP) system
 - High pressure rinsing system
 - Ultrapure water system
 - Hydrogen degassing furnace
 - Cavity vertical test system, Mid-November 2015
 - 2 Dewars and 4 cold inserts
 - Cold mass assembly, started Sep. 2015 (FRIB 0.085 first CM)
 - 900W liquid helium system, liquid helium in 3000L Dewar in Sep. 2015
 - Cryomodule two bunker test systems, under preparation





Facility for Rare Isotope Beams
U.S. Department of Energy Office of Science
Michigan State University

Ramping to Full Production

- So far ~ 50 cavities have been delivered. 7 cavities /month, now speeding up and complete cavity delivery by 1, 2017
- FRIB needs 8 -9 cavities/month in average
- SRF full production Mid- November 2015 expected 11 -12 cavities/month with 20% downtime and 20%rework Meets FRIB requirement !!
- From ReA3, ReA6-1 cryomodule assembly experiences, a 27 working days needs one bunker test.
- FRIB cryomodule production rate is 1.5 CMs per month, which can be met by two bunker systems
- Cryomodule installation to be started from 2/2018

FRIB master schedule related to SRF construction



For Future Large Scale Proton/Heavy Ion SRF Linac

■ Solenoid Package in the Cryomodule




- FRIB is challenging to build the compact SRF linac with high beam quality
- Need quick strong focusing heavy ion beam at low energy
- Increase real state gradient to make short FRIB SRF linac

■ FRIB confirmed this scheme is good choice for QWRs with local magnetic shield scheme

- The fringe field around cavity short area is small enough to not occur the Q-drop at cavity quench, for instance ReA6-1 result 162 mG at the full operation of 8 T solenoid and dipoles
- Local shield allows needless of degaussing procedure, which benefits on Operationability of cryomodule

■ Need careful solenoid package design

- The magnetic shield penetration field starts at ~ 250 G (defined as 1 G increased)
- Solenoid package has to be designed as fringe field strength is less than ~ 250 G on the magnetic shield, need well optimized bucking coil location.



Summary

- FRIB construction started on March 2014 and to be completed in 2022, early commissioning is scheduled in 2017 – 2020 starting from the Front End.
- FRIB is the first large scale SRF linac from very low beta to medium beta.
- FRIB SRF linac is the intensity frontier heavy ion machine.
- FRIB is challenging many innovative concepts to build a compact SRF linac with high quality beam: solenoid in the cryomodule, bottom up supported cryomodule assembly, and high gradient cavity. These concepts have been successfully validated.
- All hardware components have been successfully validated and has been ordered vendors. FRIB project is moving well into production phase.
- Infrastructures in SRF highbay is going into full operation since Mid-November 2015, enhances the production rate double, and ready for full production.

ReA Project in MSU

MSU own project, beam operation of SRF linac

- MSU has strong nuclear physics activities in the world (NSCL, ReA)
- ReA is the reaccelerate rare isotope system up to 3 MeV (upgrade 12 MeV future near future), and first SRF LINAC at MSU
- Excellent test bench for FRIB QWRs for beta: 0.041 QWRs and 0.085 QWR cryomodules
- ReA joins finally FRIB (Reaccelerates rare isotopes produced by FRIB)

