

FRIB Cavity Production Status

Chris Compton

17th International Conference on RF Superconductivity Whistler, September 13 – 18, 2015

This material is based upon work supported by the U.S. Department of Energy Office of Science under Cooperative Agreement DE-SC0000661, the State of Michigan and Michigan State University. Michigan State University designs and establishes FRIB as a DOE Office of Science National User Facility in support of the mission of the Office of Nuclear Physics.

Outline

- Overview
 - FRIB SRF Linac
 - FRIB SRF cavity evolution
- Cavity production status and performance
- Cavity inspection and acceptance
- Cavity production oversight
 - Frequency control
 » Virtual welding development
 - Aperture alignment control
 - Low-cost flange optimization
 - Cavity vacuum reliability
 » European knife-edge design
 - Thread fabrication
- Summary





FRIB Driver Linac





FRIB Project – SRF Acceleration

- 200 MeV beam energy, 400 kW beam power
- 332 cavities housed in 48 cryomodules
- Four cavity designs two cavity classes, two frequencies, and four betas (β₀)
- Started technical construction (CD-3) Aug. 2014
- Managing to early completion in FY2021



80.5 MHz $\beta_0 = 0.041$

FRIE



80.5 MHz β₀ = 0.085



322 MHz $\beta_0 = 0.29$



322 MHz β₀ = 0.53



 $\label{eq:basic} \begin{array}{ll} \beta_{\scriptscriptstyle 0} = 0.041 & \beta_{\scriptscriptstyle 0} = 0.085 \\ \mbox{Quarter-Wave Resonators} \\ 80.5 \mbox{ MHz} \end{array}$

322 MHz

Half-Wave Resonators

FRIB SRF Cavity Evolution

- FRIB production cavity designs evolved from internal prototype efforts at MSU
 - ReA3 project successfully in operation
 - 3 cryomodules 16 quarter-wave cavities
- Implemented design changes to improve performance and reduce costs
 - Quarter-wave outer conductor extension, relocate coupling ports, bottom flange redesign
 - Half-wave rinse port balancing, straight section, removed RF pick-up port (use rinse port)





Cavity Production Status for FRIB Driver Linac

- Worked with industrial vendors to optimize workflow for FRIB production
- Multiple vendors with large scale production experience

β _o	Development	Preproduction	Production	TOTAL
0.041	2 <mark>(2)</mark>		17 <mark>(17)</mark>	19 <mark>(19)</mark>
0.085	2 (2)	10 <mark>(10)</mark>	103	115 <mark>(12)</mark>
0.29	2 (2)	10 <mark>(3)</mark>	68	80 <mark>(5)</mark>
0.53	2 (2)	10 <mark>(8)</mark>	150	162 <mark>(10)</mark>

* Numbers in red indicate cavities received to date



Production $\beta_0 = 0.041$ cavities being sequenced for cavity processing



FRIB SRF Cavities Exceeding Performance Specification



SRF Cavity Acceptance

- All received cavities are inspected in reference to the Acceptance Criteria List (ACL)
- ACL inspection points defined
 - Vendor report review
 - Dimensional inspection
 - Visual inspection RF surfaces, sealing interfaces, and weld beads
 - Frequency measurement
 - Leak check
- All nonconformances are reported and documented in FRIB tracking system
- FRIB works directly with vendor to identify root cause and implement corrective actions



Dimensional inspection using Coordinate Measuring Machine (CMM)



Internal boroscope inspection



FRIB Cavity Frequency Control

- Quarter-wave cavities (80.5 MHz +/- 20 kHz)
 - Traditional stack and trim procedure
 - Experience through ReA3 and ReA6 projects
 - Developments from other projects
 » Differential etching TRIUMF
 » Tuning plate puck adjustment TRIUMF
- Half-wave cavities (322 MHz +/- 50 kHz)
 - Initial design using beam-cup adjustment for frequency tuning
 - Improved design stack-up and trimming of outer and inner conductors
 - Now implementing reference fixtures for stack-up
 - Frequency tuning developments

 Mechanical deformation unjacketed cavity
 Virtual welding with and without helium vessel
 Differential etching with helium vessel



HWR frequency tuning using beam cup positioning



HWR frequency tuning using OC and IC stack and trimming



Half-wave Cavity Reference Stack-up Fixtures

 FRIB developed calibrated reference fixtures to increase reproducibility in the stack-up and trim steps of half-wave cavity fabrication



Niobium short plate measurement

- Niobium short plates are machined to print
- Frequency of short plates measured against a calibrated reference copper cavity.



Niobium outer and inner conductor measurement

- Niobium outer and inner conductors left long
- Frequency is determined by stacked-up measurement using calibrated reference copper short plates
- The outer and inner conductors are trimmed and re-stacked until goal frequency is met.



Virtual Weld Frequency Adjustment in Halfwave Cavities

- FRIB developed frequency adjustment for half-wave cavities using virtual welding
- Virtual welding is non-structural welds strategically placed to cause material shrinkage resulting in a controlled frequency shift
- Virtual welding used for frequency adjustment in cavities with and without helium vessel



Electron-beam power calibrations for virtual welding of halfwave cavities ($\beta_0 = 0.29$ and 0.53) prior to helium vessel integration



Virtual

TIG

welding

Cavity Frequency Control

QWR β_0 = 0.085 Frequency Tracking





Aperture Alignment Issues Mitigated

- Work with vendors to optimize aperture alignment
 - Design tolerance +/- 0.381mm (+/- 0.015 inch)
- Work with FRIB Physics Department to set aperture tolerances
- Several processes developed to improve alignment
 - Improved tooling during electron-beam welding
 - Post fabrication mechanical deformation quarter-wave cavities
 - Post fabrication machining half-wave cavities

Corrective actions and oversight have improved alignment



Aperture alignment tracking



Facility for Rare Isotope Beams

U.S. Department of Energy Office of Science Michigan State University

Vacuum Sealing Reliability Addressed [1]

- All incoming cavities are cold shocked and vacuum leak checked; both cavity and helium vacuum spaces
 - Leak check pass = be free of leaks as measured by a calibrated helium massspectrometer leak detector having a sensitivity of <1x10⁻¹⁰ STD cc He/sec
- Several warm and cold leaks reported on early prototype and development cavities
 - Worked with vendors to improve fabrication tolerance, fabrication methods, surface quality control, and post fabrication repairs





Damage to knife-edge profile

Electrical Discharge Machining (EDM) Conflat flange fabrication



Developed method of repairing Conflat flanges on completed cavities

Vacuum Sealing Reliability Addressed [2]

- Knife-edge degrading observed after multiple assemblies
 - Knife-edge appears to be degrading/rolling over
- Implemented European knife-edge design to reduce point loading
 - Knife-edge profile integrity maintained after design change



tracking



Low-cost Flange Optimization

- Low-cost flanged designed to maintain high thermal conductivity properties and reduce costs
- Original design fabricated from niobium-titanium material
 - Poor thermal conductivity
- Redesigned cavity flange fabricated using high RRR niobium material
 - Improved thermal conductivity
 - Large cost increase required thick niobium plate
- Developed low-cost flange option
 - Thin disk of niobium welded into a titanium flange to reduce material cost
 - Addition of cooling channels allows direct cryogenic cooling to niobium disk





Thread Fabrication Lessons Learned

- To optimize cavity spacing in the cryomodule, blind tapped holes implemented into cavity design
 - Tapped holes fabricated into niobium-titanium flanges
- Formed vs machined threads
 - Formed tapped holes not passing go/no-go gauge » Titanium materials have a lot of spring back
 - Machined threads vary in surface roughness
 » High fiction when engaging fasteners
- Weld distortion from helium vessel fabrication
 - Require post weld clean-up of tapped holes
- Implemented use of electro-polished fasteners to reduce friction
 - Fasteners prepared to Cleanroom standards clean with no lubricants



Thread mill insert



Summary

- SRF cavity prototyping successful in establishing path to FRIB production designs
- SRF cavity production is quickly ramping up with awarded contacts and development of multiple cavity vendors
- A project focus on vendor management is required to ensure high quality product and maintain schedule
- FRIB has implemented a thorough acceptance inspection philosophy
- Early nonconformances mitigated by strong working relationships with vendors to identify root causes and implement corrective actions
- Cavity production on track to meet FRIB project goals

