



Achievement of Stable Pulsed Operation at **36 MV/m** in **STF-2 Cryomodule at KEK**

Kirk, E. Kako, T. Shishido, K. Umemori, T. Kubo, T. Konomi, G. Park, T. Saeki, T. Dohmae, M. Egi,
T. Matsumoto, T. Miura, T. Takenaka, H. Nakai, Y. Kojima, K. Hara, T. Honma, K. Nakanishi, H. Shimizu

THYA02






- **STF-2 Accelerator & History**
- **Cavity Performance / Degradation**
- **X-rays Measurement**
- **Vector-sum operation with eight cavities @31 MV/m**
- **Heat Load Measurement**
- **Lorentz Detuning Measurement**
- **Summary & Future Plan**



- **STF-2 Accelerator & History**
- **Cavity Performance / Degradation**
- **X-rays Measurement**
- **Vector-sum operation with eight cavities @31 MV/m**
- **Heat Load Measurement**
- **Lorentz Detuning Measurement**
- **Summary & Future Plan**



STF-2 Accelerator Layout



Cold box

CM1 + CM2a
(Twelve cavities)


To be constructed

Cold box

Capture CM
(Two cavities)

RF Gun

Chicane





Brief History for STF-2 Cryomodule

superconducting rf test facility



Date	Content
2010	Fabrication of cavities / power couplers
2011 ~ 2013	V.T. for 12 cavities / RF conditioning for 12 couplers
Jun/2013	Cleaning up STF tunnel
Jul/2013 ~ Apr/2014	Cavity string assembly (three times)
Oct/2013 ~ Jun/2014	Module assembly (CM1/CM2a)
Jul/2014	Complete certification for High pressure Gas Code
Oct/2014 ~ Dec/2014	1 st cool-down / low power test
Apr/2015 ~ Jul/2015	5MW Klystron / Single waveguide system completed
Jul/2015 ~ Sep/2015	Coupler conditioning at room temperature
Oct/2015 ~ Dec/2015	2 nd cool-down / high power test (cavity performance check)
Jan/2016 ~ Jul/2016	Multi-beam Klystron & Waveguide system completed
Jul/2016 ~ Sep/2016	Coupler conditioning at room temperature
Sep/2016 ~ Nov/2016	3 rd cool-down / LFD, Q_0 measurement, 8 Cavities Operation & LLRF study
F.Y. 2018	4 th cool-down test (?)
F.Y. 2018 ~	Beamline construction / Beam operation starts (?)




- **STF-2 Accelerator & History**
- **Cavity Performance / Degradation**
- **X-rays Measurement**
- **Vector-sum operation with eight cavities @31 MV/m**
- **Heat Load Measurement**
- **Lorentz Detuning Measurement**
- **Summary & Future Plan**

Cavity performance/Degradation

superconducting rf test facility

Summary of Achievable Gradient in V.T. & C.T. at STF-2/Capture CMs



2nd CT

Heavy F.E. & Enormous heat load



3rd CT

Unknown reason



4th CT





- **STF-2 Accelerator & History**
- **Cavity Performance / Degradation**
- **X-rays Measurement**
- **Vector-sum operation with eight cavities @31 MV/m**
- **Heat Load Measurement**
- **Lorentz Detuning Measurement**
- **Summary & Future Plan**




X-rays measurement



Onset Gradient


Onset Gradient in V.T. & C.T. at STF-2



- ✓ CAV5, 6, 7, and 9 not tested in 3rd cooldown
- ✓ CAV1 had no x-rays in last V.T.
- ✓ **A little bit higher gradient in 3rd test as resulting from RF conditioning**

X-rays @31.5MV/m

@31.5MV/m in V.T. & C.T. at STF-2



F.E. was not related to the degradation between 2nd and 3rd cool-down test!

- ✓ CAV5, 6, 7, and 9 not reached 31.5 MV/m in 2nd cooldown
- ✓ CAV10 and 12 not reached 31.5 MV/m in 3rd cooldown
- ✓ **Almost same level between 2nd and 3rd test**







- **STF-2 Accelerator & History**
- **Cavity Performance / Degradation**
- **X-rays Measurement**
- **Vector-sum operation with eight cavities @31 MV/m**
- **Heat Load Measurement**
- **Lorentz Detuning Measurement**
- **Summary & Future Plan**

Vector-sum Operation with 8 Cavities

superconducting rf test facility

Each pulse for 8 cavities

Trend graph of Ave. E_{acc} and Δf during vector-sum operation



They **almost** satisfied the ILC specification!



$30.9 \text{ MV/m} \pm 0.02 \text{ MV/m}$

$46 \text{ Hz} \pm 1.8 \text{ Hz}$



- **STF-2 Accelerator & History**
- **Cavity Performance / Degradation**
- **X-rays Measurement**
- **Vector-sum operation with eight cavities @31 MV/m**
- **Heat Load Measurement**
- **Lorentz Detuning Measurement**
- **Summary & Future Plan**

We can estimate the heat load from the helium mass flow rate.



The heating around the power coupler remained in the next day.
This effect might generate the **larger** systematic error.



◆ Reproducibility of Static Heat Load

◆ **0.36 [W]** on average for 28 times measurements

◆ Distribution of Helium Mass Flow

◆ **3.9%** on maximum for every heat load measurement

◆ Stability in Accelerating Gradient for Flat-top of Pulse

◆ **0.05%** (very stable)

◆ Stability in RF Duty Factor

◆ **0.85%** (stable)

◆ Latent Heat of Vaporization

◆ Negligible small

◆ Helium Mass Flow Meter


◆ **±0.3%** according to spec. sheet

◆ Calibrated by heater in the STF-2 cryomodule

Comparison of $Q_0 - E_{acc}$ and X-rays


superconducting rf test facility

Comparison of $Q_0 - E_{acc}$ for Cavity#1



Cavity #1


Comparison of $Q_0 - E_{acc}$ for Cavity#2



Cavity #2

The both results are contradictory!


Comparison of $Q_0 - E_{acc}$ for Cavity#8



Cavity #8

Heater is used as calibration
 Q_0 is estimated from helium mass flow

Comparison of $Q_0 - E_{acc}$ for Cavity#12



Cavity #12

Heavy field emission

Lower Q_0 may depend on cooldown rate (@LCWS2016) → Will be tried in next cool-down test




- **STF-2 Accelerator & History**
- **Cavity Performance / Degradation**
- **X-rays Measurement**
- **Vector-sum operation with eight cavities @31 MV/m**
- **Heat Load Measurement**
- **Lorentz Detuning Measurement**
- **Summary & Future Plan**




Lorentz Detuning Measurement

superconducting rf test facility


Thicker titanium end plate




Comparison of detuning frequency (full-pulse) @STF-2



The STF cavity has more stiffness than TESLA cavity.



Comparison of Elongation of Every Cavity @S1-Global/Quantum Beam/STF-2





- **STF-2 Accelerator & History**
- **Cavity Performance / Degradation**
- **X-rays Measurement**
- **Vector-sum operation with eight cavities @31 MV/m**
- **Heat Load Measurement**
- **Lorentz Detuning Measurement**
- **Summary & Future Plan**

- STF-2 Cryomodule was constructed, installed and tested since 2013
- 8 cavities achieved above 31.5 MV/m in the single cavity operation
- 3 cavities had “more” degradation in 3rd cool-down test
- X-rays was never changed in two cryomodule tests
- Vector-sum operation with 8 cavities at 30.9 MV/m successfully done
- Lower Q_0 for every cavity



□ **Change of cool-down method (like FNAL)**

□ **Beam commissioning**

Final goal for STF-2





Thank you very much for your attention!

