



SRF Status of the SHINE Project at Shanghai

Hou Hongtao for the SHINE Project Team

SRF2019 Conference, Dresden, Germany



Outline

- Introduction of SHINE
- SHINE progress
- SRF R&D and prototypes Progress
- Infrastructures progress
- Summary



Shanghai Hard X-ray FEL Facility (SHINE)


- SHINE is a high rep-rate XFEL facility, based on an 8 GeV CW SCRF linac, under development in Shanghai;
- This facility will be built in a 3.1 km long tunnel underground at Zhang-Jiang High Tech Park, across the SSRF campus;
- This XFEL facility has 3 undulator lines and 10 experimental stations in phase-I, it can provide the XFEL radiation in the photon energy range of 0.4 -25 keV.
- This XFEL project was approved by the central government in 2017, and its groundbreaking was made in April, 2018, aiming at starting user experiments in 2025.

This facility will be developed by Shanghai-Tech Univ., SARI and SIOM of Chinese Academy of Sciences.


Shanghai Hard X-ray FEL Facility (SHINE)



e-beam: 8 GeV
Photon energy: 0.4-25 keV
Pulse duration : 1-100fs
Repetition : 1MHz
Total length : 3.1km
ca 30m underground



SHINE: A high-rep rate XFEL based on SCRF




➤ XFEL Facility +100 PW Laser Facility

	Nominal	Range
Beam energy/GeV	8.0	4-8.6
Bunch charge/pC	100	10-300
Max rep-rate/MHz	1	up to 1
Beam power/MW	0.8	0 - 2.4
Photon energy/keV	0.4-25	0.4-25
Pulse length/fs	20-50	5-200
Peak brightness	5×10^{32}	1×10^{31} - 1×10^{33}
Average brightness	5×10^{25}	1×10^{23} - 1×10^{26}
Total facility length/km	3.1	3.1
Tunnel diameter/m	5.9	5.9
2K Cryogenic power/kW	12	12
RF Power/MW	2.28	3.6

FEL Line	Nominal	Objective
FEL-I		
Photon energy/keV	3-15	3-15
Photon number per pulse @12.4keV	$>10^{10}$	$>10^{11}$
Max pulse repetition rate/MHz	0.66	1
FEL-II		
Photon energy/keV	0.4-3	0.4-3
Photon number per pulse @1.24keV	$>10^{12}$	$>10^{13}$
Max pulse repetition rate/MHz	0.66	1
FEL-III		
Photon energy/keV	10-25	10-25
Photon number per pulse @15keV	$>10^9$	$>10^{10}$
Max pulse repetition rate/MHz	0.66	1

Layout of the SHINE accelerator



Injector Parameters	Value	Linac	No. of CM's	Avail. Cavities	Powered. Cavities*	Gradient (MV/m)	Eout (MeV)
Beam energy (MeV)	100	L0	1	8	7	16.3	100
Bunch charge (pC)	100	L1	2	16	15	14.8	326
Normalized emittance (95%, $\mu\text{m}\cdot\text{rad}$)	0.4	HL	2	16	15	12.5	269
Slice energy spread (10^{-4})*	0.1/0.5	L2	18	144	135	15.5	2148
Bunch length, rms (mm)	1	L3	30	240	225	15.5	5762
Peak current (A)	12	L4	24	192	180	15.5	8653

➤ 750kV VHF gun +Single cavity CM

+ 1.3GHz SCRF cryomodules: 75 + 3.9GHz SCRF cryomodules: 2



SHINE Progress

- Groundbreaking was made on April 27, 2018. Construction of shafts is in good progress;
- Accelerator engineering design, technical infrastructure development, key technology R&D, component prototyping and long-lead equipment procurements are underway ;
- Beamline design optimization are being carried out, R&D of key optics component, and Pixel array detector started;
- Technical and engineering design of high energy OPCPA, R&D of key laser technologies for SEL are in progress;
- ...

SHAFT #5 in April, 2019



Sha

SHINE





Outline

- Introduction of SHINE
- SHINE progress
- **SRF R&D and prototypes Progress**
- Infrastructures progress
- Summary

SRF R&D and prototypes progress



- Accelerator engineering design, technical infrastructure development, key technology R&D, component prototyping and long-lead equipment procurements are underway
- Three years on R&D and prototypes: 2018-2021
- Wide collaboration in China on SRF prototypes
- **Hope and Welcome worldwide collaboration with Labs / Institutes / Companies on SRF technologies**

SHINE SRF system





- 8.0 GeV 1MHz repetition rate, CW SC Linac based on TESLA / E-XFEL 1.3 GHz technology
- Totally, 600 1.3GHz SC cavities, 16 3.9GHz SC cavities

Parameter	Length	Cell shape accuracy	Straightness	f @ RT, Vacuum	f @ 2K, Vacuum	Field flatness (bare cavity)	Field flatness (dressed cavity)
SHINE	mm	mm	mm	MHz	MHz	/	/
	1283.4±3.0	±0.2	<0.4	1298.2±0.1	1300.2±0.1	>95%	>90%

- High-Q0 cavities required, $Q_0=(2.0\sim 3.0) \times 10^9$ @ $E_{acc}=14 \sim 18$ MV/m; **Baseline: EP+N2 doped fine grain cavities or traditional EP-ed large grain cavities**
- Worldwide Industrial mass production for 1) dressed cavities (ready for VT); 2) cryostats ;3) couplers ;4) HOM absorbers
- Prototype collaboration in China, R&D on cavity fabrication, surface treatment and vertical test
- Construction of a surface treatment platform for cavities and a Workshop for VT, clean assembly, cryomodule integration and horizontal test, is underway
- Digital LLRF with solid state power source: one source one cavity

Cavity prototype

three groups for cavity fabrication and high Q0 studies (EP & N-doping)



Totally, 48 prototype dressed cavities

Phase-I

In parallel

4 LG cavities with DESY (OTIC Nb material)

4 FG cavities from companies outside China

Phase-II Meet specification and fix doping recipe




Key technology and techniques



- **Frequency & length control:** half cell, dumb-bell, End-groups, whole 9-cell pre-tuning, HOM tuning; helium vessel welding;
- **Surface treatment**
 - **Electro-polishing (EP):** adopting EP to obtain fine inner surface, EP instrument and operating parameters; acid temperature and voltage control;
 - **Nitrogen doping:** high temperature annealing and N₂ doping, find optimal N₂ pressure, lasting time and following slight EP thickness; (LCLS-II: N₂-A6-EP5)
 - **High Pressure Rinsing (HPR):** important to cure field emission
- **Clean room assembly** techniques: crucial for high performance cavity
- **Fast cooldown and flux expulsion:** to obtain low earth magnetic field for high Q₀ performance;

Nb sheets for prototypes

OTIC NX



Tokyo Denkai



SHINE

- Define grain size: ASTM 6, no smaller than ASTM 7.
- Hope to find the relation between grain size and the doping cavity performance.
- NX material: RRR > 300, in average, grain size = ASTM 4.5 ~ 5.5, HV10 = 56.9, elongation = 58.8 ~ 62.8,
- TD material: RRR > 300, in average grain size = ASTM 5 ~ 6. HV = 38.7 ~ 51.6, elongation ~ 60
- Single cells have been welded, surfaced treated and some of them vertical tested.
- Quality control of sheets — EXFEL 007 as reference
- Re-test of Nb material by SHINE are in process

Spec.

- RRR value: ≥ 300
- Tensile strength $-R_m > 140$ MPa
- Yield strength $R_p 0.2 = (50 \sim 100)$ MPa
- Elongation AL 30 $\geq 30\%$
- Hardness ,HV ≤ 60

Substitutional elements	Content (ppm)	Interstitial elements	Content (weight ppm)
杂质成分	含量(ppm)	杂质成分	含量(质量 ppm)
Ta / 钽	≤ 500	H / 氢	≤ 2
W / 钨	≤ 70	N / 氮	≤ 10
Ti / 钛	≤ 50	O / 氧	≤ 10
Fe / 铁	≤ 30	C / 碳	≤ 10
Mo / 钼	≤ 50		
Ni / 镍	≤ 30		

Recent results of cavity prototypes



- Group-1: 4 FG cavities fabricated, BCP treated, 2 was vertical test; one dressed cavity vertical tested
- Group-2: 2 LG cavities fabricated, BCP treated, vertical test

See also H.T.HOU et al., MOP049
F. S. He et al., FRCAA5

Table 2: Performance of fabricated FG and LG cavities ◊

Cavity number ◊	FG#1 ◊	FG#2 ◊	LG#1 ◊	LG#2 ◊
Cavity length @ RT & 1.0 bar (mm) ◊	1284.55 ◊	1283.59 ◊	Not measured ◊	Not measured ◊
Field flatness (%) ◊	95.0 ◊	98.0 ◊	98.4 ◊	97.4 ◊
Freq. @ RT & 1.0 bar (MHz) ◊	1298.22 ◊	1298.17 ◊	1298.11 ◊	1298.07 ◊
Freq. @ 2K vacuum (MHz) ◊	1300.25 ◊	1300.20 ◊	1300.38 ◊	1300.44 ◊
Q_0 @ 16 MV/m @ 2.0K ◊	1.50×10^{10} ◊	1.15×10^{10} ◊	1.75×10^{10} ◊	1.89×10^{10} ◊
Q_0 @ 16 MV/m @ 1.8K ◊	/ ◊	1.31×10^{10} ◊	3.00×10^{10} ◊	3.20×10^{10} ◊
Maximum gradient (MV/m) ◊	20.0 ◊	19.6 ◊	25.3 ◊	26.0 ◊
Gradient limited by ◊	N-connector broken ◊	quench ◊	LHe ◊	quench ◊

- FG cavities met the specification on length, frequency, flatness, and $Q_0 \sim E_{acc}$ met the requirement of BCPed cavity .
- As LG cavities, length is not measured yet, frequency is a little higher, $Q_0 \sim E_{acc}$ met the requirement of BCPed cavity.

Latest news: #3 and #4 cavities (BCPed, NX sheets) have been vertical tested, max gradient reaches 25 MV/m and 26 MV/m, respectively. $Q_0 \sim 1.8 \times 10^{10}$ @ $E_{acc} = 16$ MV/m. See more detail in [FRCAA5](#).





1st FG cavity, Dec. 2018



LG cavity, Feb. 2019

Recent results of cavity prototypes



- Gradient limited, difficult to tell the defects, lack of diagnostic instrument such as T mapping and X-ray mapping.
- #1 and #2 FG cavities' gradient is limited to 20 MV/m, #2 has X-ray radiation, FE arose ~ 10 MV/m
- LG cavities' gradient is limited to ~ 26 MV/m, both have X-ray radiation, FE arose ~ 14 MV/m
- Clean (surface and assembly) is always a big challenge!

Recent results of cavity prototypes




- Camera was used to inspect the inner surface on #3 FG cavity
- No obvious defect at the equator welding area.
- However, some suspected spots at the welding area. Are these defects?
- #3 FG cavity: Vertical testing is completed on June 30. Maximum gradient reaches 25 MV/m, $Q_0 \sim 1.8 \times 10^{10}$ @ $E_{acc} = 16$ MV/m. It seems these kinds of spots didn't bring much limitation to gradient.
- **How to qualify the welding joints is another challenge.**

See also H.T.HOU et al., MOP049
F. S. He et al., FRCAA5




EP and N-doping studies with IHEP and PKU



FG single cell cavity @ IHEP

- N-doping studies: S3, Q-inverse, $Q_0 \sim 4e10$ @ 16 MV/m
- EP studies on FG material from NX and TD: S6_TD, S7_NX, gradient has been improved to ~ 38 MV/m
- See more detail in F. S. He, FRCAA5.

EP and N-doping studies with IHEP and PKU




LG single cell cavity @ PKU

- LG material from NingXia
- Base line: BCP 250 μm + 800°C 3hr
- N-doping: N-doping 2 min/annealing 6 min + EP (different thickness)
- $Q_0 = 3.8E10 @ 20\text{MV/m}$
- More detail in MOP039, Shu CHEN

N-doping studies at SARI



- L02 Heavy N-doping 20190110
- ◆ L03 Light N-doping 20181227
- L02 Radiation
- ◇ L03 Radiation
- L01 Heavy N-doping 20181222
- ▲ L04 No N2 20181222
- L01 Radiation
- △ L04 Radiation




1.3 GHz large-grain single-cell cavities, fabricated from Ningxia Nb, vertical tested at PKU

- L01, L02 N-doping : 800°C 3h + N20/A30@~3.3Pa+ EP15
- L03, N-doping: N-doping: 800°C 3h + N2/A6@~3.3Pa+ EP5
- L04, Baseline: BCP250 + 800°C 3h + BCP20


See also J.F. Chen et al., MOP029

N-doping studies at SARI




1.3 GHz fine-grain single-cell cavities, with NX Nb, tested at PKU

- S01 N-doping: 975°C 3h + N20/A30@~3.3Pa + EP20
- S04 BCP baseline: quenched early, with spots/pits at the equator region after BCP.



Cryostat Prototype



Insulation vacuum chamber

Cryogenic pipes

Thermal shield



1. Fabrication completed
2. Arrive at SARI
3. Acceptance test
4. To be assembled with cavities, couplers, tuners, cold BPM and SC magnet.


Pipe	Description	Pipe ID [mm]	Design Pressure [bar]	Operating Temperature [K]
A	2K-Helium supply	55	20	2.3
B	2K-Helium gas return	300	4	2
C	Low temperature intercept supply	55	20	5
D	Low temperature intercept return	51	20	5
E	High temperature shield supply	55	20	40
F	High temperature shield return	53	20	40
G	Two phase pipe	98	4	2
	Chimney	98	4	2
H	Cool down/warm up Line	39	4	5

Coldmass integration training

- Integration has been completed twice.
- Functions of tools are verified.








Solid-state power source and LLRF



Performance:

- 5.2 kW output power with 0dBm input signal
- Bandwidth (1dB): 1.0 MHz
- Modular design: plug in type; keep operation when one module broken;

Frequency	1.3GHz
Delay of small signal	<300ns
1 dB compression	5.2kW @0dBm
Bandwidth(1dB)	1MHz
Phase noise	80dBc/Hz(10Hz offset @1.3GHz)
Amplitude stability	0.1% @ 1 second
Phase stability	0.1° @ 1 second
Spur	<-70dBc
Noise	<10 dB
Harmonic	<-30 dBc
Input voltage	3×380 V AC ± 5%
Efficiency	>40% (at 5.2kW)
RF output	WR650
Reliability	Modular design, keep operation if one module broken



A & P stability in 20 mins:
 < +/- 2% and < +/-0.15 °



A & P stability in 1 second: < 1% and < 0.1 °



Solid-state power source and LLRF


Digital LLRF

- FPGA based technology
- Feedback algorithm
- Prototype developed, tested
- Microphonics suppression is under design




Specification


	CM number	Cavities	Amp. Stability % (rms)	Phase Stability deg (rms)
L0	1	8	0.01	0.015
L1	2	16	0.01	0.01
HL	2	16	0.01	0.01
L2	12	96	0.01	0.01
L3	60	480	0.01	0.015
Total	75+2	600+16		



Phase noise of LLRF output: 34 fs



Amplitude: +/- 0.03% (peak-peak), 0.012% (rms)



Phase: +/- 0.04° (peak-peak), 0.016° (rms)



Outline


- Introduction of SHINE
- SHINE progress
- SRF R&D and prototypes Progress
- **Infrastructures progress**
- Summary

Infrastructures progress

Surface treatment platform




- ◆ **Main areas:** Clean rooms (ISO4-100m², IOS7-200m²), Chemistry area, waste dealing area and normal area.
- ◆ **Main equipment:** EP, BCP, Furnaces, HPR, Optical inspection device, Tuning machine etc.
- ◆ **Present status:** Start renovation on the existing building.



Construction of the CryoModule Workshop

- A 3000 m² cryomodule assembly and test workshop with an 1kW @ 2K cryogenic system is under construction at SSRF campus.

用户装置测试大厅
1st CryoModule Workshop




➤ Main capabilities

- Components inspection
- Cavity vertical test: 2 test stands
- Coupler conditioning and test
- Clean room assembly: cleanroom nearly ready, ISO 4> 200 m²
- Cold mass assembly
- SC magnet measurement
- CM assembly
- CM horizontal test: 2 CMs in one tunnel



CryoModule Assembly Workshop



Estimated Construction Cost

Total Construction Cost	~1.5B US\$
Central/Local Investment ratio	~20/80

Preliminary Construction Schedule

	2018	2019	2020	2021	2022	2023	2024	2025
Civil engineering	[Orange bar]							
Utilities		[Blue bar]						
R&D on key components	[Green bar]							
Mass production			[Cyan bar]					
Installations					[Purple bar]			
Commissioning						[Red bar]		

Groundbreaking was made in April, 2018, user experiments is expected to start in 2025.

Summary



- SHINE is a high rep-rate hard X-ray FEL facility, with an 8 GeV CW SCRF Linac, a 100PW laser system, 3 phase-I undulator lines and 10 end-stations, is going to be developed in Shanghai;
- This hard X-ray FEL project started its civil construction in April 2018, aiming to start user experiments in 2025.
- R&D and prototypes fabrication started from 2018, several TESLA type cavities (BCP treated) have been fabricated and vertical test; doping recipes are studied on both FG and LG material single cell cavities; one cryostat prototype fabricated; Solid-state power source and LLRF are in developing.
- Infrastructures, including a workshop and a surface treatment platform, are in construction



Thank You for Your Attention !